

Technical housing standards – nationally described space standard

Introduction

1. This standard deals with internal space within new dwellings and is suitable for application across all tenures. It sets out requirements for the Gross Internal (floor) Area of new dwellings at a defined level of occupancy as well as floor areas and dimensions for key parts of the home, notably bedrooms, storage and floor to ceiling height.
2. The requirements of this standard for bedrooms, storage and internal areas are relevant only in determining compliance with this standard in new dwellings and have no other statutory meaning or use.

Using the space standard

3. The standard Gross Internal Areas set out in Table 1 are organised by storey height to take account of the extra circulation space needed for stairs to upper floors, and deal separately with one storey dwellings (typically flats) and two and three storey dwellings (typically houses).
4. Individual dwelling types are expressed with reference to the number of bedrooms (denoted as 'b') and the number of bedspaces (or people) that can be accommodated within these bedrooms (denoted as 'p'). A three bedroom (3b) home with one double bedroom (providing two bed spaces) and two single bedrooms (each providing one bed space) is therefore described as 3b4p.
5. This allows for different combinations of single and double/twin bedrooms to be reflected in the minimum Gross Internal Area. The breakdown of the minimum Gross Internal Area therefore allows not only for the different combinations of bedroom size, but also for varying amounts of additional living, dining, kitchen and storage space; all of which are related to the potential occupancy.
6. Relating internal space to the number of bedspaces is a means of classification for assessment purposes only when designing new homes and seeking planning approval (if a local authority has adopted the space standard in its Local Plan). It does not imply actual occupancy, or define the minimum for any room in a dwelling to be used for a specific purpose other than in complying with this standard.
7. Minimum floor areas and room widths for bedrooms and minimum floor areas for storage are also an integral part of the space standard. They cannot be used in isolation from other parts of the design standard or removed from it.