

7. Footprint of buildings shown at 1.0m above ground level.

①	Parking (width or widening capability) (parking space capable of enlargement)	⑨	Potential for entrance level bed space (space on entrance level for temporary bed space)
②	Approach to dwelling from parking (distance to be as short as possible and level)	⑩	Entrance level WC and shower drainage (entrance level WC in accordance with Approved Doc M)
③	Approach to all entrances (approach to all entrance to be level / gently sloping)	⑪	WC and bathroom walls (walls capable of firm fixing and support of grab rails etc)
④	Entrances (all entrances to comply with Criterion 4 requirements)	⑫	Stairs and potential through floor lift (Note: platform lift can be provided)
⑤	Communal stairs and lifts (stairs in accordance with Criterion 5a requirements)	⑬	Potential for fitting of hoists (referring structure capable of supporting ceiling hoists)
⑥	Internal doorways and hallways (hallways and doorway widths suitable for convenient use)	⑭	Bathrooms (accessible bathroom layout in accordance with Criterion 6a)
⑦	Circulation space (space provided for turning a wheelchair in main living areas)	⑮	Glazing and window handle heights (at least one accessible opening light in each habitable room)
⑧	Entrance level living space (living space provided on entrance level)	⑯	Location of service controls (set 450mm - 1200mm from floor and 300mm away from corner)



print history: Thursday, 4 February, 2021 08:46:36