

NOTES
 1. The Contractor must check and confirm dimensions
 2. All dimensions must be reported and resolved by the
 Architect before works commence
 3. This drawing is not to be scaled
 4. All work and materials to be in accordance with current
 applicable Statutory Legislation and to comply with all relevant
 Codes of Practice and British Standards
 5. Level datum is 100m above ordnance datum to avoid
 confusion with previous survey

SOME FURTHER SIGNAGE MAY BE
 REQUIRED, BUT THIS CAN ONLY BE
 DETERMINED ON SITE

TO BE READ IN CONJUNCTION WITH M. & E.
 DRAWINGS AND THE A23 SERIES

NOTES

ALL FLOORS WITHIN THE BUILDING,
 CONSTRUCTED AS COMPARTMENT FLOOR:
 90 MINS.
 MEZZANINE FLOOR: 60 MINS.
 INTERMEDIATE FLOORS WITHIN THE DUPLEX
 APARTMENTS: 30 MINS

WALL BETWEEN INDIVIDUAL APARTMENTS
 AND BETWEEN APARTMENTS AND COMMON
 PART OF THE BUILDING: 90 MINS.
 WALL ENCLOSING ANY REFUSE STORAGE
 CHAMBERS: 90 MINS.
 WALL SEPARATING DIFFERENT PURPOSE
 GROUPS & OCCUPANCIES, (I.E. WALL
 SEPARATING RESIDENTIAL BUILDINGS FROM
 THE CAR PARK & SEPARATING THE
 RETAIL UNITS FROM THE RESIDENTIAL
 PART OF THE BUILDING: 90 MINS.
 STAIRCASES (FIRE-FIGHTING), STAIR, WELL,
 ELEVATOR, MEZZANINE, SMOKE SHAFTS,
 RISERS FOR SERVICES & ANY OTHER
 SHAFTS PENETRATING THE COMPARTMENT
 FLOOR: 90 MINS

FIRE FIGHTING CORE, STAIR SHAFT, LIFT
 SHAFT: 120 MINS.

TRANSFORMER ROOMS, SWITCH GEAR
 ROOMS, BOILER ROOMS, STORAGE SPACE
 FOR FUEL EXCEPT FOR T3 (TRANSFORMER
 ROOM) AND GENERATOR ROOM: 60 MINS.

ALL CORRIDOR WALLS IN THE INTERIOR OF
 THE FLATS, HOTEL ROOMS: 30 MINS

Fire Resistance Legend:
 - - - - - 30 Minutes
 - - - - - 60 Minutes
 - - - - - 90 Minutes
 - - - - - 120 Minutes
 - - - - - 240 Minutes

Fire Signage Legend:
 To be read in conjunction with Door Signage
 Schedule 3942/A_26_C01 & A_26_C02
 - - - - - Exit/ Running Man sign
 - - - - - Refer Fire Signage Schedule A26C02
 for directions

● Fire Lift Control Switch

To EXIT / RUNNING MAN / ARROW (TO THE LEFT)
 1b EXIT / RUNNING MAN / ARROW (TO THE RIGHT)
 1c EXIT / RUNNING MAN / ARROW (STRAIGHT ON)
 2a EXIT / RUNNING MAN / ARROW (TO THE LEFT)
 2c EXIT / RUNNING MAN / ARROW (TO THE RIGHT)
 2d EXIT / RUNNING MAN / ARROW (STRAIGHT ON)
 2e EXIT / RUNNING MAN / ARROW (UP & TO THE LEFT)
 2f EXIT / RUNNING MAN / ARROW (UP & TO THE RIGHT)
 2g EXIT / RUNNING MAN / ARROW (UP & TO THE LEFT)
 2h EXIT / RUNNING MAN / ARROW (UP & TO THE RIGHT)
 2i PRE LIFT CONTROL SWITCH
 2j PRE LIFT CONTROL SWIT

10 EMERGENCY EXIT SIGN WITH GREEN RUNNING MAN LEGEND

