

DDM 9/9 E6G2503 1F 4P 1V

Technical Data

	Speed control	Curves	Nominal motor power W	Poles	Phases	Connection	Mains frequency Hz	Max. power consumption W	Max. current consumption A	Speed 1/min
DDM 9/9 E6G2503										
1F 4P 1V	(2)	[K5/K6]	550	4	1~		50/60	1611	6,8	1400

Technical Data

	Operating Capacitor μ F	Nominal capacitor voltage V	Motor protection class	Motor thermal class	Thermal protection	Media Temperature max. $^{\circ}$ C	Fan weight kg	Density of media kg/m ³	Installation type (ISO 5801)	Article number
DDM 9/9 E6G2503										
1F 4P 1V	20	450	IP10	F	EXT	40	17	1.2	B	6M02R8

(1) = Speed controllable via Transformer
(2) = Speed controllable via TRIAC or Transformer
(3) = Speed controllable via Inverter
* = No speed control available
[H] High speed, [ME] Medium speed, [L] Low speed

Attention! We suggest to do not use the fan in the grey marked area! The noise ratings given in the performance curves are sound power level L_{WA7} , see „Technical Description“.

Curves

