C:\Users\MashI\OneDrive\Documents\Work\Projects\830 Uxbridge road UB4\Submission Planning\Document\PDF Images\GPID_1100687109_DOP_0e5aad46d.png

1. Unique identification code of the product-type	UK-WER-0205-02_english
2. Intended use of the construction product as foreseen by the manufacturer, in accordance with the applicable harmonised technical specification	Thermal insulation for buildings
3. Name, registered trade name or registered trade mark and contact address of the manufacturer, as required pursuant to Article 11(5) of regulation (EU) No 305/2011	ROCKWOOL® Limited Pencoed, Bridgend, CF35 6NY
4. Applicable System or Systems of Assessment and Verification of Constancy of Performance (AVCP)	SYSTEM 1 for uses subject to regulations on reaction to fire SYSTEM 3 for all other intended uses
5. Harmonised Standard reference number and date of issue	BS EN 13162:2012 +A1 2015 Issued on 28 February 2013
6. Notified Body identification number	0086
7. Declared Performances	Please refer to the table below (NPD – No Performance Determined)

Essential Characteristics	Requirement clauses in this European Standard	Level and/or classes	Declared value
Reaction to fire Euroclass characteristics	4.2.6 Reaction to fire	Euroclasses	A1
Release of dangerous substances to the indoor environment	4.3.13 Release of dangerous substances	–	NPD
Acoustic absorption index	4.3.11 Sound absorption	Declared p and w	NPD
Impact noise transmission index (for floors)	4.3.9 Dynamic stiffness	Declared s'	NPD
	4.3.10.2 Thickness, dL	Declared dL and T Class	NPD
	4.3.10.4 Compressibility c	Declared c and CP Level	NPD
	4.3.12 Air flow resistivity	Declared AFr	NPD
Direct airborne sound insulation index	4.3.12 Air flow resistivity	Declared AFr	NPD
Continuous glowing combustion	4.3.15 Continuous glowing combustion	–	NPD
Thermal resistance	4.2.1 Thermal resistance and thermal conductivity	Declared R6050 and/or 3050	λ(90/90) = 0.038 W/mK
	4.2.2 Length and width	Declared l and b	±3mm and ±5mm
	4.2.3 Thickness	Declared d or tolerance class T T4	
	4.2.4 Squareness	Declared Sb	±2.5 per 500mm
	4.2.5 Flatness	Declared Smax	±6mm
Water permeability	4.3.7.1 Short term water absorption	Declared W(P)	NPD
	4.3.7.2 Long term water absorption	Declared WL(P)	NPD
Water vapour permeability	4.3.8 Water vapour transmission	Declared or Z	MU1
Dimensional Stability	4.3.2 Dimensional Stability	Declared DS	
Compressive strength	4.3.3 Compressive stress or compressive strength	Declared CS Level	NPD
	4.3.5 Point load	Declared Fp	NPD
Durability of reaction to fire against heat, weathering, ageing/degradation	4.2.7 Durability characteristcsa)	b)	NPD
Durability of thermal resistance against heat, weathering, ageing/degradation	4.2.1 Thermal resistance and thermal conductivity	Declared R6050 and/or 3050 c)	NPD
	4.2.7 Durability characteristics	d)	NPD
Tensile/Flexural strength	4.3.4 Tensile strength perpendicular to faces e)	Declared TR Level	NPD
Durability of compressive strength against ageing/degradation	4.3.6 Compressive creep	Declared Xct and Xt	NPD

a) No change in reaction to fire properties for mineral wool products.
b) The fire performance of mineral wool does not deteriorate with time. The Euroclass classification of the product is related to the organic content, which cannot increase with time.
c) Thermal conductivity of mineral wool products does not change with time, experience has shown the fibre structure to be stable and the porosity contains no other gases than atmospheric air.
d) For dimensional stability thickness only.
e) This characteristic also covers handling and installation.

The performance of the product identified above is in conformity with the set of declared performances. This declaration of performance is issued, in accordance with Regulation (EU) No 305/2011, under the sole responsibility of the manufacturer identified above.

Signed for and on behalf of the manufacturer by:

Ian Kellie
Production Director

At Bridgend on 10th July 2019

C:\Users\MashI\OneDrive\Documents\Work\Projects\830 Uxbridge road UB4\Submission Planning\Document\PDF Images\GPID_1100687109_DOP_0a0e08191.png

JCW Absorbent Sound Screen

FITTED INTO TIMBER OR STEEL POSTS - SUITABLE FOR INDUSTRIAL AND COMMERCIAL ENCLOSURES (MAX HEIGHT 6M)





01 Capping Rail
02 Cover Strips
03 Boards
04 Gravel Board
05 Rail
06 Vertical Batons
07 Geotex
08 Absorber
09 Post
10 Site Fix Wedges (optional for steel post only)

Please Note

1. Structural calculations may be required by qualified persons, no responsibility can be accepted by using this design without professional advice. Maximum height of 6 metres.
2. Conforms and tested to BS EN 1793. Also tested and complies to BS EN 1794-1 and BS EN 1794-2.
3. Complies with Highways Sector Scheme 2C for the prefabrication of environmental barriers.
4. Design in accordance with specification for Highway Works Clause 2504. Treatment to Sector Scheme 4.
5. Height of sound screen variable to suit specific locations. Post centres at 2.4m or 3.0m unless otherwise specified.
6. Absorbent sound screens can also be fitted to timber posts as an alternative.

JCW Absorbent Sound Screen fitted into steel posts. BS EN 1793-1: 1998. Acoustics - Road traffic noise reducing devices. Test method for determining the acoustic performance.

Size: 12m2

Receiving Room

Volume: 220m2

Condition: Clean

Type: Large Reverberation Room

Location: Acoustic Transmission Suite

Sample Out:	Temperature: 20.1°C	Humidity: 48.5%
Sample In:	Temperature: 22.4°C	Humidity: 51.7%

DLα: 12

Category: A4

Frequency HZ	α
100	0.27
125	0.40
160	0.62
200	0.90
250	0.94
315	1.03
400	1.10
500	1.06
630	0.97
800	0.99
1000	1.00
1250	0.90
1600	0.89
2000	0.92
2500	0.90
3150	0.87
4000	0.92
5000	0.91



Test results for JCW Absorbent Sound Screen issued by:
University of Salford (Acoustics Test Laboratory)
UKAS accredited test laboratory No. 1262

Test reference number: AC09/215/15





Sound insulation to prevent any noise bleeding through to the HMO above

JCW Acoustic barrier between the parking and Shisha terrace

100mm Acoustic Mineral Wool added between the timber battens. This absorbs airborne sound in the cavity partitions of timber joists, significantly improving acoustic performance and reducing reverberation

ReductoClips - able to withstand greater loads than standard clip systems, resulting in 1 /3 less clips and a more cost effective system

Reducto Furring Bar which outperforms standard resilient bar constructions by up to 7dB

Acoustic grade plasterboard (15mm) - 50% denser than standard 12.5mm plasterboard. With a mass of 12.6kg per m2 which reflects and converts high levels of sound energy into heat

Tecsound SY 100 (self-adhesive) a specially developed thin 10kg per m2 soundproofing material

Acoustic grade (15mm) plasterboard - a further layer to increase airborne noise blocking capabilities