



- 1) Slate Chips
- 2) Concrete Path Edgings
- 3) Permeable Paving Slabs
Grey Charcon non slip
- 4) Cycle Shelter for 10 Bikes
by Cycle Hoop
- 5) Eurobins 1280 litre
- 6) Eurobin Store by Bike Shed Co
- 7) 150mm Concrete, Float Finish
- 8) 900mm ht one Brick Wall in
Ibstock Class B Blue Engineering Bricks
- 9) Wood Chip Mulch 100mm deep
- 10) Lucerne Loli Bollard Light
- 11) Charcon Infilla Block Pavours

SPECIES	HEIGHT/ FORM	POT SIZE/ GIRTH	
T1 - English Yew <i>Taxus baccata</i> (To be planted at Rear boundary @ 2 metre c/s)	1.0 - 1.75m	12-14cm	Bare Root
12- <i>Magnolia grandiflora</i>	1.5 - 2m	7.5-10cm	12 litre Pot
13- <i>Californian Lilac tree</i> <i>Ceanothus 'Twilwiten Blue'</i> Tree	120 - 150cm	Multi Stem	10L pot
T4 - Japanese Maple <i>'Acer Palmatum Dissectum Atropurpureum'</i>	110 - 130	10cm	15 litre Pot
Hedging			
H1 - Oak Leaved Privet <i>Ligustrum Ovalifolium</i>	30cm	80 - 100	Bare Root
Shrub Planting			
SPECIES	HEIGHT/ FORM	POT SIZE/DENSITY/ GIRTH	M2
From:			
S1 - Forsythia - <i>Suspensa Atrocailis</i>	30 - 40	3L	2.5 - 3
S2 - <i>Hibiscus - Syriacus</i>	30 - 40	3L	2.5 - 3
S3 - <i>Viburnum - Trinus</i>	30 - 40	3L	2.5 - 3
S4 - <i>Hydrangea - Macrophylla</i>	30 - 40	3L	2.5 - 3
S5 - <i>Lilac - Syringa</i>	30 - 40	3L	2.5 - 3
S6 - <i>Weigela - Florida</i>	30 - 40	3L	2.5 - 3

Shrub Planting

PLANT MATERIAL

All goods and materials used in the execution of this project shall be produced, so far as is practicable, in the United Kingdom or other member countries of the EEC. Goods and materials not complying with this criterion shall have the approval of the Supervising Officer prior to their use.

All goods, material and workmanship shall comply with British Standards as a minimum required where an applicable standard or code exists.

Plants shall be of the same size specified in the schedule. They shall be strong sturdy plants furnished with good root systems and obtained from a reputable supplier. Plants shall be in good health, free from pests, diseases and damage. All stock must comply in all respects with BS 3396 (Parts 1, 2, 3, 4 & 10).

Plants not covered by BS 3396 shall be:

- sturdy, healthy, of good shape and without elongated shoots;
- free from pests, disease and damage;
- with balanced root and branch systems; and abundant fibrous roots;
- of vigorous growth during season prior to lifting.

All plants shall be labelled according to species and variety.

HANDLING OF PLANT MATERIAL

The shrubs must not be subjected to adverse conditions such as frost, wind or overheating in polythene bags at any time between lifting from the nursery and planting on site. Plant roots shall be kept moist from the time of lifting to the time of planting.

All plants shall be adequately and carefully packed and protected to survive transport to the site without damage in loading, transit or unloading.

The Contractor shall ensure that the plants are unpacked and heeled in or planted on the same day as delivery, that they are protected on site before planting and that they have not been allowed to over heat in transit.

Pots and other protective materials shall not be removed until immediately before planting.

The collection, loading and unloading of materials and plants shall be the sole responsibility of the Contractor and shall be allowed for in his rates.

23 Little Common, Stanmore, HA7 3BZ
Tel: +44 (0)208 416 3913
www.designedimages.co.uk