

Our Ref: JLR/21168

10 December 2015

By e-mail only

RE: Enterprise House, Hayes

Proposed Installation Procedure for Walkway Platforms

1. Construct temporary access platforms. Scaffold to bear on existing reinforced concrete roof at 1st floor level. Scaffold to include block and tackle hoist arrangement to lift beam and balcony components from ground level through openings in existing roof lights. Note existing roof lights require repair and restoration works and opening of these roof lights are required as part of the works to Enterprise House.
2. Set out and install PFC support brackets at all building connection points.
3. Deliver to site, piece together, lift, position and fix the main truss to support brackets.
4. Tension Macalloy truss members.
5. Fix primary beams to existing support brackets and to main truss and install diagonal braces.
6. Connect secondary beams, install remaining diagonal braces and install steel deck walkway.
7. Remove any required temporary props.
8. Install remaining finishes, handrails etc.
9. Remove access platforms and scaffold.
10. Repeat above steps 2-9 in appropriate construction sequence for all walkways at all levels, working down each lightwell.

Yours sincerely

Sam Saunders
For and on behalf of Hurst Peirce + Malcolm LLP
ssaunders@hurstpm.co.uk



CELTIC HOUSE
33 JOHN'S MEWS
HOLBORN
LONDON WC1N 2QL
TEL: 020 7242 3593
FAX: 020 7405 5274
E-mail:
enquiries@hurstpm.co.uk
Web Page:
www.hurstpm.co.uk

PARTNERSHIP

JOHN L. REDMOND
*B.Sc., C.ENG., M.I.C.E.,
M.I.STRUCT.E., F.CON.S.E.*

A. PHILIP HURST
*B.Sc., C.ENG., M.I.C.E.,
M.I.STRUCT.E., F.CON.S.E.*

D. MICHAEL CHUNG
*M.A.(CANTAB), C.ENG.,
M.I.C.E., M.I.STRUCT.E.*

CONSULTANTS

B. LAWRENCE HURST
*B.Sc., F.C.G.I., C.ENG., F.I.C.E.,
F.I.STRUCT.E., F.B.ENG.*

ANDREW H. DUTTON
*M.A.(CANTAB), C.ENG.,
F.I.C.E., F.I.STRUCT.E.,
F.CON.S.E.*

C.F. BOWDEN
B.Sc., C.ENG., M.I.C.E.

B.N. PAINE

SENIOR ASSOCIATES

J. PITCHER
B.ENG.
N. BRAY
BSC., CENG., MICE, M.I.STRUCT.E.
N. MASUED, *BSC. (HONS), MSC.,
D.I.C., C.ENG., M.I.STRUCT.E.*

ASSOCIATES

J. A. BOORMAN
I.ENG., A.M.I.STRUCT.E.

HURST PEIRCE + MALCOLM LLP
(REG No OC307252)
IS REGISTERED IN ENGLAND
AND WALES
REGISTERED OFFICE
CELTIC HOUSE, 33 JOHN'S
MEWS, LONDON WC1N 2QL