



1. BRICK



The Terca Hathaway Brindled



Brick, manufactured by Wienerberger, is a thrown / stock / soft mud brick that is red in colour with a light texture.

As a facing brick, the Terca Hathaway Brindled brick is commonly chosen for its aesthetic qualities, and will provide a red, light textured façade.

Name	Terca Hathaway Brindled
SKU	BH00985
Manufacturer	Wienerberger
Brand	Terca
Type	Facing Brick
Colour	Red
Material	Clay
Texture	Light
Manufacturing Process	Thrown / Stock / Soft Mud
Production Status	In Production
Samples Available	Yes

2. ROOF TILES



Redland Rosemary Classic Machine Made Clay Plain Roof Tile

The Rosemary name is synonymous with clay plain tiles, adding distinction and character to pitched roofs for over 175 years.

The Redland Rosemary Clay Plain Tile range includes both of single and cross-cambered tiles combining the quality of hand-crafted clay with the reliability of modern machine-made techniques.

Weight

Laid Weight: 78 kg/m² below 90 degrees / 68 kg/m² at 90 degrees
Weight per 1000 Tiles: 1.30 tonnes
Weight per Pallet: 1.11 tonnes

Minimum Roof Pitch & Headlap

Minimum Pitch: 35 degrees
Maximum Pitch: 90 degrees subject to fixing specification
Minimum Headlap: 65 mm below 90 degrees / 35mm at 90 degrees
Maximum Headlap: 88 mm
Minimum Gauge: 88 mm

Coverage

Linear Cover of 1 Tile: 165 mm
Covering Capacity: 60 tiles/m² below 90 degrees / 52 tiles/m² at 90 degrees
Hanging Length: 255 mm approx

Batten

Battens Required: 10 linear m/m² below 90 degrees / 8.7 m/m² at 90 degrees
Batten Size: 38 x 25 mm - rafter centres up to 600 mm

Tile Size

265 mm x 165 mm