

Site Information	
Site Name	25 The Avenue
Reg Number	
Street 1	25 The Avenue
Street 2	
Area	
Town or City	NORTHWOOD
Post Code	HA6 2NJ

Installation Type	Average Capacity/Flow Rate	Litres/Person/Day
Single Flush WC's	0	0
Dual Flush WC's	3.99	17.64
All WC's	3.99	17.64
Kitchen/Utility Room Taps	7	13.44
Other Taps	6	12.64
Baths	130	14.3
Showers	9.52	41.62
Dishwashers	0.59	2.12
Washing Machines	5.9	12.39
Water Softener		
Waste Disposal Unit	Not Present	0
Total Water Use	114.15 Litres/Person/Day	
Contribution from Rain Water	0 Litres/Person/Day	
Contribution from Grey Water	0 Litres/Person/Day	
Normalisation Factor	0.91 Litres/Person/Day	

Code for Sustainable Homes - Consumptions & Credits	
Water Consumption (Code for Sustainable Homes)	103.9 Litres/Person/Day
Credits Scored	3

Building Regulations 2000 AD Part G (2010 Ed) - Consumption	
External Water Use	5 Litres/Person/Day
Water Consumption (Building Regulation 17 K)	108.9 Litres/Person/Day

Kitchen/Utility Room Taps						
Description	Flow Rate	Qty	Total Water	Grey Water	Rain Water	Net Water
Qooker Fusion 7 l/min	7	1	7	0	0	7
Total Litres/Person/Day Gross						13.44
Total Litres/Person/Day Gross						13.44

Other Taps						
Description	Flow Rate	Qty	Total Water	Grey Water	Rain Water	Net Water
Cloak room tap 10 l/min	10	1	10	0	0	10
Basin tap 5 l/min	5	4	20	0	0	20
Total Litres/Person/Day Gross						12.64
Total Litres/Person/Day Gross						12.64

Baths						
Description	Capacity	Qty	Total Water	Grey Water	Rain Water	Net Water
UBA170LFS2V	130	1	130	0	0	130
Total Litres/Person/Day Gross						14.3
Total Litres/Person/Day Gross						14.3

Showers						
Description	Flow Rate	Qty	Total Water	Grey Water	Rain Water	Net Water
Shower 8.7 l/min	8.7	3	26.1	0	0	26.1
Shower 16 l/min	12	1	12	0	0	12
Total Litres/Person/Day Gross						41.62
Total Litres/Person/Day Gross						41.62

Washing Machines						
Description	L/Kg Dry Load	Qty	Total Water	Grey Water	Rain Water	Net Water
Siemens WM14NK08GB	5.9	1	5.9			5.9
Total Litres/Person/Day Gross						12.39
Total Litres/Person/Day Gross						12.39

Dishwashers						
Description	L/Place Setting	Qty	Total Water	Grey Water	Rain Water	Net Water
Siemens SN95ZX61CG	0.59	1	0.59	0	0	0.59
Total Litres/Person/Day Gross						2.12
Total Litres/Person/Day Gross						2.12

Single Flush WC's						
Description	Flush Volume	Qty	Total Water	Grey Water	Rain Water	Net Water
Total Litres/Person/Day Gross						0
Total Litres/Person/Day Gross						0

Dual Flush WC's						
Description	Flush Vol (P/F)	Qty	Total Water	Grey Water	Rain Water	Net Water
3/6 dual flush toilet	3/6	5	19.95			0
Total Litres/Person/Day Gross						17.64
Total Litres/Person/Day Gross						17.64

Ion Exchange Water Softener	
% of Total Capacity Used Per	
Water Consumed Per Regeneration	
Average Regeneration Cycles Per Day	
Occupants Served by the System	
Water Consumed Beyond 4%	
Water Consumed Beyond 4%	

Rain Water Collection	
Collection Area	
Yield Co-Efficient	
Hydraulic Filter Efficiency	
Average Rainfall	
Daily Rain Water Collection	
Number of Occupants	
Daily Rain Water Per Person	