

Q52

Play and sports equipment

Q52 Play and sports equipment

GENERAL

- 115A PLAYGROUND(Block D)
- Equipment: As drawing FNF-L-SITE-CAM-DR-90-904.
 - System supplier: Timberplay Ltd
Aizlewoods Mill, Nursery Street, Sheffield, S3 8GG
Tel: 0114 282 1284 Mobile: 07787 412973 Fax: 0114 282 3463
Contact: Michelle Ruthier Michelle@timberplay.com.
 - Surfacing: play sand.
 - Containment: Not required.
- 115B PLAYGROUND (Wallis Gardens)
- Equipment: As drawing FNF-L-SITE-CAM-DR-90-907.
 - System supplier: Timberplay Ltd
Aizlewoods Mill, Nursery Street, Sheffield, S3 8GG
Tel: 0114 282 1284 Mobile: 07787 412973 Fax: 0114 282 3463
Contact: Michelle Ruthier Michelle@timberplay.com.
 - Surfacing: play sand.
 - Containment: Not required.
- 115C PLAYGROUND(Sadow Square)
- Equipment: As drawing FNF-L-SITE-CAM-DR-90-906.
 - System supplier: Timberplay Ltd
Aizlewoods Mill, Nursery Street, Sheffield, S3 8GG
Tel: 0114 282 1284 Mobile: 07787 412973 Fax: 0114 282 3463
Contact: Michelle Ruthier Michelle@timberplay.com.
 - Surfacing: Paving as per the hadworks drawing FNF-L-PH1-CAM-DR-90-201.
 - Containment: Not required.
- 165A TRIM TRAIL (Block D)
- Equipment: As drawing FNF-L-SITE-CAM-DR-90-904.
 - System manufacturer: Leisure Logs or similar approved
North Hill, Chorley Wood, Hertfordshire, WD3 6HA
info@leisurelogs.co.uk
t: 01923284760.
 - Surfacing: PT9 refer to clause Q23/225B.
 - Containment: Not required.
- 165B TRIM TRAIL (Wallis Gardens)
- Equipment: As drawing FNF-L-SITE-CAM-DR-90-907.
 - System manufacturer: Leisure Logs or similar approved
North Hill, Chorley Wood, Hertfordshire, WD3 6HA
info@leisurelogs.co.uk
t: 01923284760.
 - Surfacing: PT11 refer to clause Q23/110A.
 - Containment: Not required.

165C TRIM TRAIL (Sandow Square)

- Equipment: As drawing FNF-L-SITE-CAM-DR-90-906.
 - System manufacturer: Leisure Logs or similar approved
North Hill, Chorley Wood, Hertfordshire, WD3 6HA
info@leisurelogs.co.uk
t: 01923284760.
- Surfacing: PT9 refer to clause Q23/225B.
- Containment: Not required.

PRODUCTS

319 PLAY EQUIPMENT

- Supplier: Timberplay Ltd
Aizlewoods Mill, Nursery Street, Sheffield, S3 8GG
Tel: 0114 282 1284 Mobile: 07787 412973 Fax: 0114 282 3463
Contact: Michelle Ruther Michelle@timberplay.com
- Product list:
 - Small platform hut with roof, 2 walls, 2 benches, 1 table (3.14350)
 - Inclined climbing net to huts (3.69124)
 - Small children's slide (3.19210)
 - Rigid bridge with chain handrails (3.66320 (ff))
 - End frame (3.66386)
 - Caterpillar type 04 (5.00025)
 - Straight ballancing beam (6.81000)
 - Pairs (9.15200)
 - Trunk logs (4.24200)
 - Phones in concrete (9.02710)
 - Marbles table (11.01500)
 - Caterpillar type 02 (5.00015)
 - Small see-saw (6.11700)
 - Trunk logs (4.24200)
 - Climbing structure 09 (6.51009)
 - Jackstraws see-saw (6.50600)
 - Cradle nest (6.14500)
 - Sea Roarer (9.02650)
 - Piper (9.02660)
 - Hexagonal Rocking Plate (6.31000)
 - Table Tennis (7.89000)
 - Street Musicians (9.10010)
 - Dance chimes (9.06000)
 - Ferraphone (9.07000)
 - Tree trunk - tree felled on site
- For numbers and locations refer to drawings: FNF-L-SITE-CAM-DR-90-904, FNF-L-SITE-CAM-DR-90-907, FNF-L-SITE-CAM-DR-90-906
- For technical details refer to Appendix A

560A EXERCISE EQUIPMENT

- Manufacturer: Leisure Logs or similar approved
North Hill, Chorley Wood, Hertfordshire, WD3 6HA
info@leisurelogs.co.uk
t: 01923284760.
- Product list:
 - Step ups
 - Press up bar
 - Warm up bench
 - Vertical leg rise
 - Single bar chin up
 - Sit up bench
 - Parallel bars
 - 2.4m Chin Ups
- Materials: Wood and steel.
- Method of fixing: to manufacturer's recommendation.
- For numbers and locations refer to drawings: FNF-L-SITE-CAM-DR-90-904, FNF-L-SITE-CAM-DR-90-907, FNF-L-SITE-CAM-DR-90-906

EXECUTION**710 PLAY EQUIPMENT INSTALLATION GENERALLY**

- Standard: To manufacturer's written instructions provided in accordance with BS EN 1176-1.

720 CONCRETE FOUNDATIONS GENERALLY

- Standard: To BS 8500-2.
- Concrete: Designated, not less than GEN 1 or Standard prescribed, not less than ST2.
- Admixtures: Do not use.
- Foundation holes: Neat vertical sides.
- Depth of foundations, bedding, haunching: Appropriate to provide adequate support and to receive overlying soft landscape or paving finishes.

725 SETTING COMPONENTS IN CONCRETE

- Holes: to match required foundation sizes.
- Components: Accurately positioned and securely supported.
- Concrete fill: Fully compacted as filling proceeds.
- Concrete foundations exposed to view: Finished to weathering profile to shed water and trowel smooth.
- Temporary component support: Maintain undisturbed for minimum 48 hours.

740 PRESERVATIVE TREATED TIMBER

- Surfaces exposed by minor cutting and drilling: Treated by immersion or with two flood

750 DAMAGE TO GALVANIZED SURFACES

- Minor damage in areas up to 40 mm² (including on fixings and fittings): Make good.
 - Materials: Low melting point zinc alloy repair rods or powders made for this purpose or at least two coats of zinc-rich paint to BS 4652.
 - Thickness: Sufficient to provide a zinc coating at least equal to the original layer.

COMPLETION

- 910 **INSPECTION**
 - Standard: In accordance with equipment manufacturer's maintenance and inspection instructions.
 - Timing: 2 weeks after request by contract administrator.
 - Period of notice (minimum): 3 working days.

- 920 **CLEANING**
 - General: Leave the works in a clean, tidy condition.
 - Surfaces: Clean immediately before handover.

- 930 **TESTING**
 - Standard: To BS EN 1176-1.

- 940 **LABELS**
 - Standard: To BS EN 1176-1.
 - Labels: Provide permanent labelling on all types of play equipment.
 - Location: Where visible when erected on site.

- 950 **DOCUMENTATION**
 - Standard: To BS EN 1176-1.
 - Contents:
 - Copies of test reports.
 - General product information.
 - Installation information.
 - Inspection and maintenance information.
 - Number of copies: 3.
 - Submission: 2 weeks prior to date when work is expected to be practically complete.

- 970 **OPERATING TOOLS**
 - Tools: Supply tools required for operation, maintenance and cleaning purposes.