



The Europa multi-service bollard offers a complete 'All-in-One' solution. Capable of supplying up to 4 pitches with either 16A or 32A outlets. Each socket outlet is wired with a tripping module and microswitch creating a safe electronic interlock.

Manufactured from high-density polyethylene and acrylic capped ABS, the Europa range is designed to withstand a multitude of weather conditions and provide a superior finish. This bollard is complete with combined overload and earth leakage protection devices which are safely accessible using the polycarbonate reset flaps.

Built with flexibility in mind, our 'Optional Extras' allows us to tailor the bollards to suit your needs.



Features

- Available in 16A or 32A
- 1, 2, 3 or 4 Socket Outlets
- MID Approved Meters (various metering solutions are available)
- HDPE Internal Chassis
- LED Lighting Head (photocell controlled)
- Range of Colours & Materials
- Combined Overload & Earth Leakage Protection 30mA 2 Pole
- Incoming Terminals: 2 x 35mm
- 2 x 25mm + 1 x 20mm Brass Gland Plate (other sizes available)
- 2 Pole Isolator
- Electronic Interlock
- 2P+E Socket Outlets: IP44
- Acrylic Capped ABS Shell: IP65
- Polycarbonate Reset Flap: IP67
- Fire Retardant
- BS7671 Compliant

Optional Extras

- Water: 15mm Incoming Connection
- Double Check Valve
- Isolation Valve
- ½" Brass Bib Tap
- Self Regulating Trace Heating
- TV & Data Outlet
- Integrated EV Charger
- Galvanised Root Mounting Kit



Colour Options

