

# Waterproof Buttons



**WP-EBGBWC02/PTE**



**WP-EBGBWC02/PTO**

## SPECIFICATION

- Contacts: Double pole N/O - N/C
- Output: 4 AMP contact @ 30V AC/DC
- Wear resistant legend
- External use
- Rated IP66 ingress protection
- Silver contacts
- Operating temperature -20° to +60°C
- Operating travel: 2mm
- Contact resistance: 10m OHM (Max)
- Operating life (mechanical): 1,000,000

## FEATURES

- Green dome button
- Momentary operation / contact
- High impact plastic back box
- Surface fitting
- Easy clean surface
- Ideal for general / sensitive areas
- Gasket and gland included
- Screw footprint for flush fitting onto standard back box
- Distance between fixing holes 60mm
- Anti rotational mounting

## DIMENSIONS

- 85H x 85W x 40/50D (mm)
- 248g (Boxed)
- 200g (Unboxed)

## CONTENTS

- Green Dome Exit Button
- Stainless Steel Plate (2mm)
- 2 Security Screws
- Allen Key
- Surface Box
- Gland
- Gasket