



#### BS 5837:2012 TREE RETENTION CATEGORIES

The original of this drawing was produced in colour - a monochrome copy should not be relied upon.

- Canopy spread (m)
- Tree Stem
- Root Protection Area (RPA)
- Group canopy extents shown in their retrospective retention category.
- Unique group identification number
- Root Protection Area (RPA)
- Category A
- Trees and groups of high quality with an estimated remaining life expectancy of at least 40 years.
- Category B
- Trees and groups of moderate quality with an estimated remaining life expectancy of at least 20 years.
- Category C
- Trees and groups of low quality with an estimated remaining life expectancy of at least 10 years or young trees with a stem diameter below 150mm.
- Category U
- Those in such a condition that the tree cannot realistically be retained as living trees in the context of the current land use for longer than 10 years.
- BS5837 Root Protection Areas
- Precautionary areas within which tree roots and soil structure must be protected. All works within these areas will require special methods of work.
- T33
- The RPAs of affected trees and tree groups have been amended, due to the presence of adjacent influencing factors (e.g., buried structures).
- Application Site boundary
- Trees and groups to be removed shown shaded grey and dashed. Tree tags are shown red.
- Trees to be pruned back shown shaded orange. Please refer to tree works schedule for exact extents.

#### SCHEDULE OF IMPACT:

- TREES LARGELY RETAINED ON THE SITE
- T5 REMOVED
- S12 REMOVED
- S13 REMOVED
- S35 PARTIALLY REMOVED
- H34 REMOVED