



Handrails to match existing in size painted black.

Infill bars to be either 12mm or 16mm solid square bar

50x50x3SHS steel box frame to match existing painted green

Posts core drilled with 70mm core into new brickwork

Handrail set at 600mm from pitch

Handrail set at 1000mm from pitch

REV MARK	DESCRIPTION	By CREATED	Date	By CHECKED	Date
Hillingdon Civic Centre					
DRAWING TITLE	3D VIEW Of Typical handrail detail				
CONTRACT	Hillingdon Civic Centre				
MODELLLED BY	RF			ISSUE DATE	
CONTRACT NO	1652			SCALE	1:10
DRAWING No	G [1]			REVISION No.	

ASAP Steel Fabrications LTD
Unit 1B
Nup End Business Centre
Hertfordshire
SG360J