

Materials and Construction Specification

1. Sub-base and Bedding Materials

- The works shall include the use of **MOT Type 1 sub-base** as the foundational structural layer.
- **Sharp sand** shall be provided for the bedding layer.
- **Kiln-dried sand** shall be used for jointing the block paving.

2. Edging Blocks Installation

- Edging blocks are to be set in **C20 concrete mix (minimum)** to provide adequate restraint and maintain the integrity of the paved area.

3. Weed Control Membrane

- A **weed control membrane** shall be installed beneath the bedding layer to prevent weed growth through the paved surface.

4. Block Paving

- **Permeable block paving** shall be installed to match the finish, colour, and appearance of the existing driveway.
- The paving must ensure both aesthetic consistency and functional permeability.