



Declaration of Performance

in accordance with Construction Products Regulation no. 305/2011
of 9th March 2011, article 6

No. 2013-SDG1-1-A-3182

1. Product type:

PREFA Siding (SDG)

2. Intended use as foreseen by the manufacturer:

Wall cladding elements

3. Name and address of manufacturer as required pursuant to article 11, paragraph 5:

PREFA Aluminiumprodukte GmbH, Werkstraße 1, 3182 Marktl, Austria

4. System for the assessment and verification of the constancy of performance of the construction product as set out in annex V:

System 4

5. The source reference and date of issue of the harmonised standard used for the assessment of each individual characteristic of the construction product was:

EN 14782, January 2006 - Self-supporting metal sheet for roofing, external cladding and internal lining - Product specification and requirements

6. Declared performance

Essential Characteristics	Performance	Harmonized technical specification
Water permeability	The cladding element has no holes.	EN 14782
Dimensional Change	$24 \times 10^{-6} \text{ K}^{-1}$	EN 14782
Water vapour and air permeability	The cladding element has no holes.	EN 14782
Release of dangerous substances		EN 14782
External fire performance	Compliant without further testing	EN 14782
Reaction of fire	Class A1	EN 14782
Durability	Various coatings $> 20 \mu\text{m} < 40 \mu\text{m}$	EN 14782

7. The performance of the product described in point 1 complies with the declared performance in point 6.

This declaration of performance is issued under the sole responsibility of the manufacturer identified in point 3.

Signed for and on behalf of the manufacturer by:

Ing. Edwin Kroisenbrunner (Production Manager)

Name and position

Marktl, 1.7.2013

Place and date of issue



Signature