Brick private driveway surface

Existing retained mature laurel hedge at boundary of driveway

Proposed evergreen hedge clipped & maintained at @ 3.0m

Bin Area with Green Roof

Proposed Cherry Tree

Proposed replacement boundary fence system of 1.8m treated timber closeboard

Mixed shrub planting and flowers with architectural / clipped specimens

Proposed replacement boundary fence system of 1.8m treated timber closeboard

Proposed Natural Stone with permeable surface and Material

Proposed Natural Stone Paving

Proposed Large Planters [pair] at entrance with architectural / clipped planting

Mixed shrub planting with architectural / clipped specimens

43

Proposed replacement boundary fence system of 1.8m treated timber closeboard

Outline of existing house

Proposed Natural Stone Paving

Proposed replacement boundary fence system of 1.8m treated timber closeboard

Proposed Large Planters [pair] at rear entrance with architectural / clipped planting

Proposed Decking

Existing / Retained / Rejuvenated garden lawn with existing garden features and pathways retained

Existing / Retained boundary mature shrub / hedge planting

Proposed Garden Open Seating area

Proposed PlumTree

Mixed shrub planting and flowers with architectural / clipped specimens

Existing / Retained boundary mature shrub / hedge planting

Proposed Apple Tree

Shed

Existing / Retained / Rejuvenated orchard tree planting to be pruned to shape for future health of mature orchard stock

Scale Bar 1:100

Drawing: **Proposed Site Plan**

HOMECRAFT GLOBAL LTD

Client: **47 Sweetcraft Lane, UB10**

3 Pennine Parade ,Pennine Drive London ,NW2 1NT
Mobile: 07801 445580
Email: info@homecraftglobal.com

Note: All dimensions to be checked on site Disclaimer: Floor Plan measurements are approximate and are for illustrative purposes only. You or your advisors should conduct a careful, independent investigation of the property to determine to your satisfaction as to the suitability of the property for your space requirements

Scale@A0,**1:100**

Drawing Date : 08.2026

Drawing Number : A2647/10/PR/STPL