

Hi [REDACTED]

Thank you, we are happy to now approve with the following standard conditions:

Prior to commencement (except for demolition, ground and enabling work) any relevant phase of this development (excluding demolition and site clearance), a scheme for the provision of sustainable water management shall be submitted to, and approved in writing by the Local Planning Authority in consultation with the relevant stakeholders. The scheme shall clearly demonstrate how it manages water and demonstrate ways of controlling the surface water on site by providing information on:

a) Sustainable Drainage features:

- i. Surface water discharge - the submitted drainage strategy must identify the proposed method and location of discharging collected surface water from the site in accordance with the hierarchy set out in Policy SI 13 of the London Plan (2021). Where the proposal does not utilise the most sustainable solution, justification must be provided.
- ii. SuDS - the submitted drainage strategy should incorporate Sustainable Drainage System (SuDS) elements that are embedded, where practicable, within the landscaping plan for the development. Preference should be given to above-ground SuDS elements that control water at source and provide wider biodiversity, water quality and amenity benefits.

iii. Runoff rates - provide the greenfield and proposed runoff rates for a variety of return periods including 1 in 1 year, 1 in 30, 1 in 100, and 1 in 100 plus 40% climate change. Developments should aim to meet greenfield runoff rates unless a suitable justification can be provided.

iv. Drainage calculations - include calculations to demonstrate that the volume of storage and size of drainage features provided is adequate to control surface water for a range of storm duration and rainfall intensities for the entire site area for events up to and including the critical 1 in 100 plus 40% climate change rainfall event.

v. Exceedance routes - provide a plan showing the route surface water will take through the development for rainfall events exceeding the 1 in 100 year event. Where it is intended to store water on the ground surface, the maximum extent of overland flooding should be mapped and the depth of the flooding confirmed. Safe access and egress for the site must be demonstrated.

b) Long-term management and maintenance of the drainage system.

- i. Provide a Management and Maintenance Plan for the drainage system that includes clear plans showing all of the drainage network above and below ground, and identifies the responsibility of different parties for each component of the drainage network.
- ii. Include details of the necessary inspection regimes and maintenance frequencies.

Thereafter the development shall be implemented and retained/maintained in accordance with these details for as long as the development remains in existence.

Reason: To ensure that surface water run off is controlled and to ensure the development does not increase flood risk, in compliance with Policy EM6 of the Hillingdon Local Plan: Part 1 (2012), Policy DMEI 9 and DMEI 10 of the Hillingdon Local Plan Part 2 (2020), Policies SI 12 and SI 13 of the London Plan (2021), the National Planning Policy Framework (2021); and Planning Practice Guidance (Flood Risk and Coastal Change March 2014).

No building hereby permitted shall be occupied until evidence (photographs and installation contracts) is submitted to demonstrate that the sustainable drainage scheme for the site has been completed in accordance with the submitted details. The sustainable drainage scheme shall be managed and maintained thereafter in accordance with the agreed management and maintenance plan for all of the proposed drainage components.

Reason: To comply with the National Standards for Sustainable Drainage Systems, the National Planning Policy Framework (Paragraph 103), the London Plan (Policies SI 12 and SI 13) along with associated guidance to these policies and Hillingdon Council's Local Plan Policy EM6.

Best wishes,