

Job Title: PR Architecture Ltd Ref: 11 Sandy Lodge Way, Northwood, HA6 2AH

Job Number: 2286

Luminaire Ref: Outdoor Bollard 400mm 9w 3000K 420lm IP65

General Description:

LED Outdoor Bollard Lights are stylish, hardwearing and weather-proof. These free-standing luminaires are an attractive way to light walkways and driveways in residential and commercial premises.

Stylish and contemporary design

Hard-wearing and weatherproof

Die cast aluminium body with powder coated finish

Material: Die cast aluminium body with powder coated finish

Lumens: 420lm Lumens per Watt: 47.0lm/W

Correlated Colour Temperature (CCT): 3000k Warm White

Colour Rendering Index (CRI): ≥ 80

LED Type: Surface mounted device (SMD)

Instant on - Less than 1 second: Yes

Lifetime: 25,000 hrs

General Appearance:



400mm Height

Luminaire:

Manufacturer	Integral	Type	LED
Location	Car Park & Rear	Wattage	9w
Finish	Black	Lumens	420lm
Type	Post Light	Lens	

Additional Information:

Job Title: PR Architecture Ltd Ref: 11 Sandy Lodge Way, Northwood, HA6 2AH

Job Number: 2286

Luminaire Ref: Outdoor Curve Wall Light 8W 3000K 360lm IP54 with Integrated PIR sensor

General Description:

Weatherproof and hard-wearing, this range is designed to last against the elements while bringing a designer look to your surroundings.

Sleek and sophisticated, the Curve wall light is the ideal accessory to light up your outdoor space. This product includes a PIR sensor to automatically switch on as people walk past, ideal for safety and security.

Material: Die cast aluminium body with powder coated finish

Length: 275mm Width: 117mm Depth: 112.00mm

Lumens: 360lm Lumens per Watt: 45.0lm/W

Correlated Colour Temperature (CCT): 3000k Warm white

Colour Rendering Index (CRI): ≥ 80

Instant on - Less than 1 second: Yes

Lifetime: 25,000 hrs

General Appearance:



Luminaire:

Manufacturer	Integral	Type	LED
Location	Perimeter of building	Wattage	8w
Finish	Black	Lumens	360lm
Type	Wall Mount w/PIR	Lens	

Additional Information:

Job Title: PR Architecture Ltd Ref: 11 Sandy Lodge Way, Northwood, HA6 2AH

Job Number: 2286

Luminaire Ref: Outdoor Recessed Brick Light 3.8W 3000K 180lm IP65

General Description:

Optic: Opal Polycarbonate diffuser
Material: Aluminium body, stainless steel covers
Length: 205mm Width: 95mm Depth: 65.00mm
Recessed fitting
Lumens: 180lm Lumens per Watt: 47.0lm/W
Correlated Colour Temperature (CCT): 3000k Warm White
Colour Rendering Index (CRI): >=80
Instant on - Less than 1 second: Yes
Lifetime: 25,000 hrs

General Appearance:



Luminaire:

Manufacturer	Integral	Type	LED
Location	Post	Wattage	3.8w
Finish	Black Surround	Lumens	180lm
Type	Recessed Brick Light	Lens	

Additional Information:

Job Title: PR Architecture Ltd Ref: 11 Sandy Lodge Way, Northwood, HA6 2AH

Job Number: 2286

Luminaire Ref: Pathlux In ground 4-Way Path Light IP67 115LM 4.5W 3000K

General Description:

This stylish and practical recessed pathlight provides a four-way beam of light for highlighting paths and driveways, perfect for homes or hospitality venues. Hard-wearing and weatherproof, the die-cast aluminium body and aluminium dome bezel makes it suitable for coastal areas, and H2O STOP technology provides additional protection against moisture ingress through the electrical cables.

Product Finish: Brushed aluminium

Optic: Facetted Aluminium

Material: Die cast Aluminium with Aluminium Dome Bezel

Depth: 105.00mm Diameter: 88mm

Lumens: 115lm

Correlated Colour Temperature (CCT): 3000k Warm White

Colour Rendering Index (CRI): >=80

LED Type: Chip-on-board (COB)

Lifetime: 25,000 hrs

General Appearance:



Luminaire:

Manufacturer	Integral	Type	LED
Location	Pathway	Wattage	4.5w
Finish	Aluminium	Lumens	115lm
Type	Recessed ground	Lens	

Additional Information:

Job Title: PR Architecture Ltd Ref: 11 Sandy Lodge Way, Northwood, HA6 2AH

Job Number: 2286

Luminaire Ref: LED external spike/wall light - 3000k

General Description:

Built in LED
Matt black finish
Removable spike to allow wall mounting
Comes with 1 metre input lead
Lumens 550
CCT 3000 Warm White
Finish Black
Voltage 240
Wattage 7
CRI 80
IP Rating 65
Dimmable No
Length 287 Width 58 Depth 125

General Appearance:



Luminaire:

Manufacturer	ELD	Type	LED
Location	Surround	Wattage	7w
Finish	Black	Lumens	550lm
Type	Spike	Lens	

Additional Information: