

NOTE: New sprinkler system to be installed throughout new & existing parts of the school - refer to MEP information



- 01 - Courtyard garden below
- 02 - Feature fin wall
- 03 - Triple-height atrium
- 04 - Existing acrylic white render finish to be repaired and recoated to match
- 05 - Replacement Velfac windows with louvers to fanlight to suit hybrid ventilation system. See Elevations.
- 06 - Replacement Velfac windows where adjacent to new extension
- 07 - Extensive sedum roof to extension, 300mm gravel margin to parapet edge and rooflights.
- 08 - New platform lift in self-supporting enclosure.
- 09 - Rainwater chute with hopper head and downpipe
- 10 - Rain-light
- 11 - Fall arrest system for safe roof maintenance access
- 12 - Flat roof parapet
- 13 - Extended floor slab with screening.

KEY

- Teaching space
- Support space
- Sanitary space
- Residential
- Circulation



GENERAL NOTES

This document and its design content is copyright © and shall be read in conjunction with all other associated project information including plans, specifications, schedules and related consultants documents. Do not scale from documents. All information is to be used for reference only. Do not report any discrepancies, errors or omissions on this document to the Originator. If in doubt ASK.

NOTES

This drawing is based on KLH As-Built issue on 08.07.11

Proposed building extension

STUDIO: 17 COMBETON RD, CAMBRIDGE CB3 7BA
S 7 JANER ST, LONDON SE1 3EL
01223 344666 or yves@chadwickdryerclarke.co.uk T 0203 26243

chadwickdryerclarke studio
architects + designers

TITLE: PROPOSED SECOND FLOOR PLAN

CLIENT: London Borough of Hillingdon

ADDRESS: Northwood Way, Harefield Uxbridge UB9 6ET

PROJECT: Harefield School Expansion

DATE: 06/05/2022

SCALE @ A1: 1:100

PROJECT: 4266 CDC XX 02 DR A (GA) 120

REV: E

REV	DATE	ISSUE
E	06/05/2022	FOR PLANNING
D	29/04/2022	FOR COSTING
C	13/04/2022	FOR INFORMATION
B	29/03/2022	FOR PREVIEW ONLY
A	03/03/2022	FOR INFORMATION
	25/02/2022	FOR INFORMATION