

Middlesex Stadium Indicative Landscape Schedules (See Location Reference Sc on Plans 820.07)									
Species	1. Plan Reference / 2. Area Of Planting (m ²) / 3. Density (plants per m ²)								
	1	SC1	SC2	SC3	SC4				Species Tot
	2	3,850	96	122	412				
3	1m Centres	1m Centres	1m Centres	1m Centres	1m Centres				
Species	% mix	Size							
Clematis vitalba	8%	Whips	308	8	10	33			358
Crataegus monogyna	11%	Whips	424	11	13	45			493
Euonymus europaeus	9%	Whips	347	9	11	37			403
Ligustrum vulgare	10%	Whips	385	10	12	41			448
Prunus spinosa	12%	Whips	462	12	15	49			538
Rosa canina	8%	Whips	308	8	10	33			358
Rubus fruticosus	16%	Whips	616	15	20	66			717
Sambucus nigra	6%	Whips	231	6	7	25			269
Ulex europeus	5%	Whips	193	5	6	21			224
Viburnum opulus	15%	Whips	578	14	18	62			672
Total	100%		3850	96	122	412			4480

Wildflower Areas EM4

Area of wildflower Meadow = 2,396m²
Sowing rate 3-5 g per m²

0.5% Achillea millefolium (Yarrow)
1% Betonica officinalis (Betony)
3.5% centaurea nigra (Common Knapweed)
1% Filipendula ulmaria (Meadowsweet)
2.5% Galium verum (Lady's Bedstraw)
0.4% Lathyrus pratensis (Meadow Vetchling)
1% Leucanthemum vulgare (Oxeye Daisy)
0.5% Lotus corniculatus (Bird's-foot Trefoil)
1% Plantago lanceolata (Ribwort Plantain)
0.3% Primula veris (Cowslip)
2% Prunella vulgaris (selfheal)
3% Ranunculus acris (Meadow Buttercup)
1.5% Rhinanthus minor (Yellow Rattle)
1.5% Rumex acetosa (Common Sorrel)
0.2% Silene flos-cuculi (Ragged Robin)
0.1% Trifolium pratense (Wild Red Clover)
10% Agrostis capillaris (Common Bent)
2% Alopecurus pratensis (Meadow Foxtail)
2% Anthoxanthum odoratum (Sweet Vernal-grass)
1% Briza media (Quaking Grass)
36% Cynosurus cristatus (Crested Dogtail)
24% Festuca rubra (Slender Creeping Red Fescue)
1% Hordeum secalinum (Meadow Barley)
4% Phleum bertolonii (Smaller Cat's-tail)

Amenity Grass E2

Area of Meadow = 22,665m²
Sowing rate 25-35g per m²

80% Perennial Ryegrass
20% Strong Creeping Red Fescue



Application Boundary Line

Boundary of Proposed Grass Youth Football Pitches

Retained vegetation

Proposed Wildflower

8m Buffer Zone From Stream

Proposed Drainage swale

Existing Car Park

Proposed Shrub Planting

Proposed Amenity Grassland

Project Name: Middlesex Stadium (Formerly Hillingdon Borough Football Club)

Drawn By: DW

Approved By: BW

Revision: A

Drawing Name: Landscape Plan

Scale: 1:500 @ A1

Date: 16/04/2025

Adjustment: B 16/04/2025 - Flood zone 3 and stream buffer added / Slight adjustment to contours in south west corner to remove from Flood zone 3 & stream buffer / Senior Pitch removed / Pitch locations slightly adjusted to allow for Respect zone / runoff strip illustrated

Project No: 820

Drawing No: 820.04 Rev B



Weller Designs Limited