

3.0 MANUFACTURERS DATASHEETS

APPENDIX A

JSW 41 Issue 04

**Jacksons
Fencing**

SECURI-MESH®



Securi-Mesh® fencing system provides an ideal solution for a wide variety of high security perimeter and access control applications. Both the mesh and posts are designed to meet Home Office specifications for use in utilities sites, high risk locations and secure compounds.

- Posts can be customised for Barbed wire/Razor wire/Rota Spike®/Alarm-aFence®
- Overlapped by a minimum of 75mm at posts to maintain integrity of protection
- Clamp bar fixings
- Mesh spacing conforms to building regulations for anti-trap
- Anti-climb design
- Can be stepped to accommodate sloping ground
- Custom designs available
- 25-year service life guarantee



APPLICATIONS

- ✓ Utilities
- ✓ High risk
- ✓ Secure compounds

PANELS

Securi-Mesh® panels are constructed from 76.2 x 12.7mm mesh (3" x 1/2") with 4mm wire. Panel widths are 2515mm as standard, with heights up to 5210mm.

GATES

Matching gates available