

## APPENDIX D

JSW 95 Issue 02

### SECURI-MESH® SWING GATES

**Jacksons  
Fencing**



- Climb resistant mesh with its small apertures eliminates foot and finger holds
- Welded frame design
- Horizontal rails for all gates are 60x40mm. Hanging and shutting stiles are rectangular hollow section 60x60mm
- Single or double leaf options available
- Manual or automated operation
- Complete with tamperproof hinges that allow the gate to swing through an angle of 180 degrees (manual only)
- Square hollow section gate posts

#### FINISHES

- Hot dip galvanised to BS EN ISO 1461 as standard
- Hot dip galvanised and powder coated to BS EN 13438
- Marine coat for installations within 500m of salt water or an estuary

#### POST OPTIONS

- Over length set in concrete as standard
- Base plated to bolt down onto concrete