



SOUTH WEST ELEVATION



SOUTH WEST SECTIONAL ELEVATION D-D

Elevational Materials:

- 1 New Standing Seam Vertical Zinc Cladding supplied by VM Zinc (or similar approved)
- 2 Bespoke Steel Balustrading with Galvanised Finish comprising of 10x75mm Vertical Flat Steel Sections @100mm c/c Spacings
- 3 Naturally Weathered Vertical T & G Siberian Larch Timber Cladding (with Sioo Preservative Treatment or Similar Approved)
- 4 New Double Glazed Powder Coated Aluminium Windows and External Doors with Grey Frames (RAL Colour TBC)
- 5 Naturally Weathered Vertical Siberian Larch Timber Privacy Screens @ min. +1800mm above Finished Deck Level
- 6 Cantilevered Entrance Canopy with Galvanised Steel Frame / Edging



- 7 New Dormer Windows to have a Zinc Finished 'Flat' Roof, Side Cheeks and Window Surround
- 8 Pitched Tile Roof Finish to Remain as Existing
- 9 Rear Access to Remain as Existing
- 10 Black Cast Iron Rainwater Goods (or Similar Approved) Throughout
- 11 Galvanised Steel External Communal Access Steps
- 12 Flush Fitting Opening Conservation Style Rooflights



BLOCK³ ARCHITECTS		REV A - Planning Application Submission - December 2020	
		TITLE: F.E.R. 173-175 Field End Road, Pinner Elevations and Sections - Proposed	
HOLLY COTTAGE, BAVENEY WOOD, NR KIDDERMINSTER, DY14 8JB		DRG. NO: L (-) 006	SCALE: 1:100@A2 / 1:50@A0
T +44 (0)1299 841111 E info@b3a.co.uk W www.b3a.co.uk		DATE: December 2020	REV: A