



FNH432 – Former Chailey Industrial Estate, Pump Lane, Hayes

2010/APP/2018/4231 Condition 7 Summary Report

Sustainable Water Management

FNH432/C7/01

Issue 1: 12th February 2020

1.0 Introduction

- 1.1 Infrastructure Design Ltd (IDL) has been appointed by Fairview New Homes (Developments) Ltd to prepare a Foul, Surface Water & SuDS design for their proposed residential development site.
- 1.2 A Drainage Strategy was prepared in support of the planning application (Ref: FNH432/DS/01, dated 26th November 2018), following a meeting with the LLFA on 2nd October 2018.
- 1.3 This planning drainage strategy report accompanied a the Flood Risk Assessment prepared by Hydrock (ref: 08639-HYD-XX-XX-RP-D-5001) and the completed *Hillingdon Technical Assessment ProForma*.
- 1.4 The scheme obtain planning consent on 4th October 2019.
- 1.5 This summary report supplies the information required to satisfy Condition 7 of the Planning Consent.

2.0 Condition 7 Requirements

Prior to commencement (excluding demolition and site clearance) a scheme for the provision of sustainable water management shall be submitted to, and approved in writing by the Local Planning Authority. The scheme shall follow the strategy set out in the submitted letter dated 21st September from GTA Civils. The scheme shall clearly demonstrate how it, manages water and demonstrate ways of controlling the surface water on site by providing information on:

a) Suds features

- i. incorporating sustainable urban drainage (SuDs) in accordance with the hierarchy set out in Policy 5.15 of the London Plan. Where the proposal does not utilise the most sustainable solution, justification must be provided,*
- ii. calculations showing storm period and intensity and volume of storage required to control surface water and size of features to control that volume to Greenfield run off rates at a variety of return periods including 1 in 1 year, 1 in 30, 1 in 100, and 1 in 100 plus Climate change. This rate should be presented per hectare as well as the total for the whole site.*
- iii. where it is intended to have above ground storage, overland flooding should be mapped, both designed and exceedance routes above the 100, plus climate change, including flow paths depths and velocities identified as well as any hazards, (safe access and egress must be demonstrated).*
- iv. Where infiltration techniques (soakaway) a site investigation must be provided to establish the level of groundwater on the site, and to demonstrate the suitability of infiltration techniques proposed on the site. (This should be undertaken at the appropriate time of year as groundwater levels fluctuate).*

b) Minimise water use

i. incorporate water saving measures and equipment.

ii. provide details of how rain and or grey water will be recycled and reused in the development.

c) Long Term Management and Maintenance of the drainage system

i. Provide a management and maintenance plan

ii Include details of Inspection regimes, performance specification, (remediation and timescales for the resolving of issues where a PMC).

iii Where overland flooding is proposed, the plan should include the appropriate actions to define those areas and actions required to ensure the safety of the users of the site should that be required.

iv. Clear plans showing all of the drainage network above and below ground. The responsibility of different parties such as the landowner.

Thereafter the development shall be implemented and retained/maintained in accordance with these details for as long as the development remains in existence.

REASON

To ensure that surface water run off is controlled to ensure the development does not increase the risk of flooding contrary to: Policy EM6 Flood Risk Management in Hillingdon Local Plan: Part 1- Strategic Policies (Nov 2012), Policy 5.12 Flood Risk Management of the London Plan (March 2016) and To be handled as close to its

source as possible in compliance with Policy 5.13 Sustainable Drainage of the London Plan (March 2016), and Conserve water supplies in accordance with Policy 5.15 Water use and supplies of the London Plan (March 2016). National Planning Policy Framework (July 2018), and the Planning Practice Guidance (Flood Risk and Coastal Change March 2014)

2.1 The wording of the condition is incorrect within the first paragraph, as it refers to letter date 21st September from GTA Civils. The strategy report submitted, is that provided by Infrastructure Design Limited, dated 26th November 2018.

2.2 Item b (i) is dealt with outside of the scope of this report, as it relates to the use of fittings provided to reduce water usage. Information in the regard is provided separately by the Developer.

3.0 Condition 7 Response (SuDS Features)

3.1 *i. incorporating sustainable urban drainage (SuDs) in accordance with the hierarchy set out in Policy 5.15 of the London Plan. Where the proposal does not utilise the most sustainable solution, justification must be provided,*

We feel that that the clause referred to in this paragraph should read 5.13 (rather than 5.15) as it relates to the SuDS Hierarchy

The London Plan Policy 5.13 (SUSTAINABLE DRAINAGE)

A Development should utilise sustainable urban drainage systems (SUDS) unless there are practical reasons for not doing so, and should aim to achieve greenfield run-off rates and ensure that surface water run-off is managed as close to its source as possible in line with the following drainage hierarchy:

1 Store rainwater for later use

Consideration has been given to the incorporation of Rainwater Harvesting, however, given the limited fall across the site, RWHT installations are not possible as they include a step in invert across the tank which cannot be accommodated.

2 Use infiltration techniques, such as porous surfaces in non-clay areas

The underlying geology is unsuitable for infiltration techniques.

3 Attenuate rainwater in ponds or open water features for gradual release

Given the desires of the LPA and viability of the site, density on this development is such that insufficient communal space is available for this larger form of above-ground SuDS feature. Blue Roofs however have been incorporated at podium level which will serve to deal with some surface water at source.

4 Attenuate rainwater by storing in tanks or sealed water features for gradual release

Cellular attenuation crates are proposed, along with a series of staged gravity flow control devices to ultimately limit discharge rates to greenfield runoff rates. Lined permeable paving is proposed extensively in the construction of roads and external parking areas.

5 Discharge rainwater direct to a watercourse

There are no watercourses within the immediate vicinity of the site.

6 Discharge rainwater to a surface water sewer/drain

Adoptable SW sewers exist in Pump Lane and agreement has been reached with Thames Water to connect.

7 Discharge rainwater to the combined sewer.

Not required.

- 3.2 *ii. calculations showing storm period and intensity and volume of storage required to control surface water and size of features to control that volume to Greenfield run off rates at a variety of return periods including 1 in 1 year, 1 in 30, 1 in 100, and 1 in 100 plus Climate change. This rate should be presented per hectare as well as the total for the whole site.*

Calculations are included in Appendix B

- 3.3 *iii. where it is intended to have above ground storage, overland flooding should be mapped, both designed and exceedance routes above the 100, plus climate change, including flow paths depths and velocities identified as well as any hazards, (safe access and egress must be demonstrated).*

We can confirm that there will be no above-ground storage.

- 3.4 *iv. Where infiltration techniques (soakaway) a site investigation must be provided to establish the level of groundwater on the site, and to demonstrate the suitability of infiltration techniques proposed on the site. (This should be undertaken at the appropriate time of year as groundwater levels fluctuate).*

Infiltration techniques are not proposed on this development

4.0 Condition 7 Response (Minimising Water Use)

- 4.1 *i. incorporate water saving measures and equipment.*

Information in the regard is provided separately by the Developer.

- 4.2 *ii. provide details of how rain and or grey water will be recycled and reused in the development.*

As noted above under The London Plan Hierarchy, rainwater, and indeed grey water cannot be collected for reuse given the step in inverts across the tanks which would be provided to store the water. This is due to the fall across the site and the minimum self-cleansing gradients of the surface water drains required to serve the development.

5.0 Condition 7 Response (Long Term Management and Maintenance of the drainage system)

5.1 i. Provide a management and maintenance plan

Refer to Management & Maintenance Plan included as Appendix C.

5.2 ii Include details of Inspection regimes, performance specification, (remediation and timescales for the resolving of issues where a PMC).

Refer to Management & Maintenance Plan included as Appendix C.

5.3 iii Where overland flooding is proposed, the plan should include the appropriate actions to define those areas and actions required to ensure the safety of the users of the site should that be required. iv. Clear plans showing all of the drainage network above and below ground. The responsibility of different parties such as the landowner.

No overland flooding is proposed

6.0 Enclosures

6.1 Appendix A includes the Drainage Layout

6.2 Appendix B includes the surface water calculations for each SuDs feature.

6.3 Appendix C includes the Management & Maintenance Requirements.

.

Appendix A – Drainage Layout

ConDoc Issue

NOTES

- This drawing is to be read in conjunction with the private and drainage construction details.
- All private drainage works to be carried out in accordance with the provisions laid down in BS EN 122.8 The Building Regulations, Part 15.
- Levels shown in buildings are Finished Floor Level.
- Drainage under adopted roads to be either:
a) Vertically Drained to BS EN 122.8
b) Concrete to BS 5911, Class M. Latexes to be formed of either vitrified clay or "Extra Strength" concrete "Class M".
- Before commencing any Sewer or drainage works, the Developer's Groundwater must satisfy themselves, the developer and the Local Authority of actual levels and conditions of existing sewers.
- Bored concrete to satisfy the requirements of BRE Special Digest 1 as predetermined by the site's Geotechnical Report.
- All abandoned, buried obstructions encountered during the construction of Highway A Drainage Works are to be broken out to bed level of drains and sewers, and to the formation of capsaids and covers etc. and to sufficient depth to allow for laying service company's mains and services.
- Depth and Location of existing services to be traced prior to any excavation.
- All private drainage to be laid to levels shown using flexibly jointed pipes, either UPVC to BS 4640 and BS 5445 or vitrified clayware to BS EN 295.
- Generally pipes to have granular Bed & Surround in accordance with manufacturers recommendations, ensuring adequate protection with respect to depth and location. Where bedding material is placed at depths susceptible to ground water ingress, it is to be wrapped in a geotextile (Terran 700 or better).
- Private paved concrete kerbsides and catchpits to be constructed using conc. box sections or circular rings to BS 5911:200, with 150mm conc. surround. Size and construction to comply with Table 12 of Approved Document, Part H.
- All manholes / inspection chambers in block paved areas, to have recessed covers. These are to be orientated such as to minimise cut blocks.
- All pipework to be 100mmD (1500 from road gullies) unless otherwise stated.
- All levels in manholes (if) unless specified otherwise.
- All drain runs from Sigs, stub stacks or FW gullies to be laid at 1:40 gradient unless otherwise stated.
- Sigs, stub stacks & 6000's are shown indicative only. Refer to FH432/12 series drawings for accurate locations.
- House/Fit drainage to be laid prior to erection of scaffold.
- All cover and invert levels shown are in metres. All pipe diameters are in millimetres U.N.G.
- All chambers located in trafficked areas to have concrete surround as detailed on FH432/13 series construction details.
- IMPORTANT NOTE:
At depths where groundwater ingress is encountered, consider the use of a sump / pump arrangement. Additional reference should be made to the Interpretative Geotechnical Report for supplementary measures in such instances.
Where excavations are 1m deep, consider the use of full perimeter trench support.
- IMPORTANT NOTE:
The new sewer connections are to be successfully made prior to commencing any upstream drainage works.
-

Key

- FW Existing foul water sewer
- SW Existing surface water sewer
- Private below-ground foul water drainage
- Private below-ground surface water drainage
- 100 dia perforated pipe below subbase of permeable road (not presently shown. Allow 470 linear metres)
- Polypropylene universal inspection chambers 1200 deep max. 450 dia. 100 inlet / outlet connections (6 no. max) or 150 individual connections (4 no. max) as detailed on FH432/13.3series construction details.
- Polypropylene "non-entry" inspection chambers 3000 deep max. 450 dia. 100 inlet / outlet connections (6 no. max) or 150 individual connections (4 no. max) as detailed on FH432/13.3series construction details.
- Denotes 250 dia. pvc. 600mm deep with 4 no. max 100 dia. inlets / outlets up to 150mm dia. as detailed on FH432/13.3series construction details. Where >1200mm deep, use reduced size access cover. Waven Range 500/600 or similar.
- Denotes 500/600 dia pvc. 600mm deep max with 4 no. max inlets / outlets up to 150mm dia. as detailed on FH432/13.3series construction details. Where >1200mm deep, use reduced size access cover. Waven Range 500/600 or similar.
- Denotes 450 dia polypropylene silt trap with 300mm nominal sump, as messrs Polytype Basic Silt Trap or similar.
- Rodding eye same dia. as downstream drain
- 900 deep gully (trapped) with 150 outlet.
- 600 deep yard gully (trapped) with 100 outlet.
- 110mm dia bottle gully with 100 outlet to FW drainage system.
- Podium gully
- PCC surface water catchpit as detailed on FH432/13.3series construction details
- Stitched linear drainage channel with sump unit and 100 outlet to drainage system, as messrs ACO Drain or similar approved
- Denotes extent of below-ground drainage to benefit from a root barrier as detailed on FH432/13.3series construction details
- Denotes extent of below-ground drainage to benefit from a root barrier as detailed on FH432/13.3series construction details
- Denotes brick retaining walls. Refer to FH432/14 series drawings for details
- Proposed trees. Locations TBC
- Denotes extent of off-podium permeable block paved access road and parking areas. Refer to details on FH432/28.1 & 2series
- Denotes extent of on-podium permeable block paving. Refer to details on FH432/28.1 & 2series
- Denotes extent of Permavoid cellular system (450mm depth) under roads where noted
- Denotes extent of Aquacell or equivalent cellular attenuation (800mm depth) where noted
- Potential land for Highway dedication.

Crate Storage

PNO.	EASTING	NORTHING
1	510152.586	179600.969
2	510155.292	179609.653
3	510152.781	179601.239
4	510124.085	179602.555
5	510181.585	179724.414
6	510185.977	179727.753
7	510168.116	179693.140
8	510162.724	179665.772
9	510085.515	179747.356
10	510092.214	179743.979
11	510050.633	179664.807
12	510056.633	179668.223
13	510070.608	179716.855
14	510071.881	179716.224
15	510072.813	179716.143
16	510071.540	179716.764

Surface Water Chamber Schedule

NO.	Cover Level	Invert Level	Chamber Type	Eastng	Northng	Remarks
SW01	30.75	29.93	600 IC	510181.839	179600.397	450mm deep sump
SW02	30.75	29.93	1200 PCC MH	510136.972	179607.272	Hydrobrake Control Chamber
SW03	30.70	29.15	1200 PCC MH	510146.513	179653.264	Non-Entry Cover
SW04	30.72	29.09	600 IC	510153.306	179664.603	450mm deep sump
SW05	30.65	29.00	1200 catchpit	510164.437	179663.328	450mm deep sump
SW06	30.40	28.93	1200 catchpit	510185.022	179729.425	450mm deep sump
SW07	30.60	28.85	1200 PCC MH	510168.344	179728.123	Hydrobrake/Office Control Chamber
SW08	30.85	30.00	450 IC	510099.461	179629.359	450mm deep sump
SW09	30.85	29.41	1200 catchpit	510107.132	179635.019	450mm deep sump
SW10	30.75	29.26	1200 catchpit	510121.892	179665.275	450mm deep sump
SW11	30.85	29.88	450 IC	510111.403	179685.056	450mm deep sump
SW12	31.08	30.22	450 IC	510022.735	179686.786	450mm deep sump
SW13	31.08	29.98	450 IC	510066.879	179717.763	450mm deep sump
SW14	31.09	29.92	1200 catchpit	510074.205	179724.772	450mm deep sump
SW15	31.08	29.40	600 IC	510084.901	179756.686	Non-Entry Cover
SW16	30.77	29.27	1200 PCC MH	510096.927	179751.745	Hydrobrake Control Chamber
SW17	31.07	29.16	1200 catchpit	510101.338	179737.073	450mm deep sump
SW18	31.02	30.15	450 Silt Trap	510041.326	179708.800	300mm deep sump
SW19	31.02	29.93	450 Silt Trap	510052.863	179733.437	Non-Entry Cover. 300mm deep sump
SW20	31.01	29.78	1200 catchpit	510068.707	179741.312	450mm deep sump
SW21	31.02	30.18	450 Silt Trap	510053.829	179755.903	300mm deep sump
SW22	31.06	30.27	450 IC	510087.709	179767.454	Non-Entry Cover. 300mm deep sump
SW23	31.06	29.77	450 Silt Trap	510084.510	179747.373	Non-Entry Cover
SW24	31.08	29.58	450 IC	510086.337	179757.627	Non-Entry Cover
SW25	30.89	30.09	450 IC	510102.359	179768.363	450mm deep sump
SW26	30.79	29.75	450 Silt Trap	510105.480	179758.804	Non-Entry Cover. 300mm deep sump
SW27	30.83	29.64	450 Silt Trap	510112.215	179726.554	Non-Entry Cover. 300mm deep sump
SW28	30.73	29.40	1200 catchpit	510171.261	179738.891	450mm deep sump
SW29	30.75	29.33	1200 catchpit	510102.754	179745.972	450mm deep sump
SW30	30.79	29.97	450 Silt Trap	510126.909	179765.389	300mm deep sump
SW31	30.78	29.78	450 Silt Trap	510105.887	179765.589	Non-Entry Cover. 300mm deep sump
SW32	30.71	29.85	450 Silt Trap	510146.490	179724.624	300mm deep sump
SW33	30.88	29.80	450 IC	510084.819	179769.228	450mm deep sump
SW34	30.86	29.79	450 IC	510090.654	179761.554	300mm deep sump
SW35	30.73	29.60	1200 catchpit	510108.475	179665.801	450mm deep sump
SW36	30.85	30.17	450 Silt Trap	510111.622	179652.780	300mm deep sump
SW37	30.74	30.05	450 Silt Trap	510097.586	179639.313	300mm deep sump
SW38	31.00	30.16	450 Silt Trap	510082.256	179760.455	300mm deep sump
SW39	30.50	29.72	450 Silt Trap	510146.652	179741.125	300mm deep sump
SW40	30.65	29.70	450 IC	510110.523	179761.889	300mm deep sump

Foul Water Chamber Schedule

NO.	Cover Level	Invert Level	Chamber Type	Eastng	Northng	Remarks
FW01	30.75	29.65	450 IC	510105.885	179607.191	Non Entry Cover
FW02	30.75	29.46	450 IC	510120.071	179602.700	Non Entry Cover
FW03	30.75	29.16	450 IC	510136.151	179634.620	Non Entry Cover
FW04	30.70	28.84	450 IC	510148.199	179653.375	Non Entry Cover
FW05	30.70	28.57	450 IC	510164.208	179665.125	Non Entry Cover
FW06	30.65	28.52	450 IC	510161.056	179665.666	Non Entry Cover
FW07	30.45	28.12	450 IC	510183.289	179729.371	Non Entry Cover
FW08	30.60	27.75	1200 PCC MH	510152.263	179745.254	Non Entry Cover
FW09	30.79	28.60	450 IC	510092.458	179618.854	Non Entry Cover
FW10	30.79	29.47	450 IC	510097.073	179629.308	Non Entry Cover
FW11	30.84	29.35	450 IC	510107.540	179638.368	Non Entry Cover
FW12	30.75	29.09	450 IC	510121.526	179666.334	Non Entry Cover
FW13	30.80	29.60	450 IC	510088.217	179692.954	Non Entry Cover
FW14	31.05	29.85	450 IC	510041.136	179702.146	Non Entry Cover
FW15	31.05	29.49	450 IC	510060.143	179738.676	Non Entry Cover
FW16	31.07	29.35	600 IC	510074.734	179731.654	Non Entry Cover
FW17	31.06	29.15	450 IC	510085.307	179752.340	Non Entry Cover
FW18	30.77	28.71	1200 PCC MH	510091.688	179750.256	Non Entry Cover
FW19	30.75	28.52	1200 PCC MH	510101.490	179737.338	Non Entry Cover
FW20	31.05	29.85	450 IC	510067.510	179769.605	Non Entry Cover
FW21	31.05	29.71	450 IC	510069.681	179768.216	Non Entry Cover
FW22	31.06	29.90	450 IC	510106.028	179761.160	Non Entry Cover
FW23	31.07	29.80	450 IC	510082.601	179776.556	Non Entry Cover
FW24	30.88	29.60	450 IC	510142.665	179689.513	Non Entry Cover
FW25	30.88	29.22	450 IC	510101.840	179704.440	Non Entry Cover
FW26	31.76	28.84	450 IC	510115.976	179736.400	Non Entry Cover
FW27	30.77	29.40	450 IC	510146.518	179741.125	Non Entry Cover
FW28	30.72	29.22	450 IC	510157.100	179718.303	Non Entry Cover

0

ConDoc Issue

IDL 29.11.19

2

Prelim Issue

IDL 28.10.19

REV

AMENDMENTS

BY

DATE

Drawn:

IDL

Date:

Aug 2019

Scale:

1:250@AO

Section:

Infra

Checked:

DC

Approved:

PT

Title

Drainage Layout (Site Level)

Job:

Challey Industrial Estate Pump Lane, Hayes

Dwg No:

FNH432/13.3/1

Rev:


0

Dwg File Name:

I:\Drawings\9006 Challey Ind Est\7 Drainage\13-3-1.dwg

Fairview
NEW HOMES Ltd.


Technical Department
50 Lancaster Road
Enfield, Middlesex. EN2 0BY
Telephone No. 020-8432-1271
Facsimile No. 020-8432-3861
Web Site: www.fairview.co.uk
E-mail: technical@fnhld.co.uk



ConDoc Issue

NOTES

-  Denotes extent of blue roof system
-  Podium Gully Outlet. Refer to detail on FNH432/35.101



0	ConDoc Issue	IDL	29.11.19
2	Prelim Issue	IDL	28.10.19
REV AMENDMENTS		DATE	

Fairview[®] NEW HOMES Ltd.

Technical Department
50 Lancaster Road
Enfield, Middlesex EN2 OBY
Telephone No. 020-8432-1271
Facsimile No. 020-8342-3861
Web Site: www.fairview.co.uk
E-mail: technical@fnhltd.co.uk

Drawn :	IDL	Date :	Aug 2019
Scale :	1:250 @ A1	Section :	Infra
Checked :	DC	Approved :	PT

Drainage Layout (Podium Level)

Job : Chailey Ind Est, Pump Lane, Hayes

Dwg. No :	FNH432/13.3/2	Rev :	0
-----------	---------------	-------	---

Dwg file name:
\\Drawings\906 Chailey Ind Est\07 Drainage\13-3-1.dwg

Appendix B – Surface Water Drainage Calculations

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:1yr				
Date 26/11/2018 12:01 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.629	0.029	0.0	0.5	0.5	31.0	O K
10080 min Summer	34.628	0.028	0.0	0.5	0.5	29.8	O K
15 min Winter	34.612	0.012	0.0	0.1	0.1	12.6	O K
30 min Winter	34.617	0.017	0.0	0.2	0.2	17.9	O K
60 min Winter	34.623	0.023	0.0	0.3	0.3	23.8	O K
120 min Winter	34.629	0.029	0.0	0.5	0.5	30.3	O K
180 min Winter	34.632	0.032	0.0	0.6	0.6	34.1	O K
240 min Winter	34.635	0.035	0.0	0.7	0.7	36.5	O K
360 min Winter	34.637	0.037	0.0	0.8	0.8	38.9	O K
480 min Winter	34.638	0.038	0.0	0.8	0.8	39.8	O K
600 min Winter	34.639	0.039	0.0	0.9	0.9	40.6	O K
720 min Winter	34.639	0.039	0.0	0.9	0.9	41.1	O K
960 min Winter	34.640	0.040	0.0	0.9	0.9	41.6	O K
1440 min Winter	34.639	0.039	0.0	0.9	0.9	41.5	O K
2160 min Winter	34.638	0.038	0.0	0.9	0.9	40.2	O K
2880 min Winter	34.637	0.037	0.0	0.8	0.8	38.6	O K
4320 min Winter	34.634	0.034	0.0	0.7	0.7	35.8	O K
5760 min Winter	34.632	0.032	0.0	0.6	0.6	33.3	O K
7200 min Winter	34.630	0.030	0.0	0.5	0.5	31.2	O K
8640 min Winter	34.628	0.028	0.0	0.5	0.5	29.4	O K
10080 min Winter	34.627	0.027	0.0	0.4	0.4	27.9	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.352	0.0	80.3	4760			
10080 min Summer	0.315	0.0	81.4	5504			
15 min Winter	31.332	0.0	5.1	84			
30 min Winter	20.391	0.0	9.3	87			
60 min Winter	12.872	0.0	18.0	100			
120 min Winter	7.960	0.0	24.7	136			
180 min Winter	5.980	0.0	29.1	182			
240 min Winter	4.876	0.0	32.5	238			
360 min Winter	3.634	0.0	37.3	346			
480 min Winter	2.942	0.0	40.9	432			
600 min Winter	2.497	0.0	43.8	474			
720 min Winter	2.184	0.0	46.2	548			
960 min Winter	1.768	0.0	50.0	694			
1440 min Winter	1.313	0.0	55.0	984			
2160 min Winter	0.975	0.0	68.1	1404			
2880 min Winter	0.789	0.0	72.4	1812			
4320 min Winter	0.586	0.0	77.2	2592			
5760 min Winter	0.474	0.0	87.8	3392			
7200 min Winter	0.403	0.0	90.8	4112			
8640 min Winter	0.352	0.0	92.8	4920			
10080 min Winter	0.315	0.0	94.0	5648			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:1yr	
Date 26/11/2018 12:01 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for BlueRoof-01.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	1	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m²)	1107	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)
0	4	0.020116	32	36	0.004061	64	68	0.000820	96	100	0.000166
4	8	0.016470	36	40	0.003325	68	72	0.000671	100	104	0.000136
8	12	0.013484	40	44	0.002722	72	76	0.000550	104	108	0.000111
12	16	0.011040	44	48	0.002229	76	80	0.000450	108	112	0.000091
16	20	0.009039	48	52	0.001825	80	84	0.000368	112	116	0.000074
20	24	0.007400	52	56	0.001494	84	88	0.000302	116	120	0.000061
24	28	0.006059	56	60	0.001223	88	92	0.000247			
28	32	0.004961	60	64	0.001002	92	96	0.000202			

Time Area Diagram

Total Area (ha) 0.176

Time (mins) From:	To:	Area (ha)
0	4	0.176

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:1yr	
Date 26/11/2018 12:01 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-01.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	1107.0	1107.0	1.300	0.0	1127.0
0.100	1107.0	1120.3	1.400	0.0	1127.0
0.200	0.0	1127.0	1.500	0.0	1127.0
0.300	0.0	1127.0	1.600	0.0	1127.0
0.400	0.0	1127.0	1.700	0.0	1127.0
0.500	0.0	1127.0	1.800	0.0	1127.0
0.600	0.0	1127.0	1.900	0.0	1127.0
0.700	0.0	1127.0	2.000	0.0	1127.0
0.800	0.0	1127.0	2.100	0.0	1127.0
0.900	0.0	1127.0	2.200	0.0	1127.0
1.000	0.0	1127.0	2.300	0.0	1127.0
1.100	0.0	1127.0	2.400	0.0	1127.0
1.200	0.0	1127.0	2.500	0.0	1127.0

Pipe Outflow Control

Diameter (m) 0.150 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited		Page 1					
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU		Chailey Ind Est Blue Roof 02 1:1yr					
Date 26/11/2018 12:02 File Cascade.casx		Designed by IDL Checked by PT					
Micro Drainage		Source Control 2017.1.2					
<u>Cascade Summary of Results for BlueRoof-02.SRCX</u>							
Upstream Structures		Outflow To	Overflow To				
(None)		Hydrobrake-02.SRCX	(None)				
Half Drain Time : 573 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	34.607	0.007	0.0	0.0	0.0	4.2	O K
30 min Summer	34.610	0.010	0.0	0.1	0.1	6.4	O K
60 min Summer	34.614	0.014	0.0	0.1	0.1	8.8	O K
120 min Summer	34.619	0.019	0.0	0.2	0.2	11.4	O K
180 min Summer	34.621	0.021	0.0	0.2	0.2	13.0	O K
240 min Summer	34.623	0.023	0.0	0.3	0.3	14.0	O K
360 min Summer	34.625	0.025	0.0	0.3	0.3	15.0	O K
480 min Summer	34.625	0.025	0.0	0.3	0.3	15.4	O K
600 min Summer	34.626	0.026	0.0	0.3	0.3	15.7	O K
720 min Summer	34.626	0.026	0.0	0.3	0.3	16.0	O K
960 min Summer	34.627	0.027	0.0	0.3	0.3	16.4	O K
1440 min Summer	34.627	0.027	0.0	0.4	0.4	16.7	O K
2160 min Summer	34.627	0.027	0.0	0.4	0.4	16.6	O K
2880 min Summer	34.627	0.027	0.0	0.3	0.3	16.3	O K
4320 min Summer	34.625	0.025	0.0	0.3	0.3	15.4	O K
5760 min Summer	34.624	0.024	0.0	0.3	0.3	14.6	O K
7200 min Summer	34.623	0.023	0.0	0.2	0.2	13.9	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	31.332	0.0	1.5	92			
30 min Summer	20.391	0.0	3.1	94			
60 min Summer	12.872	0.0	6.4	108			
120 min Summer	7.960	0.0	9.1	144			
180 min Summer	5.980	0.0	10.9	188			
240 min Summer	4.876	0.0	12.2	242			
360 min Summer	3.634	0.0	14.2	360			
480 min Summer	2.942	0.0	15.6	416			
600 min Summer	2.497	0.0	16.7	474			
720 min Summer	2.184	0.0	17.6	534			
960 min Summer	1.768	0.0	19.1	664			
1440 min Summer	1.313	0.0	20.9	932			
2160 min Summer	0.975	0.0	25.9	1332			
2880 min Summer	0.789	0.0	27.4	1728			
4320 min Summer	0.586	0.0	28.8	2504			
5760 min Summer	0.474	0.0	32.5	3232			
7200 min Summer	0.403	0.0	33.4	4032			
©1982-2017 XP Solutions							

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 02 1:1yr				
Date 26/11/2018 12:02 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.622	0.022	0.0	0.2	0.2	13.4	O K
10080 min Summer	34.621	0.021	0.0	0.2	0.2	12.8	O K
15 min Winter	34.608	0.008	0.0	0.0	0.0	5.1	O K
30 min Winter	34.612	0.012	0.0	0.1	0.1	7.5	O K
60 min Winter	34.617	0.017	0.0	0.1	0.1	10.2	O K
120 min Winter	34.622	0.022	0.0	0.2	0.2	13.1	O K
180 min Winter	34.624	0.024	0.0	0.3	0.3	14.8	O K
240 min Winter	34.626	0.026	0.0	0.3	0.3	15.9	O K
360 min Winter	34.628	0.028	0.0	0.4	0.4	17.0	O K
480 min Winter	34.629	0.029	0.0	0.4	0.4	17.4	O K
600 min Winter	34.629	0.029	0.0	0.4	0.4	17.7	O K
720 min Winter	34.630	0.030	0.0	0.4	0.4	18.0	O K
960 min Winter	34.630	0.030	0.0	0.4	0.4	18.2	O K
1440 min Winter	34.630	0.030	0.0	0.4	0.4	18.1	O K
2160 min Winter	34.629	0.029	0.0	0.4	0.4	17.5	O K
2880 min Winter	34.628	0.028	0.0	0.4	0.4	16.7	O K
4320 min Winter	34.625	0.025	0.0	0.3	0.3	15.4	O K
5760 min Winter	34.624	0.024	0.0	0.3	0.3	14.3	O K
7200 min Winter	34.622	0.022	0.0	0.2	0.2	13.4	O K
8640 min Winter	34.621	0.021	0.0	0.2	0.2	12.7	O K
10080 min Winter	34.620	0.020	0.0	0.2	0.2	12.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.352	0.0	34.0	4760			
10080 min Summer	0.315	0.0	34.4	5480			
15 min Winter	31.332	0.0	2.1	88			
30 min Winter	20.391	0.0	4.0	92			
60 min Winter	12.872	0.0	7.8	106			
120 min Winter	7.960	0.0	10.9	140			
180 min Winter	5.980	0.0	12.9	184			
240 min Winter	4.876	0.0	14.4	238			
360 min Winter	3.634	0.0	16.6	348			
480 min Winter	2.942	0.0	18.3	420			
600 min Winter	2.497	0.0	19.6	476			
720 min Winter	2.184	0.0	20.6	548			
960 min Winter	1.768	0.0	22.3	694			
1440 min Winter	1.313	0.0	24.5	986			
2160 min Winter	0.975	0.0	30.1	1404			
2880 min Winter	0.789	0.0	31.9	1796			
4320 min Winter	0.586	0.0	33.8	2596			
5760 min Winter	0.474	0.0	38.0	3344			
7200 min Winter	0.403	0.0	39.1	4112			
8640 min Winter	0.352	0.0	39.7	4928			
10080 min Winter	0.315	0.0	40.0	5656			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for BlueRoof-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	1	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m³)	639	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)
0	4	0.011612	32	36	0.002344	64	68	0.000473	96	100	0.000096
4	8	0.009507	36	40	0.001919	68	72	0.000388	100	104	0.000078
8	12	0.007784	40	44	0.001571	72	76	0.000317	104	108	0.000064
12	16	0.006373	44	48	0.001287	76	80	0.000260	108	112	0.000052
16	20	0.005218	48	52	0.001053	80	84	0.000213	112	116	0.000043
20	24	0.004272	52	56	0.000862	84	88	0.000174	116	120	0.000035
24	28	0.003497	56	60	0.000706	88	92	0.000143			
28	32	0.002863	60	64	0.000578	92	96	0.000117			

Time Area Diagram

Total Area (ha) 0.067

Time (mins)	Area (ha)
From: To:	

0	4	0.067
---	---	-------

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-02.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	639.0	639.0	1.300	0.0	654.2
0.100	639.0	649.1	1.400	0.0	654.2
0.200	0.0	654.2	1.500	0.0	654.2
0.300	0.0	654.2	1.600	0.0	654.2
0.400	0.0	654.2	1.700	0.0	654.2
0.500	0.0	654.2	1.800	0.0	654.2
0.600	0.0	654.2	1.900	0.0	654.2
0.700	0.0	654.2	2.000	0.0	654.2
0.800	0.0	654.2	2.100	0.0	654.2
0.900	0.0	654.2	2.200	0.0	654.2
1.000	0.0	654.2	2.300	0.0	654.2
1.100	0.0	654.2	2.400	0.0	654.2
1.200	0.0	654.2	2.500	0.0	654.2

Pipe Outflow Control

Diameter (m) 0.100 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited		Page 1					
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU		Chailey Ind Est Hydrobrake 01 1:1yr					
Date 26/11/2018 12:02 File Cascade.casx		Designed by IDL Checked by PT					
Micro Drainage		Source Control 2017.1.2					
Cascade Summary of Results for Hydrobrake-01.srcx							
Upstream Structures		Outflow To	Overflow To				
Porous-CP-to-HB01.SRCX		Hydrobrake-03.SRCX	(None)				
Half Drain Time : 35 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control E (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	29.595	0.045	0.0	4.0	4.0	8.3	O K
30 min Summer	29.608	0.058	0.0	4.0	4.0	10.8	O K
60 min Summer	29.616	0.066	0.0	4.0	4.0	12.2	O K
120 min Summer	29.618	0.068	0.0	4.0	4.0	12.5	O K
180 min Summer	29.615	0.065	0.0	4.0	4.0	12.0	O K
240 min Summer	29.609	0.059	0.0	4.0	4.0	11.0	O K
360 min Summer	29.594	0.044	0.0	4.0	4.0	8.2	O K
480 min Summer	29.580	0.030	0.0	4.0	4.0	5.6	O K
600 min Summer	29.569	0.019	0.0	4.0	4.0	3.5	O K
720 min Summer	29.560	0.010	0.0	4.0	4.0	1.9	O K
960 min Summer	29.551	0.001	0.0	4.0	4.0	0.2	O K
1440 min Summer	29.550	0.000	0.0	3.1	3.1	0.0	O K
2160 min Summer	29.550	0.000	0.0	2.3	2.3	0.0	O K
2880 min Summer	29.550	0.000	0.0	1.9	1.9	0.0	O K
4320 min Summer	29.550	0.000	0.0	1.4	1.4	0.0	O K
5760 min Summer	29.550	0.000	0.0	1.1	1.1	0.0	O K
7200 min Summer	29.550	0.000	0.0	0.9	0.9	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	31.332	0.0	13.3	18			
30 min Summer	20.391	0.0	18.5	32			
60 min Summer	12.872	0.0	24.3	52			
120 min Summer	7.960	0.0	30.7	86			
180 min Summer	5.980	0.0	35.1	120			
240 min Summer	4.876	0.0	38.4	152			
360 min Summer	3.634	0.0	43.4	216			
480 min Summer	2.942	0.0	47.1	276			
600 min Summer	2.497	0.0	49.9	334			
720 min Summer	2.184	0.0	52.5	390			
960 min Summer	1.768	0.0	56.6	494			
1440 min Summer	1.313	0.0	62.9	0			
2160 min Summer	0.975	0.0	69.8	0			
2880 min Summer	0.789	0.0	74.8	0			
4320 min Summer	0.586	0.0	82.0	0			
5760 min Summer	0.474	0.0	87.2	0			
7200 min Summer	0.403	0.0	91.3	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 01 1:1yr				
Date 26/11/2018 12:02 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-01.srcx</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	29.550	0.000	0.0	0.8	0.8	0.0	O K
10080 min Summer	29.550	0.000	0.0	0.7	0.7	0.0	O K
15 min Winter	29.604	0.054	0.0	4.0	4.0	10.1	O K
30 min Winter	29.621	0.071	0.0	4.0	4.0	13.2	O K
60 min Winter	29.630	0.080	0.0	4.0	4.0	14.9	O K
120 min Winter	29.628	0.078	0.0	4.0	4.0	14.5	O K
180 min Winter	29.621	0.071	0.0	4.0	4.0	13.1	O K
240 min Winter	29.611	0.061	0.0	4.0	4.0	11.2	O K
360 min Winter	29.586	0.036	0.0	4.0	4.0	6.7	O K
480 min Winter	29.566	0.016	0.0	4.0	4.0	2.9	O K
600 min Winter	29.553	0.003	0.0	4.0	4.0	0.5	O K
720 min Winter	29.550	0.000	0.0	3.7	3.7	0.0	O K
960 min Winter	29.550	0.000	0.0	3.0	3.0	0.0	O K
1440 min Winter	29.550	0.000	0.0	2.2	2.2	0.0	O K
2160 min Winter	29.550	0.000	0.0	1.7	1.7	0.0	O K
2880 min Winter	29.550	0.000	0.0	1.3	1.3	0.0	O K
4320 min Winter	29.550	0.000	0.0	1.0	1.0	0.0	O K
5760 min Winter	29.550	0.000	0.0	0.8	0.8	0.0	O K
7200 min Winter	29.550	0.000	0.0	0.7	0.7	0.0	O K
8640 min Winter	29.550	0.000	0.0	0.6	0.6	0.0	O K
10080 min Winter	29.550	0.000	0.0	0.5	0.5	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.352	0.0	94.5	0			
10080 min Summer	0.315	0.0	97.1	0			
15 min Winter	31.332	0.0	15.5	19			
30 min Winter	20.391	0.0	21.1	32			
60 min Winter	12.872	0.0	27.6	58			
120 min Winter	7.960	0.0	34.8	92			
180 min Winter	5.980	0.0	39.8	128			
240 min Winter	4.876	0.0	43.4	164			
360 min Winter	3.634	0.0	48.9	228			
480 min Winter	2.942	0.0	53.0	284			
600 min Winter	2.497	0.0	56.5	326			
720 min Winter	2.184	0.0	59.3	0			
960 min Winter	1.768	0.0	64.0	0			
1440 min Winter	1.313	0.0	71.2	0			
2160 min Winter	0.975	0.0	79.0	0			
2880 min Winter	0.789	0.0	84.7	0			
4320 min Winter	0.586	0.0	93.1	0			
5760 min Winter	0.474	0.0	99.3	0			
7200 min Winter	0.403	0.0	104.1	0			
8640 min Winter	0.352	0.0	108.1	0			
10080 min Winter	0.315	0.0	111.4	0			

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:1yr																																		
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Hydrobrake-01.srcx</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>1</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.167 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.167</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	1	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.167
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	1	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.167																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-01.srcx

Storage is Online Cover Level (m) 30.650

Cellular Storage Structure

Invert Level (m) 29.550 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	195.0	195.0	1.300	0.0	242.5
0.100	195.0	200.6	1.400	0.0	242.5
0.200	195.0	206.2	1.500	0.0	242.5
0.300	195.0	211.8	1.600	0.0	242.5
0.400	195.0	217.3	1.700	0.0	242.5
0.500	195.0	222.9	1.800	0.0	242.5
0.600	195.0	228.5	1.900	0.0	242.5
0.700	195.0	234.1	2.000	0.0	242.5
0.800	195.0	239.7	2.100	0.0	242.5
0.900	0.0	242.5	2.200	0.0	242.5
1.000	0.0	242.5	2.300	0.0	242.5
1.100	0.0	242.5	2.400	0.0	242.5
1.200	0.0	242.5	2.500	0.0	242.5

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0095-4000-1000-4000
Design Head (m) 1.000
Design Flow (l/s) 4.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 95
Invert Level (m) 29.310
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	4.0
Flush-Flo™	0.294	4.0
Kick-Flo®	0.629	3.2
Mean Flow over Head Range	-	3.5

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.0	1.200	4.3	3.000	6.7	7.000	10.0
0.200	3.9	1.400	4.7	3.500	7.2	7.500	10.3
0.300	4.0	1.600	5.0	4.000	7.6	8.000	10.6
0.400	3.9	1.800	5.3	4.500	8.1	8.500	10.9
0.500	3.8	2.000	5.5	5.000	8.5	9.000	11.2
0.600	3.4	2.200	5.8	5.500	8.9	9.500	11.5
0.800	3.6	2.400	6.0	6.000	9.3		
1.000	4.0	2.600	6.2	6.500	9.6		

Infrastructure Design Limited		Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-02.SRCX

Upstream Structures
 BlueRoof-01.SRCX **Outflow To** Hydrobrake-03.SRCX **Overflow To** (None)
 BlueRoof-02.SRCX
 Porous-CP-to-HB02.SRCX

Half Drain Time : 27 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
15 min Summer	29.374	0.024	0.0	5.2	5.2	11.6	O K
30 min Summer	29.378	0.028	0.0	5.5	5.5	13.7	O K
60 min Summer	29.381	0.031	0.0	5.7	5.7	14.9	O K
120 min Summer	29.381	0.031	0.0	5.7	5.7	14.9	O K
180 min Summer	29.379	0.029	0.0	5.6	5.6	14.2	O K
240 min Summer	29.377	0.027	0.0	5.4	5.4	13.1	O K
360 min Summer	29.372	0.022	0.0	5.0	5.0	10.6	O K
480 min Summer	29.368	0.018	0.0	4.7	4.7	8.5	O K
600 min Summer	29.364	0.014	0.0	4.5	4.5	6.8	O K
720 min Summer	29.361	0.011	0.0	4.3	4.3	5.4	O K
960 min Summer	29.357	0.007	0.0	3.9	3.9	3.3	O K
1440 min Summer	29.352	0.002	0.0	3.6	3.6	0.7	O K
2160 min Summer	29.350	0.000	0.0	3.1	3.1	0.0	O K
2880 min Summer	29.350	0.000	0.0	2.7	2.7	0.0	O K
4320 min Summer	29.350	0.000	0.0	2.2	2.2	0.0	O K
5760 min Summer	29.350	0.000	0.0	1.9	1.9	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
15 min Summer	31.332	0.0	21.1	16
30 min Summer	20.391	0.0	31.8	28
60 min Summer	12.872	0.0	49.3	44
120 min Summer	7.960	0.0	64.9	80
180 min Summer	5.980	0.0	75.4	114
240 min Summer	4.876	0.0	83.5	146
360 min Summer	3.634	0.0	95.0	212
480 min Summer	2.942	0.0	103.2	276
600 min Summer	2.497	0.0	110.1	338
720 min Summer	2.184	0.0	115.9	400
960 min Summer	1.768	0.0	125.3	522
1440 min Summer	1.313	0.0	138.8	752
2160 min Summer	0.975	0.0	163.4	0
2880 min Summer	0.789	0.0	174.2	0
4320 min Summer	0.586	0.0	187.9	0
5760 min Summer	0.474	0.0	207.0	0

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-02.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
10080 min Winter	29.350	0.000	0.0	1.2	1.2	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
10080 min Winter	0.315	0.0	260.7	0

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	1	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.199

Time (mins)	Area
From:	To: (ha)

0	4 0.199
---	---------

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-02.SRCX

Storage is Online Cover Level (m) 30.630

Cellular Storage Structure

Invert Level (m) 29.350 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	510.0	510.0	1.300	0.0	559.7
0.100	510.0	519.0	1.400	0.0	559.7
0.200	510.0	528.1	1.500	0.0	559.7
0.300	510.0	537.1	1.600	0.0	559.7
0.400	510.0	546.1	1.700	0.0	559.7
0.500	510.0	555.2	1.800	0.0	559.7
0.600	0.0	559.7	1.900	0.0	559.7
0.700	0.0	559.7	2.000	0.0	559.7
0.800	0.0	559.7	2.100	0.0	559.7
0.900	0.0	559.7	2.200	0.0	559.7
1.000	0.0	559.7	2.300	0.0	559.7
1.100	0.0	559.7	2.400	0.0	559.7
1.200	0.0	559.7	2.500	0.0	559.7

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0136-8000-0680-8000
Design Head (m) 0.680
Design Flow (l/s) 8.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 136
Invert Level (m) 29.270
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.680	8.0
Flush-Flo™	0.231	8.0
Kick-Flo®	0.492	6.9
Mean Flow over Head Range	-	6.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:1yr	
Date 26/11/2018 12:02 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.9	1.200	10.4	3.000	16.1	7.000	24.1
0.200	7.9	1.400	11.2	3.500	17.4	7.500	25.0
0.300	7.9	1.600	12.0	4.000	18.5	8.000	25.8
0.400	7.6	1.800	12.6	4.500	19.6	8.500	26.6
0.500	6.9	2.000	13.3	5.000	20.6	9.000	27.4
0.600	7.5	2.200	13.9	5.500	21.6	9.500	28.1
0.800	8.6	2.400	14.5	6.000	22.5		
1.000	9.6	2.600	15.1	6.500	23.4		

Infrastructure Design Limited						Page 1	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 03 1:1yr				
Date 26/11/2018 14:21 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>							
Upstream Structures			Outflow To Overflow To				
Hydrobrake-01.srcx			(None)		(None)		
Porous-CP-to-HB01.SRCX							
Hydrobrake-02.SRCX							
BlueRoof-01.SRCX							
BlueRoof-02.SRCX							
Porous-CP-to-HB02.SRCX							
Half Drain Time : 76 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	29.015	0.065	0.0	6.0	6.0	19.4	O K
30 min Summer	29.039	0.089	0.0	6.0	6.0	26.4	O K
60 min Summer	29.062	0.112	0.0	6.0	6.0	33.2	O K
120 min Summer	29.083	0.133	0.0	6.0	6.0	39.4	O K
180 min Summer	29.096	0.146	0.0	6.0	6.0	43.2	O K
240 min Summer	29.102	0.152	0.0	6.0	6.0	45.1	O K
360 min Summer	29.100	0.150	0.0	6.0	6.0	44.3	O K
480 min Summer	29.092	0.142	0.0	6.0	6.0	42.1	O K
600 min Summer	29.082	0.132	0.0	6.0	6.0	39.3	O K
720 min Summer	29.073	0.123	0.0	6.0	6.0	36.3	O K
960 min Summer	29.052	0.102	0.0	6.0	6.0	30.4	O K
1440 min Summer	29.017	0.067	0.0	6.0	6.0	19.9	O K
2160 min Summer	28.982	0.032	0.0	5.8	5.8	9.5	O K
2880 min Summer	28.967	0.017	0.0	5.1	5.1	4.9	O K
4320 min Summer	28.951	0.001	0.0	4.3	4.3	0.3	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	31.332	0.0	45.3	57			
30 min Summer	20.391	0.0	64.4	81			
60 min Summer	12.872	0.0	91.6	112			
120 min Summer	7.960	0.0	118.1	158			
180 min Summer	5.980	0.0	135.6	198			
240 min Summer	4.876	0.0	149.2	232			
360 min Summer	3.634	0.0	169.0	284			
480 min Summer	2.942	0.0	183.2	338			
600 min Summer	2.497	0.0	194.9	402			
720 min Summer	2.184	0.0	205.1	464			
960 min Summer	1.768	0.0	221.7	592			
1440 min Summer	1.313	0.0	246.1	810			
2160 min Summer	0.975	0.0	282.6	1148			
2880 min Summer	0.789	0.0	302.3	1504			
4320 min Summer	0.586	0.0	329.3	2204			
©1982-2017 XP Solutions							

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 03 1:1yr				
Date 26/11/2018 14:21 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
5760 min Summer	28.950	0.000	0.0	3.7	3.7	0.0	O K
7200 min Summer	28.950	0.000	0.0	3.2	3.2	0.0	O K
8640 min Summer	28.950	0.000	0.0	2.9	2.9	0.0	O K
10080 min Summer	28.950	0.000	0.0	2.6	2.6	0.0	O K
15 min Winter	29.026	0.076	0.0	6.0	6.0	22.4	O K
30 min Winter	29.053	0.103	0.0	6.0	6.0	30.6	O K
60 min Winter	29.082	0.132	0.0	6.0	6.0	39.1	O K
120 min Winter	29.108	0.158	0.0	6.0	6.0	46.8	O K
180 min Winter	29.123	0.173	0.0	6.0	6.0	51.3	O K
240 min Winter	29.132	0.182	0.0	6.0	6.0	54.0	O K
360 min Winter	29.125	0.175	0.0	6.0	6.0	51.9	O K
480 min Winter	29.111	0.161	0.0	6.0	6.0	47.9	O K
600 min Winter	29.096	0.146	0.0	6.0	6.0	43.2	O K
720 min Winter	29.078	0.128	0.0	6.0	6.0	38.0	O K
960 min Winter	29.045	0.095	0.0	6.0	6.0	28.2	O K
1440 min Winter	28.993	0.043	0.0	5.9	5.9	12.7	O K
2160 min Winter	28.965	0.015	0.0	5.0	5.0	4.4	O K
2880 min Winter	28.951	0.001	0.0	4.4	4.4	0.4	O K
4320 min Winter	28.950	0.000	0.0	3.5	3.5	0.0	O K
5760 min Winter	28.950	0.000	0.0	2.9	2.9	0.0	O K
7200 min Winter	28.950	0.000	0.0	2.5	2.5	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
5760 min Summer	0.474	0.0	358.5	0			
7200 min Summer	0.403	0.0	374.9	0			
8640 min Summer	0.352	0.0	388.1	0			
10080 min Summer	0.315	0.0	398.5	0			
15 min Winter	31.332	0.0	52.9	66			
30 min Winter	20.391	0.0	74.3	91			
60 min Winter	12.872	0.0	104.6	124			
120 min Winter	7.960	0.0	134.5	170			
180 min Winter	5.980	0.0	154.8	210			
240 min Winter	4.876	0.0	169.9	246			
360 min Winter	3.634	0.0	192.1	300			
480 min Winter	2.942	0.0	208.3	366			
600 min Winter	2.497	0.0	222.0	436			
720 min Winter	2.184	0.0	233.4	504			
960 min Winter	1.768	0.0	252.6	632			
1440 min Winter	1.313	0.0	280.1	850			
2160 min Winter	0.975	0.0	321.1	1208			
2880 min Winter	0.789	0.0	344.0	1556			
4320 min Winter	0.586	0.0	375.7	0			
5760 min Winter	0.474	0.0	409.2	0			
7200 min Winter	0.403	0.0	428.3	0			

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:1yr	
Date 26/11/2018 14:21 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-03.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
8640 min Winter	28.950	0.000	0.0	2.2	2.2	0.0	O K
10080 min Winter	28.950	0.000	0.0	2.0	2.0	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
8640 min Winter	0.352	0.0	443.4	0
10080 min Winter	0.315	0.0	455.6	0

Infrastructure Design Limited		Page 4																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:1yr																																		
Date 26/11/2018 14:21 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Hydrobrake-03.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>1</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.188 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.188</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	1	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.188
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	1	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.188																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:1yr	
Date 26/11/2018 14:21 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-03.SRCX

Storage is Online Cover Level (m) 30.550

Cellular Storage Structure

Invert Level (m) 28.950 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	312.0	312.0	1.300	0.0	372.1
0.100	312.0	319.1	1.400	0.0	372.1
0.200	312.0	326.1	1.500	0.0	372.1
0.300	312.0	333.2	1.600	0.0	372.1
0.400	312.0	340.3	1.700	0.0	372.1
0.500	312.0	347.3	1.800	0.0	372.1
0.600	312.0	354.4	1.900	0.0	372.1
0.700	312.0	361.5	2.000	0.0	372.1
0.800	312.0	368.5	2.100	0.0	372.1
0.900	0.0	372.1	2.200	0.0	372.1
1.000	0.0	372.1	2.300	0.0	372.1
1.100	0.0	372.1	2.400	0.0	372.1
1.200	0.0	372.1	2.500	0.0	372.1

Complex Outflow Control

Hydro-Brake® Optimum

Unit Reference MD-SHE-0121-6000-0600-6000
Design Head (m) 0.600
Design Flow (l/s) 6.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 121
Invert Level (m) 28.850
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.600	6.0
Flush-Flo™	0.202	6.0
Kick-Flo®	0.435	5.2
Mean Flow over Head Range	-	5.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:1yr	
Date 26/11/2018 14:21 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.3	1.200	8.3	3.000	12.8	7.000	19.2
0.200	6.0	1.400	8.9	3.500	13.8	7.500	19.9
0.300	5.9	1.600	9.5	4.000	14.7	8.000	20.5
0.400	5.5	1.800	10.0	4.500	15.5	8.500	21.1
0.500	5.5	2.000	10.6	5.000	16.3	9.000	21.8
0.600	6.0	2.200	11.0	5.500	17.1	9.500	22.4
0.800	6.9	2.400	11.5	6.000	17.8		
1.000	7.6	2.600	12.0	6.500	18.5		

Orifice

Diameter (m) 0.125 Discharge Coefficient 0.600 Invert Level (m) 29.450

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU				Chailey Ind Est Porous CP to HB01 1:1yr			
Date 26/11/2018 12:03 File Cascade.casx				Designed by IDL Checked by PT			
Micro Drainage				Source Control 2017.1.2			
<u>Cascade Summary of Results for Porous-CP-to-HB01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.024	0.044	0.0	0.3	0.3	0.3	O K
10080 min Summer	30.022	0.042	0.0	0.3	0.3	0.2	O K
15 min Winter	30.116	0.136	0.0	6.7	6.7	2.5	O K
30 min Winter	30.126	0.146	0.0	7.7	7.7	2.9	O K
60 min Winter	30.119	0.139	0.0	7.0	7.0	2.6	O K
120 min Winter	30.097	0.117	0.0	5.3	5.3	1.9	O K
180 min Winter	30.085	0.105	0.0	4.2	4.2	1.5	O K
240 min Winter	30.077	0.097	0.0	3.4	3.4	1.3	O K
360 min Winter	30.069	0.089	0.0	2.6	2.6	1.1	O K
480 min Winter	30.061	0.081	0.0	2.1	2.1	0.9	O K
600 min Winter	30.056	0.076	0.0	1.8	1.8	0.8	O K
720 min Winter	30.052	0.072	0.0	1.6	1.6	0.7	O K
960 min Winter	30.047	0.067	0.0	1.3	1.3	0.6	O K
1440 min Winter	30.040	0.060	0.0	0.9	0.9	0.5	O K
2160 min Winter	30.034	0.054	0.0	0.7	0.7	0.4	O K
2880 min Winter	30.031	0.051	0.0	0.6	0.6	0.3	O K
4320 min Winter	30.026	0.046	0.0	0.4	0.4	0.3	O K
5760 min Winter	30.023	0.043	0.0	0.3	0.3	0.3	O K
7200 min Winter	30.021	0.041	0.0	0.3	0.3	0.2	O K
8640 min Winter	30.019	0.039	0.0	0.2	0.2	0.2	O K
10080 min Winter	30.018	0.038	0.0	0.2	0.2	0.2	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.352	0.0	30.9	4256			
10080 min Summer	0.315	0.0	30.8	5032			
15 min Winter	31.332	0.0	4.6	13			
30 min Winter	20.391	0.0	7.0	22			
60 min Winter	12.872	0.0	9.7	38			
120 min Winter	7.960	0.0	12.8	68			
180 min Winter	5.980	0.0	14.8	96			
240 min Winter	4.876	0.0	16.3	126			
360 min Winter	3.634	0.0	18.5	188			
480 min Winter	2.942	0.0	20.1	246			
600 min Winter	2.497	0.0	21.4	308			
720 min Winter	2.184	0.0	22.5	368			
960 min Winter	1.768	0.0	24.3	492			
1440 min Winter	1.313	0.0	27.0	720			
2160 min Winter	0.975	0.0	29.7	1100			
2880 min Winter	0.789	0.0	31.6	1456			
4320 min Winter	0.586	0.0	34.0	2204			
5760 min Winter	0.474	0.0	35.4	2928			
7200 min Winter	0.403	0.0	36.3	3672			
8640 min Winter	0.352	0.0	36.9	4392			
10080 min Winter	0.315	0.0	37.1	5056			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:1yr																																		
Date 26/11/2018 12:03 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB01.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>1</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.123 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.123</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	1	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.123
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	1	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.123																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:1yr																																									
Date 26/11/2018 12:03 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB01.SRCX</u> Storage is Online Cover Level (m) 30.590 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>6.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>115.0</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>191.7</td> <td>Slope (1:X)</td> <td>150.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>29.980</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>30.000</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	115.0	Max Percolation (l/s)	191.7	Slope (1:X)	150.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	29.980	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	30.000	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	115.0																																							
Max Percolation (l/s)	191.7	Slope (1:X)	150.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	29.980	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	30.000																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:1yr				
Date 26/11/2018 12:03 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.020	0.000	0.0	0.3	0.3	0.0	O K
10080 min Summer	30.020	0.000	0.0	0.3	0.3	0.0	O K
15 min Winter	30.020	0.000	0.0	18.2	18.2	0.0	O K
30 min Winter	30.020	0.000	0.0	13.7	13.7	0.0	O K
60 min Winter	30.020	0.000	0.0	9.0	9.0	0.0	O K
120 min Winter	30.020	0.000	0.0	5.6	5.6	0.0	O K
180 min Winter	30.020	0.000	0.0	4.2	4.2	0.0	O K
240 min Winter	30.020	0.000	0.0	3.5	3.5	0.0	O K
360 min Winter	30.020	0.000	0.0	2.6	2.6	0.0	O K
480 min Winter	30.020	0.000	0.0	2.1	2.1	0.0	O K
600 min Winter	30.020	0.000	0.0	1.8	1.8	0.0	O K
720 min Winter	30.020	0.000	0.0	1.5	1.5	0.0	O K
960 min Winter	30.020	0.000	0.0	1.2	1.2	0.0	O K
1440 min Winter	30.020	0.000	0.0	0.9	0.9	0.0	O K
2160 min Winter	30.020	0.000	0.0	0.7	0.7	0.0	O K
2880 min Winter	30.020	0.000	0.0	0.5	0.5	0.0	O K
4320 min Winter	30.020	0.000	0.0	0.4	0.4	0.0	O K
5760 min Winter	30.020	0.000	0.0	0.3	0.3	0.0	O K
7200 min Winter	30.020	0.000	0.0	0.3	0.3	0.0	O K
8640 min Winter	30.020	0.000	0.0	0.2	0.2	0.0	O K
10080 min Winter	30.020	0.000	0.0	0.2	0.2	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.352	0.0	32.0	0			
10080 min Summer	0.315	0.0	32.1	0			
15 min Winter	31.332	0.0	4.9	0			
30 min Winter	20.391	0.0	7.3	0			
60 min Winter	12.872	0.0	10.0	0			
120 min Winter	7.960	0.0	13.0	0			
180 min Winter	5.980	0.0	15.0	0			
240 min Winter	4.876	0.0	16.5	0			
360 min Winter	3.634	0.0	18.7	0			
480 min Winter	2.942	0.0	20.3	0			
600 min Winter	2.497	0.0	21.6	0			
720 min Winter	2.184	0.0	22.7	0			
960 min Winter	1.768	0.0	24.5	0			
1440 min Winter	1.313	0.0	27.2	0			
2160 min Winter	0.975	0.0	29.9	0			
2880 min Winter	0.789	0.0	31.8	0			
4320 min Winter	0.586	0.0	34.4	0			
5760 min Winter	0.474	0.0	36.0	0			
7200 min Winter	0.403	0.0	37.1	0			
8640 min Winter	0.352	0.0	37.8	0			
10080 min Winter	0.315	0.0	38.3	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:1yr																																		
Date 26/11/2018 12:03 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB02.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>1</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.121 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.121</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	1	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.121
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	1	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.121																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:1yr																																									
Date 26/11/2018 12:03 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB02.SRCX</u> Storage is Online Cover Level (m) 30.630 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>8.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>76.3</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>169.6</td> <td>Slope (1:X)</td> <td>40.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>30.020</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>28.850</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0	Membrane Percolation (mm/hr)	1000	Length (m)	76.3	Max Percolation (l/s)	169.6	Slope (1:X)	40.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	30.020	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	28.850	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	76.3																																							
Max Percolation (l/s)	169.6	Slope (1:X)	40.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	30.020	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	28.850																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited							Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:30yr				
Date 26/11/2018 12:08 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Upstream Structures			Outflow To		Overflow To		
(None)			Hydrobrake-02.SRCX		(None)		
Half Drain Time : 317 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E (l/s)	Max Outflow Volume (m³)	Status
15 min Summer	34.632	0.032		0.0	0.6	0.6	33.2 O K
30 min Summer	34.642	0.042		0.0	1.0	1.0	44.0 O K
60 min Summer	34.652	0.052		0.0	1.6	1.6	55.0 O K
120 min Summer	34.663	0.063		0.0	2.2	2.2	65.7 O K
180 min Summer	34.667	0.067		0.0	2.5	2.5	70.1 O K
240 min Summer	34.668	0.068		0.0	2.5	2.5	71.5 O K
360 min Summer	34.669	0.069		0.0	2.6	2.6	73.1 O K
480 min Summer	34.670	0.070		0.0	2.7	2.7	74.0 O K
600 min Summer	34.671	0.071		0.0	2.8	2.8	74.4 O K
720 min Summer	34.671	0.071		0.0	2.8	2.8	74.4 O K
960 min Summer	34.670	0.070		0.0	2.7	2.7	73.9 O K
1440 min Summer	34.668	0.068		0.0	2.6	2.6	71.7 O K
2160 min Summer	34.664	0.064		0.0	2.3	2.3	67.7 O K
2880 min Summer	34.661	0.061		0.0	2.1	2.1	64.0 O K
4320 min Summer	34.655	0.055		0.0	1.8	1.8	58.1 O K
5760 min Summer	34.651	0.051		0.0	1.5	1.5	53.8 O K
7200 min Summer	34.648	0.048		0.0	1.3	1.3	50.4 O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	76.886	0.0	22.8	69			
30 min Summer	49.908	0.0	33.4	72			
60 min Summer	30.968	0.0	52.0	86			
120 min Summer	18.650	0.0	65.2	124			
180 min Summer	13.718	0.0	73.1	182			
240 min Summer	10.984	0.0	78.8	226			
360 min Summer	8.013	0.0	87.1	282			
480 min Summer	6.403	0.0	93.3	344			
600 min Summer	5.378	0.0	98.2	408			
720 min Summer	4.662	0.0	102.2	476			
960 min Summer	3.719	0.0	108.5	608			
1440 min Summer	2.701	0.0	116.7	874			
2160 min Summer	1.960	0.0	134.7	1256			
2880 min Summer	1.560	0.0	141.4	1640			
4320 min Summer	1.130	0.0	149.1	2376			
5760 min Summer	0.898	0.0	162.7	3112			
7200 min Summer	0.751	0.0	167.1	3864			
©1982-2017 XP Solutions							

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:30yr				
Date 26/11/2018 12:08 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.645	0.045	0.0	1.2	1.2	47.5	O K
10080 min Summer	34.643	0.043	0.0	1.1	1.1	45.0	O K
15 min Winter	34.636	0.036	0.0	0.8	0.8	37.5	O K
30 min Winter	34.647	0.047	0.0	1.3	1.3	49.6	O K
60 min Winter	34.659	0.059	0.0	2.0	2.0	61.8	O K
120 min Winter	34.670	0.070	0.0	2.7	2.7	73.7	O K
180 min Winter	34.674	0.074	0.0	3.1	3.1	78.3	O K
240 min Winter	34.676	0.076	0.0	3.3	3.3	79.6	O K
360 min Winter	34.677	0.077	0.0	3.4	3.4	80.7	O K
480 min Winter	34.677	0.077	0.0	3.4	3.4	81.0	O K
600 min Winter	34.677	0.077	0.0	3.4	3.4	80.6	O K
720 min Winter	34.676	0.076	0.0	3.3	3.3	79.9	O K
960 min Winter	34.674	0.074	0.0	3.1	3.1	78.0	O K
1440 min Winter	34.670	0.070	0.0	2.7	2.7	73.7	O K
2160 min Winter	34.664	0.064	0.0	2.3	2.3	67.4	O K
2880 min Winter	34.659	0.059	0.0	2.0	2.0	62.4	O K
4320 min Winter	34.652	0.052	0.0	1.6	1.6	55.1	O K
5760 min Winter	34.648	0.048	0.0	1.3	1.3	50.2	O K
7200 min Winter	34.644	0.044	0.0	1.1	1.1	46.3	O K
8640 min Winter	34.641	0.041	0.0	1.0	1.0	43.0	O K
10080 min Winter	34.638	0.038	0.0	0.9	0.9	40.5	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.649	0.0	169.9	4584			
10080 min Summer	0.574	0.0	170.9	5344			
15 min Winter	76.886	0.0	27.0	66			
30 min Winter	49.908	0.0	39.2	70			
60 min Winter	30.968	0.0	59.9	84			
120 min Winter	18.650	0.0	74.7	122			
180 min Winter	13.718	0.0	83.6	176			
240 min Winter	10.984	0.0	90.0	224			
360 min Winter	8.013	0.0	99.4	282			
480 min Winter	6.403	0.0	106.4	354			
600 min Winter	5.378	0.0	112.0	428			
720 min Winter	4.662	0.0	116.5	500			
960 min Winter	3.719	0.0	123.7	638			
1440 min Winter	2.701	0.0	133.2	918			
2160 min Winter	1.960	0.0	152.9	1316			
2880 min Winter	1.560	0.0	160.8	1700			
4320 min Winter	1.130	0.0	170.1	2464			
5760 min Winter	0.898	0.0	185.2	3200			
7200 min Winter	0.751	0.0	190.7	3968			
8640 min Winter	0.649	0.0	194.5	4680			
10080 min Winter	0.574	0.0	196.3	5448			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:30yr	
Date 26/11/2018 12:08 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for BlueRoof-01.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m²)	1107	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)
0	4	0.020116	32	36	0.004061	64	68	0.000820	96	100	0.000166
4	8	0.016470	36	40	0.003325	68	72	0.000671	100	104	0.000136
8	12	0.013484	40	44	0.002722	72	76	0.000550	104	108	0.000111
12	16	0.011040	44	48	0.002229	76	80	0.000450	108	112	0.000091
16	20	0.009039	48	52	0.001825	80	84	0.000368	112	116	0.000074
20	24	0.007400	52	56	0.001494	84	88	0.000302	116	120	0.000061
24	28	0.006059	56	60	0.001223	88	92	0.000247			
28	32	0.004961	60	64	0.001002	92	96	0.000202			

Time Area Diagram

Total Area (ha) 0.176

Time (mins) From:	To:	Area (ha)
0	4	0.176

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:30yr	
Date 26/11/2018 12:08 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-01.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	1107.0	1107.0	1.300	0.0	1127.0
0.100	1107.0	1120.3	1.400	0.0	1127.0
0.200	0.0	1127.0	1.500	0.0	1127.0
0.300	0.0	1127.0	1.600	0.0	1127.0
0.400	0.0	1127.0	1.700	0.0	1127.0
0.500	0.0	1127.0	1.800	0.0	1127.0
0.600	0.0	1127.0	1.900	0.0	1127.0
0.700	0.0	1127.0	2.000	0.0	1127.0
0.800	0.0	1127.0	2.100	0.0	1127.0
0.900	0.0	1127.0	2.200	0.0	1127.0
1.000	0.0	1127.0	2.300	0.0	1127.0
1.100	0.0	1127.0	2.400	0.0	1127.0
1.200	0.0	1127.0	2.500	0.0	1127.0

Pipe Outflow Control

Diameter (m) 0.150 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

©1982-2017 XP Solutions

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 02 1:30yr				
Date 26/11/2018 12:08 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.634	0.034	0.0	0.5	0.5	20.6	O K
10080 min Summer	34.632	0.032	0.0	0.5	0.5	19.5	O K
15 min Winter	34.627	0.027	0.0	0.4	0.4	16.4	O K
30 min Winter	34.636	0.036	0.0	0.6	0.6	21.8	O K
60 min Winter	34.645	0.045	0.0	0.9	0.9	27.3	O K
120 min Winter	34.654	0.054	0.0	1.4	1.4	32.5	O K
180 min Winter	34.657	0.057	0.0	1.5	1.5	34.5	O K
240 min Winter	34.658	0.058	0.0	1.6	1.6	35.1	O K
360 min Winter	34.659	0.059	0.0	1.7	1.7	35.6	O K
480 min Winter	34.659	0.059	0.0	1.7	1.7	35.6	O K
600 min Winter	34.658	0.058	0.0	1.6	1.6	35.4	O K
720 min Winter	34.658	0.058	0.0	1.6	1.6	35.0	O K
960 min Winter	34.656	0.056	0.0	1.5	1.5	34.0	O K
1440 min Winter	34.653	0.053	0.0	1.3	1.3	32.0	O K
2160 min Winter	34.649	0.049	0.0	1.1	1.1	29.5	O K
2880 min Winter	34.645	0.045	0.0	0.9	0.9	27.4	O K
4320 min Winter	34.639	0.039	0.0	0.7	0.7	24.0	O K
5760 min Winter	34.636	0.036	0.0	0.6	0.6	21.6	O K
7200 min Winter	34.633	0.033	0.0	0.5	0.5	20.0	O K
8640 min Winter	34.631	0.031	0.0	0.4	0.4	18.7	O K
10080 min Winter	34.629	0.029	0.0	0.4	0.4	17.5	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.649	0.0	74.7	4584			
10080 min Summer	0.574	0.0	74.9	5336			
15 min Winter	76.886	0.0	12.1	70			
30 min Winter	49.908	0.0	17.7	74			
60 min Winter	30.968	0.0	27.0	88			
120 min Winter	18.650	0.0	33.8	124			
180 min Winter	13.718	0.0	37.9	176			
240 min Winter	10.984	0.0	40.8	222			
360 min Winter	8.013	0.0	45.0	280			
480 min Winter	6.403	0.0	48.2	352			
600 min Winter	5.378	0.0	50.7	424			
720 min Winter	4.662	0.0	52.8	494			
960 min Winter	3.719	0.0	56.0	634			
1440 min Winter	2.701	0.0	60.3	906			
2160 min Winter	1.960	0.0	68.8	1300			
2880 min Winter	1.560	0.0	72.3	1700			
4320 min Winter	1.130	0.0	76.2	2460			
5760 min Winter	0.898	0.0	82.5	3176			
7200 min Winter	0.751	0.0	84.7	3960			
8640 min Winter	0.649	0.0	86.0	4680			
10080 min Winter	0.574	0.0	86.6	5448			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:30yr	
Date 26/11/2018 12:08 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for BlueRoof-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m³)	639	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)
0	4	0.011612	32	36	0.002344	64	68	0.000473	96	100	0.000096
4	8	0.009507	36	40	0.001919	68	72	0.000388	100	104	0.000078
8	12	0.007784	40	44	0.001571	72	76	0.000317	104	108	0.000064
12	16	0.006373	44	48	0.001287	76	80	0.000260	108	112	0.000052
16	20	0.005218	48	52	0.001053	80	84	0.000213	112	116	0.000043
20	24	0.004272	52	56	0.000862	84	88	0.000174	116	120	0.000035
24	28	0.003497	56	60	0.000706	88	92	0.000143			
28	32	0.002863	60	64	0.000578	92	96	0.000117			

Time Area Diagram

Total Area (ha) 0.067

Time (mins) From:	To:	Area (ha)
0	4	0.067

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:30yr	
Date 26/11/2018 12:08 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-02.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	639.0	639.0	1.300	0.0	654.2
0.100	639.0	649.1	1.400	0.0	654.2
0.200	0.0	654.2	1.500	0.0	654.2
0.300	0.0	654.2	1.600	0.0	654.2
0.400	0.0	654.2	1.700	0.0	654.2
0.500	0.0	654.2	1.800	0.0	654.2
0.600	0.0	654.2	1.900	0.0	654.2
0.700	0.0	654.2	2.000	0.0	654.2
0.800	0.0	654.2	2.100	0.0	654.2
0.900	0.0	654.2	2.200	0.0	654.2
1.000	0.0	654.2	2.300	0.0	654.2
1.100	0.0	654.2	2.400	0.0	654.2
1.200	0.0	654.2	2.500	0.0	654.2

Pipe Outflow Control

Diameter (m) 0.100 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 01 1:30yr				
Date 26/11/2018 12:09 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-01.srcx</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	29.550	0.000	0.0	1.5	1.5	0.0	O K
10080 min Summer	29.550	0.000	0.0	1.3	1.3	0.0	O K
15 min Winter	29.743	0.193	0.0	4.0	4.0	35.7	O K
30 min Winter	29.805	0.255	0.0	4.0	4.0	47.2	O K
60 min Winter	29.856	0.306	0.0	4.0	4.0	56.7	O K
120 min Winter	29.879	0.329	0.0	4.0	4.0	61.0	O K
180 min Winter	29.874	0.324	0.0	4.0	4.0	60.1	O K
240 min Winter	29.859	0.309	0.0	4.0	4.0	57.2	O K
360 min Winter	29.825	0.275	0.0	4.0	4.0	50.9	O K
480 min Winter	29.789	0.239	0.0	4.0	4.0	44.2	O K
600 min Winter	29.753	0.203	0.0	4.0	4.0	37.6	O K
720 min Winter	29.718	0.168	0.0	4.0	4.0	31.2	O K
960 min Winter	29.657	0.107	0.0	4.0	4.0	19.9	O K
1440 min Winter	29.572	0.022	0.0	4.0	4.0	4.1	O K
2160 min Winter	29.550	0.000	0.0	3.3	3.3	0.0	O K
2880 min Winter	29.550	0.000	0.0	2.7	2.7	0.0	O K
4320 min Winter	29.550	0.000	0.0	1.9	1.9	0.0	O K
5760 min Winter	29.550	0.000	0.0	1.5	1.5	0.0	O K
7200 min Winter	29.550	0.000	0.0	1.3	1.3	0.0	O K
8640 min Winter	29.550	0.000	0.0	1.1	1.1	0.0	O K
10080 min Winter	29.550	0.000	0.0	1.0	1.0	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.649	0.0	187.4	0			
10080 min Summer	0.574	0.0	191.7	0			
15 min Winter	76.886	0.0	43.1	27			
30 min Winter	49.908	0.0	57.2	39			
60 min Winter	30.968	0.0	71.8	62			
120 min Winter	18.650	0.0	86.9	118			
180 min Winter	13.718	0.0	96.1	172			
240 min Winter	10.984	0.0	102.9	196			
360 min Winter	8.013	0.0	113.0	270			
480 min Winter	6.403	0.0	120.7	342			
600 min Winter	5.378	0.0	126.7	412			
720 min Winter	4.662	0.0	131.5	478			
960 min Winter	3.719	0.0	139.9	604			
1440 min Winter	2.701	0.0	152.2	810			
2160 min Winter	1.960	0.0	165.3	0			
2880 min Winter	1.560	0.0	174.8	0			
4320 min Winter	1.130	0.0	188.5	0			
5760 min Winter	0.898	0.0	198.3	0			
7200 min Winter	0.751	0.0	205.9	0			
8640 min Winter	0.649	0.0	212.0	0			
10080 min Winter	0.574	0.0	217.1	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-01.srcx

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.167

Time (mins)	Area
From:	To: (ha)
0	4 0.167

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-01.srcx

Storage is Online Cover Level (m) 30.650

Cellular Storage Structure

Invert Level (m) 29.550 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	195.0	195.0	1.300	0.0	242.5
0.100	195.0	200.6	1.400	0.0	242.5
0.200	195.0	206.2	1.500	0.0	242.5
0.300	195.0	211.8	1.600	0.0	242.5
0.400	195.0	217.3	1.700	0.0	242.5
0.500	195.0	222.9	1.800	0.0	242.5
0.600	195.0	228.5	1.900	0.0	242.5
0.700	195.0	234.1	2.000	0.0	242.5
0.800	195.0	239.7	2.100	0.0	242.5
0.900	0.0	242.5	2.200	0.0	242.5
1.000	0.0	242.5	2.300	0.0	242.5
1.100	0.0	242.5	2.400	0.0	242.5
1.200	0.0	242.5	2.500	0.0	242.5

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0095-4000-1000-4000
Design Head (m) 1.000
Design Flow (l/s) 4.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 95
Invert Level (m) 29.310
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	4.0
Flush-Flo™	0.294	4.0
Kick-Flo®	0.629	3.2
Mean Flow over Head Range	-	3.5

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.0	1.200	4.3	3.000	6.7	7.000	10.0
0.200	3.9	1.400	4.7	3.500	7.2	7.500	10.3
0.300	4.0	1.600	5.0	4.000	7.6	8.000	10.6
0.400	3.9	1.800	5.3	4.500	8.1	8.500	10.9
0.500	3.8	2.000	5.5	5.000	8.5	9.000	11.2
0.600	3.4	2.200	5.8	5.500	8.9	9.500	11.5
0.800	3.6	2.400	6.0	6.000	9.3		
1.000	4.0	2.600	6.2	6.500	9.6		

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 02 1:30yr				
Date 26/11/2018 12:09 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
7200 min Summer	29.352	0.002	0.0	3.6	3.6	0.8	O K
8640 min Summer	29.350	0.000	0.0	3.3	3.3	0.0	O K
10080 min Summer	29.350	0.000	0.0	3.0	3.0	0.0	O K
15 min Winter	29.438	0.088	0.0	7.8	7.8	42.7	O K
30 min Winter	29.460	0.110	0.0	7.9	7.9	53.5	O K
60 min Winter	29.477	0.127	0.0	8.0	8.0	61.3	O K
120 min Winter	29.483	0.133	0.0	8.0	8.0	64.5	O K
180 min Winter	29.482	0.132	0.0	8.0	8.0	64.0	O K
240 min Winter	29.478	0.128	0.0	8.0	8.0	62.0	O K
360 min Winter	29.467	0.117	0.0	7.9	7.9	56.9	O K
480 min Winter	29.458	0.108	0.0	7.9	7.9	52.5	O K
600 min Winter	29.449	0.099	0.0	7.9	7.9	48.1	O K
720 min Winter	29.441	0.091	0.0	7.9	7.9	43.9	O K
960 min Winter	29.425	0.075	0.0	7.8	7.8	36.3	O K
1440 min Winter	29.405	0.055	0.0	7.1	7.1	26.8	O K
2160 min Winter	29.387	0.037	0.0	6.1	6.1	18.0	O K
2880 min Winter	29.375	0.025	0.0	5.3	5.3	12.2	O K
4320 min Winter	29.360	0.010	0.0	4.2	4.2	4.8	O K
5760 min Winter	29.350	0.000	0.0	3.5	3.5	0.0	O K
7200 min Winter	29.350	0.000	0.0	3.0	3.0	0.0	O K
8640 min Winter	29.350	0.000	0.0	2.6	2.6	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
7200 min Summer	0.751	0.0	445.1	3752			
8640 min Summer	0.649	0.0	455.0	0			
10080 min Summer	0.574	0.0	461.3	0			
15 min Winter	76.886	0.0	87.5	17			
30 min Winter	49.908	0.0	120.6	31			
60 min Winter	30.968	0.0	166.9	60			
120 min Winter	18.650	0.0	205.3	118			
180 min Winter	13.718	0.0	228.6	174			
240 min Winter	10.984	0.0	245.2	228			
360 min Winter	8.013	0.0	270.0	288			
480 min Winter	6.403	0.0	288.4	364			
600 min Winter	5.378	0.0	303.2	440			
720 min Winter	4.662	0.0	315.6	512			
960 min Winter	3.719	0.0	335.2	646			
1440 min Winter	2.701	0.0	362.6	908			
2160 min Winter	1.960	0.0	405.4	1296			
2880 min Winter	1.560	0.0	427.3	1672			
4320 min Winter	1.130	0.0	456.1	2420			
5760 min Winter	0.898	0.0	489.1	3120			
7200 min Winter	0.751	0.0	505.6	0			
8640 min Winter	0.649	0.0	517.9	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-02.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
10080 min Winter	29.350	0.000	0.0	2.3	2.3	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
10080 min Winter	0.574	0.0	526.4	0

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.199

Time (mins)	Area
From:	To: (ha)

0	4 0.199
---	---------

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-02.SRCX

Storage is Online Cover Level (m) 30.630

Cellular Storage Structure

Invert Level (m) 29.350 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	510.0	510.0	1.300	0.0	559.7
0.100	510.0	519.0	1.400	0.0	559.7
0.200	510.0	528.1	1.500	0.0	559.7
0.300	510.0	537.1	1.600	0.0	559.7
0.400	510.0	546.1	1.700	0.0	559.7
0.500	510.0	555.2	1.800	0.0	559.7
0.600	0.0	559.7	1.900	0.0	559.7
0.700	0.0	559.7	2.000	0.0	559.7
0.800	0.0	559.7	2.100	0.0	559.7
0.900	0.0	559.7	2.200	0.0	559.7
1.000	0.0	559.7	2.300	0.0	559.7
1.100	0.0	559.7	2.400	0.0	559.7
1.200	0.0	559.7	2.500	0.0	559.7

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0136-8000-0680-8000
Design Head (m) 0.680
Design Flow (l/s) 8.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 136
Invert Level (m) 29.270
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.680	8.0
Flush-Flo™	0.231	8.0
Kick-Flo®	0.492	6.9
Mean Flow over Head Range	-	6.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:30yr	
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.9	1.200	10.4	3.000	16.1	7.000	24.1
0.200	7.9	1.400	11.2	3.500	17.4	7.500	25.0
0.300	7.9	1.600	12.0	4.000	18.5	8.000	25.8
0.400	7.6	1.800	12.6	4.500	19.6	8.500	26.6
0.500	6.9	2.000	13.3	5.000	20.6	9.000	27.4
0.600	7.5	2.200	13.9	5.500	21.6	9.500	28.1
0.800	8.6	2.400	14.5	6.000	22.5		
1.000	9.6	2.600	15.1	6.500	23.4		

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 03 1:30yr				
Date 26/11/2018 14:25 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
5760 min Summer	29.055	0.105	0.0	6.0	6.0	31.0	O K
7200 min Summer	28.997	0.047	0.0	5.9	5.9	13.9	O K
8640 min Summer	28.975	0.025	0.0	5.5	5.5	7.5	O K
10080 min Summer	28.964	0.014	0.0	5.0	5.0	4.1	O K
15 min Winter	29.183	0.233	0.0	6.0	6.0	69.1	O K
30 min Winter	29.287	0.337	0.0	6.0	6.0	99.9	O K
60 min Winter	29.401	0.451	0.0	6.0	6.0	133.5	O K
120 min Winter	29.492	0.542	0.0	7.1	7.1	160.7	O K
180 min Winter	29.515	0.565	0.0	8.5	8.5	167.6	O K
240 min Winter	29.526	0.576	0.0	9.4	9.4	170.7	O K
360 min Winter	29.539	0.589	0.0	10.2	10.2	174.7	O K
480 min Winter	29.547	0.597	0.0	10.8	10.8	177.0	O K
600 min Winter	29.554	0.604	0.0	11.3	11.3	179.2	O K
720 min Winter	29.557	0.607	0.0	11.6	11.6	180.0	O K
960 min Winter	29.551	0.601	0.0	11.0	11.0	178.3	O K
1440 min Winter	29.516	0.566	0.0	8.6	8.6	167.7	O K
2160 min Winter	29.463	0.513	0.0	6.2	6.2	151.9	O K
2880 min Winter	29.351	0.401	0.0	6.0	6.0	118.8	O K
4320 min Winter	29.088	0.138	0.0	6.0	6.0	40.8	O K
5760 min Winter	28.983	0.033	0.0	5.8	5.8	9.8	O K
7200 min Winter	28.964	0.014	0.0	5.0	5.0	4.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
5760 min Summer	0.898	0.0	728.5	3224			
7200 min Summer	0.751	0.0	754.1	3816			
8640 min Summer	0.649	0.0	774.0	4416			
10080 min Summer	0.574	0.0	788.8	5144			
15 min Winter	76.886	0.0	160.7	166			
30 min Winter	49.908	0.0	217.2	244			
60 min Winter	30.968	0.0	287.6	310			
120 min Winter	18.650	0.0	351.0	384			
180 min Winter	13.718	0.0	389.4	416			
240 min Winter	10.984	0.0	417.6	436			
360 min Winter	8.013	0.0	458.9	496			
480 min Winter	6.403	0.0	490.1	556			
600 min Winter	5.378	0.0	514.8	606			
720 min Winter	4.662	0.0	535.5	686			
960 min Winter	3.719	0.0	568.8	784			
1440 min Winter	2.701	0.0	617.1	1048			
2160 min Winter	1.960	0.0	681.5	1576			
2880 min Winter	1.560	0.0	720.2	2020			
4320 min Winter	1.130	0.0	773.0	2644			
5760 min Winter	0.898	0.0	823.5	3104			
7200 min Winter	0.751	0.0	853.7	3816			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:30yr	
Date 26/11/2018 14:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-03.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
8640 min Winter	28.951	0.001	0.0	4.4	4.4	0.3	O K
10080 min Winter	28.950	0.000	0.0	3.9	3.9	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
8640 min Winter	0.649	0.0	877.6	4440
10080 min Winter	0.574	0.0	895.7	0

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:30yr	
Date 26/11/2018 14:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-03.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.188

Time (mins)	Area
From:	To: (ha)

0	4 0.188
---	---------

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:30yr	
Date 26/11/2018 14:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-03.SRCX

Storage is Online Cover Level (m) 30.550

Cellular Storage Structure

Invert Level (m) 28.950 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	312.0	312.0	1.300	0.0	372.1
0.100	312.0	319.1	1.400	0.0	372.1
0.200	312.0	326.1	1.500	0.0	372.1
0.300	312.0	333.2	1.600	0.0	372.1
0.400	312.0	340.3	1.700	0.0	372.1
0.500	312.0	347.3	1.800	0.0	372.1
0.600	312.0	354.4	1.900	0.0	372.1
0.700	312.0	361.5	2.000	0.0	372.1
0.800	312.0	368.5	2.100	0.0	372.1
0.900	0.0	372.1	2.200	0.0	372.1
1.000	0.0	372.1	2.300	0.0	372.1
1.100	0.0	372.1	2.400	0.0	372.1
1.200	0.0	372.1	2.500	0.0	372.1

Complex Outflow Control

Hydro-Brake® Optimum

Unit Reference MD-SHE-0121-6000-0600-6000
Design Head (m) 0.600
Design Flow (l/s) 6.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 121
Invert Level (m) 28.850
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.600	6.0
Flush-Flo™	0.202	6.0
Kick-Flo®	0.435	5.2
Mean Flow over Head Range	-	5.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:30yr	
Date 26/11/2018 14:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.3	1.200	8.3	3.000	12.8	7.000	19.2
0.200	6.0	1.400	8.9	3.500	13.8	7.500	19.9
0.300	5.9	1.600	9.5	4.000	14.7	8.000	20.5
0.400	5.5	1.800	10.0	4.500	15.5	8.500	21.1
0.500	5.5	2.000	10.6	5.000	16.3	9.000	21.8
0.600	6.0	2.200	11.0	5.500	17.1	9.500	22.4
0.800	6.9	2.400	11.5	6.000	17.8		
1.000	7.6	2.600	12.0	6.500	18.5		

Orifice

Diameter (m) 0.125 Discharge Coefficient 0.600 Invert Level (m) 29.450

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB01 1:30yr				
Date 26/11/2018 12:09 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.033	0.053	0.0	0.6	0.6	0.4	O K
10080 min Summer	30.031	0.051	0.0	0.6	0.6	0.3	O K
15 min Winter	30.238	0.258	0.0	18.9	18.9	9.0	O K
30 min Winter	30.240	0.260	0.0	19.1	19.1	9.2	O K
60 min Winter	30.211	0.231	0.0	17.1	17.1	7.2	O K
120 min Winter	30.168	0.188	0.0	12.3	12.3	4.8	O K
180 min Winter	30.142	0.162	0.0	9.5	9.5	3.6	O K
240 min Winter	30.126	0.146	0.0	7.7	7.7	2.9	O K
360 min Winter	30.102	0.122	0.0	5.7	5.7	2.0	O K
480 min Winter	30.088	0.108	0.0	4.6	4.6	1.6	O K
600 min Winter	30.081	0.101	0.0	3.9	3.9	1.4	O K
720 min Winter	30.077	0.097	0.0	3.4	3.4	1.3	O K
960 min Winter	30.070	0.090	0.0	2.7	2.7	1.1	O K
1440 min Winter	30.058	0.078	0.0	1.9	1.9	0.8	O K
2160 min Winter	30.049	0.069	0.0	1.4	1.4	0.6	O K
2880 min Winter	30.044	0.064	0.0	1.1	1.1	0.6	O K
4320 min Winter	30.037	0.057	0.0	0.8	0.8	0.4	O K
5760 min Winter	30.033	0.053	0.0	0.6	0.6	0.4	O K
7200 min Winter	30.030	0.050	0.0	0.5	0.5	0.3	O K
8640 min Winter	30.028	0.048	0.0	0.5	0.5	0.3	O K
10080 min Winter	30.026	0.046	0.0	0.4	0.4	0.3	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.649	0.0	70.3	4264			
10080 min Summer	0.574	0.0	70.9	5120			
15 min Winter	76.886	0.0	16.3	13			
30 min Winter	49.908	0.0	22.2	22			
60 min Winter	30.968	0.0	28.4	38			
120 min Winter	18.650	0.0	34.9	68			
180 min Winter	13.718	0.0	38.8	98			
240 min Winter	10.984	0.0	41.5	128			
360 min Winter	8.013	0.0	45.6	188			
480 min Winter	6.403	0.0	48.7	248			
600 min Winter	5.378	0.0	51.2	308			
720 min Winter	4.662	0.0	53.3	364			
960 min Winter	3.719	0.0	56.6	490			
1440 min Winter	2.701	0.0	61.4	722			
2160 min Winter	1.960	0.0	66.3	1096			
2880 min Winter	1.560	0.0	69.7	1464			
4320 min Winter	1.130	0.0	74.4	2196			
5760 min Winter	0.898	0.0	77.4	2920			
7200 min Winter	0.751	0.0	79.4	3552			
8640 min Winter	0.649	0.0	80.9	4344			
10080 min Winter	0.574	0.0	81.9	5200			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:30yr																																		
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB01.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>30</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.123 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.123</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	30	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.123
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	30	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.123																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:30yr																																									
Date 26/11/2018 12:09 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB01.SRCX</u> Storage is Online Cover Level (m) 30.590 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>6.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>115.0</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>191.7</td> <td>Slope (1:X)</td> <td>150.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>29.980</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>30.000</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	115.0	Max Percolation (l/s)	191.7	Slope (1:X)	150.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	29.980	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	30.000	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	115.0																																							
Max Percolation (l/s)	191.7	Slope (1:X)	150.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	29.980	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	30.000																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited							Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:30yr				
Date 26/11/2018 12:10 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Upstream Structures			Outflow To		Overflow To		
(None)			Hydrobrake-02.SRCX		(None)		
Half Drain Time : 0 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E (l/s)	Max Outflow Volume (m³)	Status
15 min Summer	30.020	0.000	0.0	44.7	44.7	0.0	O K
30 min Summer	30.020	0.000	0.0	38.7	38.7	0.0	O K
60 min Summer	30.020	0.000	0.0	27.6	27.6	0.0	O K
120 min Summer	30.020	0.000	0.0	17.8	17.8	0.0	O K
180 min Summer	30.020	0.000	0.0	13.4	13.4	0.0	O K
240 min Summer	30.020	0.000	0.0	10.8	10.8	0.0	O K
360 min Summer	30.020	0.000	0.0	7.9	7.9	0.0	O K
480 min Summer	30.020	0.000	0.0	6.3	6.3	0.0	O K
600 min Summer	30.020	0.000	0.0	5.3	5.3	0.0	O K
720 min Summer	30.020	0.000	0.0	4.6	4.6	0.0	O K
960 min Summer	30.020	0.000	0.0	3.7	3.7	0.0	O K
1440 min Summer	30.020	0.000	0.0	2.6	2.6	0.0	O K
2160 min Summer	30.020	0.000	0.0	1.9	1.9	0.0	O K
2880 min Summer	30.020	0.000	0.0	1.5	1.5	0.0	O K
4320 min Summer	30.020	0.000	0.0	1.1	1.1	0.0	O K
5760 min Summer	30.020	0.000	0.0	0.9	0.9	0.0	O K
7200 min Summer	30.020	0.000	0.0	0.7	0.7	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	76.886	0.0	14.4	0			
30 min Summer	49.908	0.0	19.6	0			
60 min Summer	30.968	0.0	25.0	0			
120 min Summer	18.650	0.0	30.6	0			
180 min Summer	13.718	0.0	34.1	0			
240 min Summer	10.984	0.0	36.5	0			
360 min Summer	8.013	0.0	40.1	0			
480 min Summer	6.403	0.0	42.8	0			
600 min Summer	5.378	0.0	45.0	0			
720 min Summer	4.662	0.0	46.8	0			
960 min Summer	3.719	0.0	49.7	0			
1440 min Summer	2.701	0.0	53.9	0			
2160 min Summer	1.960	0.0	58.2	0			
2880 min Summer	1.560	0.0	61.2	0			
4320 min Summer	1.130	0.0	65.3	0			
5760 min Summer	0.898	0.0	67.9	0			
7200 min Summer	0.751	0.0	69.6	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:30yr				
Date 26/11/2018 12:10 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.020	0.000	0.0	0.6	0.6	0.0	O K
10080 min Summer	30.020	0.000	0.0	0.5	0.5	0.0	O K
15 min Winter	30.020	0.000	0.0	44.8	44.8	0.0	O K
30 min Winter	30.020	0.000	0.0	33.5	33.5	0.0	O K
60 min Winter	30.020	0.000	0.0	21.7	21.7	0.0	O K
120 min Winter	30.020	0.000	0.0	13.2	13.2	0.0	O K
180 min Winter	30.020	0.000	0.0	9.8	9.8	0.0	O K
240 min Winter	30.020	0.000	0.0	7.8	7.8	0.0	O K
360 min Winter	30.020	0.000	0.0	5.7	5.7	0.0	O K
480 min Winter	30.020	0.000	0.0	4.6	4.6	0.0	O K
600 min Winter	30.020	0.000	0.0	3.8	3.8	0.0	O K
720 min Winter	30.020	0.000	0.0	3.3	3.3	0.0	O K
960 min Winter	30.020	0.000	0.0	2.6	2.6	0.0	O K
1440 min Winter	30.020	0.000	0.0	1.9	1.9	0.0	O K
2160 min Winter	30.020	0.000	0.0	1.4	1.4	0.0	O K
2880 min Winter	30.020	0.000	0.0	1.1	1.1	0.0	O K
4320 min Winter	30.020	0.000	0.0	0.8	0.8	0.0	O K
5760 min Winter	30.020	0.000	0.0	0.6	0.6	0.0	O K
7200 min Winter	30.020	0.000	0.0	0.5	0.5	0.0	O K
8640 min Winter	30.020	0.000	0.0	0.4	0.4	0.0	O K
10080 min Winter	30.020	0.000	0.0	0.4	0.4	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.649	0.0	70.8	0			
10080 min Summer	0.574	0.0	71.6	0			
15 min Winter	76.886	0.0	16.5	0			
30 min Winter	49.908	0.0	22.3	0			
60 min Winter	30.968	0.0	28.3	0			
120 min Winter	18.650	0.0	34.7	0			
180 min Winter	13.718	0.0	38.5	0			
240 min Winter	10.984	0.0	41.3	0			
360 min Winter	8.013	0.0	45.4	0			
480 min Winter	6.403	0.0	48.4	0			
600 min Winter	5.378	0.0	50.8	0			
720 min Winter	4.662	0.0	52.9	0			
960 min Winter	3.719	0.0	56.2	0			
1440 min Winter	2.701	0.0	61.0	0			
2160 min Winter	1.960	0.0	65.9	0			
2880 min Winter	1.560	0.0	69.4	0			
4320 min Winter	1.130	0.0	74.2	0			
5760 min Winter	0.898	0.0	77.3	0			
7200 min Winter	0.751	0.0	79.6	0			
8640 min Winter	0.649	0.0	81.1	0			
10080 min Winter	0.574	0.0	82.3	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:30yr																																		
Date 26/11/2018 12:10 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB02.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>30</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.121 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.121</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	30	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.121
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	30	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.121																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:30yr																																									
Date 26/11/2018 12:10 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB02.SRCX</u> Storage is Online Cover Level (m) 30.630 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>8.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>76.3</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>169.6</td> <td>Slope (1:X)</td> <td>40.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>30.020</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>28.850</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0	Membrane Percolation (mm/hr)	1000	Length (m)	76.3	Max Percolation (l/s)	169.6	Slope (1:X)	40.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	30.020	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	28.850	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	76.3																																							
Max Percolation (l/s)	169.6	Slope (1:X)	40.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	30.020	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	28.850																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:100yr				
Date 26/11/2018 12:18 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.651	0.051	0.0	1.5	1.5	53.7	O K
10080 min Summer	34.648	0.048	0.0	1.3	1.3	50.9	O K
15 min Winter	34.647	0.047	0.0	1.3	1.3	49.6	O K
30 min Winter	34.662	0.062	0.0	2.2	2.2	65.3	O K
60 min Winter	34.677	0.077	0.0	3.4	3.4	81.1	O K
120 min Winter	34.691	0.091	0.0	4.8	4.8	95.3	O K
180 min Winter	34.695	0.095	0.0	5.1	5.1	99.4	O K
240 min Winter	34.695	0.095	0.0	5.1	5.1	100.1	O K
360 min Winter	34.696	0.096	0.0	5.2	5.2	100.8	O K
480 min Winter	34.695	0.095	0.0	5.1	5.1	100.0	O K
600 min Winter	34.694	0.094	0.0	5.0	5.0	98.5	O K
720 min Winter	34.692	0.092	0.0	4.9	4.9	96.7	O K
960 min Winter	34.688	0.088	0.0	4.6	4.6	92.8	O K
1440 min Winter	34.682	0.082	0.0	3.9	3.9	86.2	O K
2160 min Winter	34.675	0.075	0.0	3.2	3.2	78.6	O K
2880 min Winter	34.669	0.069	0.0	2.6	2.6	72.7	O K
4320 min Winter	34.660	0.060	0.0	2.0	2.0	62.9	O K
5760 min Winter	34.654	0.054	0.0	1.7	1.7	56.5	O K
7200 min Winter	34.650	0.050	0.0	1.4	1.4	52.1	O K
8640 min Winter	34.646	0.046	0.0	1.2	1.2	48.6	O K
10080 min Winter	34.643	0.043	0.0	1.1	1.1	45.4	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.796	0.0	214.9	4544			
10080 min Summer	0.701	0.0	216.2	5280			
15 min Winter	99.825	0.0	39.3	62			
30 min Winter	65.339	0.0	56.3	65			
60 min Winter	40.718	0.0	83.0	78			
120 min Winter	24.507	0.0	102.6	120			
180 min Winter	17.966	0.0	114.1	172			
240 min Winter	14.329	0.0	122.0	204			
360 min Winter	10.392	0.0	133.6	272			
480 min Winter	8.272	0.0	142.2	344			
600 min Winter	6.925	0.0	149.0	416			
720 min Winter	5.987	0.0	154.6	486			
960 min Winter	4.754	0.0	163.3	622			
1440 min Winter	3.431	0.0	174.8	890			
2160 min Winter	2.471	0.0	197.1	1276			
2880 min Winter	1.956	0.0	206.4	1676			
4320 min Winter	1.405	0.0	217.4	2420			
5760 min Winter	1.110	0.0	234.2	3168			
7200 min Winter	0.925	0.0	240.6	3888			
8640 min Winter	0.796	0.0	244.9	4672			
10080 min Winter	0.701	0.0	247.1	5376			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage Source Control 2017.1.2		

Cascade Rainfall Details for BlueRoof-01.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m²)	1107	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)
0 4	0.020116	32 36	0.004061	64 68	0.000820	96 100	0.000166
4 8	0.016470	36 40	0.003325	68 72	0.000671	100 104	0.000136
8 12	0.013484	40 44	0.002722	72 76	0.000550	104 108	0.000111
12 16	0.011040	44 48	0.002229	76 80	0.000450	108 112	0.000091
16 20	0.009039	48 52	0.001825	80 84	0.000368	112 116	0.000074
20 24	0.007400	52 56	0.001494	84 88	0.000302	116 120	0.000061
24 28	0.006059	56 60	0.001223	88 92	0.000247		
28 32	0.004961	60 64	0.001002	92 96	0.000202		

Time Area Diagram

Total Area (ha) 0.176

Time (mins) From: To:	Area (ha)
0 4	0.176

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-01.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	1107.0	1107.0	1.300	0.0	1127.0
0.100	1107.0	1120.3	1.400	0.0	1127.0
0.200	0.0	1127.0	1.500	0.0	1127.0
0.300	0.0	1127.0	1.600	0.0	1127.0
0.400	0.0	1127.0	1.700	0.0	1127.0
0.500	0.0	1127.0	1.800	0.0	1127.0
0.600	0.0	1127.0	1.900	0.0	1127.0
0.700	0.0	1127.0	2.000	0.0	1127.0
0.800	0.0	1127.0	2.100	0.0	1127.0
0.900	0.0	1127.0	2.200	0.0	1127.0
1.000	0.0	1127.0	2.300	0.0	1127.0
1.100	0.0	1127.0	2.400	0.0	1127.0
1.200	0.0	1127.0	2.500	0.0	1127.0

Pipe Outflow Control

Diameter (m) 0.150 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 02 1:100yr				
Date 26/11/2018 12:18 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.638	0.038	0.0	0.7	0.7	23.3	O K
10080 min Summer	34.636	0.036	0.0	0.6	0.6	22.0	O K
15 min Winter	34.636	0.036	0.0	0.6	0.6	21.8	O K
30 min Winter	34.648	0.048	0.0	1.0	1.0	28.9	O K
60 min Winter	34.659	0.059	0.0	1.7	1.7	35.9	O K
120 min Winter	34.670	0.070	0.0	2.1	2.1	42.4	O K
180 min Winter	34.673	0.073	0.0	2.3	2.3	44.5	O K
240 min Winter	34.674	0.074	0.0	2.3	2.3	44.8	O K
360 min Winter	34.674	0.074	0.0	2.3	2.3	45.1	O K
480 min Winter	34.674	0.074	0.0	2.3	2.3	44.7	O K
600 min Winter	34.672	0.072	0.0	2.2	2.2	44.0	O K
720 min Winter	34.671	0.071	0.0	2.2	2.2	43.1	O K
960 min Winter	34.668	0.068	0.0	2.0	2.0	41.2	O K
1440 min Winter	34.662	0.062	0.0	1.8	1.8	37.7	O K
2160 min Winter	34.656	0.056	0.0	1.5	1.5	33.9	O K
2880 min Winter	34.652	0.052	0.0	1.3	1.3	31.3	O K
4320 min Winter	34.645	0.045	0.0	0.9	0.9	27.6	O K
5760 min Winter	34.641	0.041	0.0	0.8	0.8	24.6	O K
7200 min Winter	34.637	0.037	0.0	0.7	0.7	22.5	O K
8640 min Winter	34.634	0.034	0.0	0.6	0.6	20.9	O K
10080 min Winter	34.632	0.032	0.0	0.5	0.5	19.7	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.796	0.0	95.3	4576			
10080 min Summer	0.701	0.0	95.6	5256			
15 min Winter	99.825	0.0	17.7	65			
30 min Winter	65.339	0.0	25.5	68			
60 min Winter	40.718	0.0	37.6	80			
120 min Winter	24.507	0.0	46.6	122			
180 min Winter	17.966	0.0	51.8	174			
240 min Winter	14.329	0.0	55.4	210			
360 min Winter	10.392	0.0	60.6	276			
480 min Winter	8.272	0.0	64.5	348			
600 min Winter	6.925	0.0	67.6	420			
720 min Winter	5.987	0.0	70.1	490			
960 min Winter	4.754	0.0	74.1	626			
1440 min Winter	3.431	0.0	79.3	884			
2160 min Winter	2.471	0.0	89.0	1272			
2880 min Winter	1.956	0.0	93.1	1644			
4320 min Winter	1.405	0.0	97.8	2424			
5760 min Winter	1.110	0.0	104.9	3168			
7200 min Winter	0.925	0.0	107.4	3880			
8640 min Winter	0.796	0.0	109.1	4664			
10080 min Winter	0.701	0.0	109.8	5376			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for BlueRoof-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Green Roof

Area (m³)	639	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)	Time (mins) From:	To:	Area (ha)
0	4	0.011612	32	36	0.002344	64	68	0.000473	96	100	0.000096
4	8	0.009507	36	40	0.001919	68	72	0.000388	100	104	0.000078
8	12	0.007784	40	44	0.001571	72	76	0.000317	104	108	0.000064
12	16	0.006373	44	48	0.001287	76	80	0.000260	108	112	0.000052
16	20	0.005218	48	52	0.001053	80	84	0.000213	112	116	0.000043
20	24	0.004272	52	56	0.000862	84	88	0.000174	116	120	0.000035
24	28	0.003497	56	60	0.000706	88	92	0.000143			
28	32	0.002863	60	64	0.000578	92	96	0.000117			

Time Area Diagram

Total Area (ha) 0.067

Time (mins) From:	To:	Area (ha)
0	4	0.067

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 02 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-02.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	639.0	639.0	1.300	0.0	654.2
0.100	639.0	649.1	1.400	0.0	654.2
0.200	0.0	654.2	1.500	0.0	654.2
0.300	0.0	654.2	1.600	0.0	654.2
0.400	0.0	654.2	1.700	0.0	654.2
0.500	0.0	654.2	1.800	0.0	654.2
0.600	0.0	654.2	1.900	0.0	654.2
0.700	0.0	654.2	2.000	0.0	654.2
0.800	0.0	654.2	2.100	0.0	654.2
0.900	0.0	654.2	2.200	0.0	654.2
1.000	0.0	654.2	2.300	0.0	654.2
1.100	0.0	654.2	2.400	0.0	654.2
1.200	0.0	654.2	2.500	0.0	654.2

Pipe Outflow Control

Diameter (m) 0.100 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 01 1:100yr				
Date 26/11/2018 12:18 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-01.srcx</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
7200 min Summer	29.586	0.036	0.0	4.0	4.0	6.7	O K
8640 min Summer	29.550	0.000	0.0	4.0	4.0	0.0	O K
10080 min Summer	29.550	0.000	0.0	3.5	3.5	0.0	O K
15 min Winter	29.823	0.273	0.0	4.0	4.0	50.7	O K
30 min Winter	29.926	0.376	0.0	4.0	4.0	69.7	O K
60 min Winter	30.059	0.509	0.0	4.0	4.0	94.4	O K
120 min Winter	30.202	0.652	0.0	4.0	4.0	120.7	O K
180 min Winter	30.281	0.731	0.0	4.0	4.0	135.3	O K
240 min Winter	30.329	0.779	0.0	4.0	4.0	144.3	O K
360 min Winter	31.068	1.518	0.0	5.2	5.2	154.4	FLOOD
480 min Winter	32.052	2.502	0.0	6.4	6.4	156.0	FLOOD
600 min Winter	32.053	2.503	0.0	6.4	6.4	157.2	FLOOD
720 min Winter	32.052	2.502	0.0	6.4	6.4	155.9	FLOOD
960 min Winter	32.050	2.500	0.0	6.4	6.4	154.4	FLOOD
1440 min Winter	30.352	0.802	0.0	4.1	4.1	148.6	O K
2160 min Winter	30.229	0.679	0.0	4.0	4.0	125.8	O K
2880 min Winter	30.098	0.548	0.0	4.0	4.0	101.5	O K
4320 min Winter	29.761	0.211	0.0	4.0	4.0	39.0	O K
5760 min Winter	29.574	0.024	0.0	4.0	4.0	4.5	O K
7200 min Winter	29.550	0.000	0.0	3.6	3.6	0.0	O K
8640 min Winter	29.550	0.000	0.0	3.1	3.1	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
7200 min Summer	0.925	0.0	533.0	3896			
8640 min Summer	0.796	0.0	543.6	0			
10080 min Summer	0.701	0.0	549.9	0			
15 min Winter	99.825	0.0	114.1	34			
30 min Winter	65.339	0.0	157.8	67			
60 min Winter	40.718	0.0	216.3	172			
120 min Winter	24.507	0.0	264.6	248			
180 min Winter	17.966	0.0	293.2	304			
240 min Winter	14.329	0.0	313.2	354			
360 min Winter	10.392	0.0	341.8	430			
480 min Winter	8.272	1.7	363.8	476			
600 min Winter	6.925	2.9	380.6	582			
720 min Winter	5.987	1.6	395.1	668			
960 min Winter	4.754	0.0	417.8	788			
1440 min Winter	3.431	0.0	449.1	1216			
2160 min Winter	2.471	0.0	496.6	1644			
2880 min Winter	1.956	0.0	520.5	2088			
4320 min Winter	1.405	0.0	552.2	2768			
5760 min Winter	1.110	0.0	587.0	3280			
7200 min Winter	0.925	0.0	604.6	0			
8640 min Winter	0.796	0.0	617.3	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-01.srcx

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
10080 min Winter	29.550	0.000	0.0	2.7	2.7	0.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
10080 min Winter	0.701	0.0	625.8	0

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-01.srcx

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.167

Time (mins)	Area
From:	To: (ha)
0	4 0.167

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-01.srcx

Storage is Online Cover Level (m) 30.650

Cellular Storage Structure

Invert Level (m) 29.550 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	195.0	195.0	1.300	0.0	242.5
0.100	195.0	200.6	1.400	0.0	242.5
0.200	195.0	206.2	1.500	0.0	242.5
0.300	195.0	211.8	1.600	0.0	242.5
0.400	195.0	217.3	1.700	0.0	242.5
0.500	195.0	222.9	1.800	0.0	242.5
0.600	195.0	228.5	1.900	0.0	242.5
0.700	195.0	234.1	2.000	0.0	242.5
0.800	195.0	239.7	2.100	0.0	242.5
0.900	0.0	242.5	2.200	0.0	242.5
1.000	0.0	242.5	2.300	0.0	242.5
1.100	0.0	242.5	2.400	0.0	242.5
1.200	0.0	242.5	2.500	0.0	242.5

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0095-4000-1000-4000
Design Head (m) 1.000
Design Flow (l/s) 4.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 95
Invert Level (m) 29.310
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	4.0
Flush-Flo™	0.294	4.0
Kick-Flo®	0.629	3.2
Mean Flow over Head Range	-	3.5

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr	
Date 26/11/2018 12:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.0	1.200	4.3	3.000	6.7	7.000	10.0
0.200	3.9	1.400	4.7	3.500	7.2	7.500	10.3
0.300	4.0	1.600	5.0	4.000	7.6	8.000	10.6
0.400	3.9	1.800	5.3	4.500	8.1	8.500	10.9
0.500	3.8	2.000	5.5	5.000	8.5	9.000	11.2
0.600	3.4	2.200	5.8	5.500	8.9	9.500	11.5
0.800	3.6	2.400	6.0	6.000	9.3		
1.000	4.0	2.600	6.2	6.500	9.6		

Infrastructure Design Limited							Page 1	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 02 1:100yr					
Date 26/11/2018 12:19 File Cascade.casx			Designed by IDL Checked by PT					
Micro Drainage			Source Control 2017.1.2					
<u>Cascade Summary of Results for Hydrobrake-02.SRCX</u>								
Upstream Structures			Outflow To		Overflow To			
Porous-CP-to-HB02.SRCX			Hydrobrake-03.SRCX		(None)			
Half Drain Time : 92 minutes.								
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	29.454	0.104		0.0	7.9	7.9	50.2	O K
30 min Summer	29.481	0.131		0.0	8.0	8.0	63.5	O K
60 min Summer	29.498	0.148		0.0	8.0	8.0	71.9	O K
120 min Summer	29.500	0.150		0.0	8.0	8.0	72.6	O K
180 min Summer	29.495	0.145		0.0	8.0	8.0	70.2	O K
240 min Summer	29.487	0.137		0.0	8.0	8.0	66.5	O K
360 min Summer	29.471	0.121		0.0	8.0	8.0	58.7	O K
480 min Summer	29.457	0.107		0.0	7.9	7.9	51.8	O K
600 min Summer	29.444	0.094		0.0	7.9	7.9	45.6	O K
720 min Summer	29.433	0.083		0.0	7.8	7.8	40.1	O K
960 min Summer	29.415	0.065		0.0	7.6	7.6	31.7	O K
1440 min Summer	29.394	0.044		0.0	6.5	6.5	21.4	O K
2160 min Summer	29.375	0.025		0.0	5.3	5.3	12.2	O K
2880 min Summer	29.364	0.014		0.0	4.4	4.4	6.7	O K
4320 min Summer	29.351	0.001		0.0	3.5	3.5	0.7	O K
5760 min Summer	29.350	0.000		0.0	2.9	2.9	0.0	O K
7200 min Summer	29.350	0.000		0.0	2.4	2.4	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)				
15 min Summer	99.825	0.0	56.4	18				
30 min Summer	65.339	0.0	75.0	32				
60 min Summer	40.718	0.0	94.2	60				
120 min Summer	24.507	0.0	114.2	96				
180 min Summer	17.966	0.0	125.9	128				
240 min Summer	14.329	0.0	134.1	162				
360 min Summer	10.392	0.0	145.9	230				
480 min Summer	8.272	0.0	154.7	294				
600 min Summer	6.925	0.0	162.3	358				
720 min Summer	5.987	0.0	168.2	420				
960 min Summer	4.754	0.0	177.9	540				
1440 min Summer	3.431	0.0	192.4	780				
2160 min Summer	2.471	0.0	207.5	1144				
2880 min Summer	1.956	0.0	218.4	1500				
4320 min Summer	1.405	0.0	234.3	2204				
5760 min Summer	1.110	0.0	245.5	0				
7200 min Summer	0.925	0.0	254.1	0				
©1982-2017 XP Solutions								

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 02 1:100yr				
Date 26/11/2018 12:19 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	29.350	0.000	0.0	2.1	2.1	0.0	O K
10080 min Summer	29.350	0.000	0.0	1.8	1.8	0.0	O K
15 min Winter	29.470	0.120	0.0	7.9	7.9	58.0	O K
30 min Winter	29.500	0.150	0.0	8.0	8.0	72.9	O K
60 min Winter	29.522	0.172	0.0	8.0	8.0	83.5	O K
120 min Winter	29.525	0.175	0.0	8.0	8.0	84.7	O K
180 min Winter	29.517	0.167	0.0	8.0	8.0	80.9	O K
240 min Winter	29.506	0.156	0.0	8.0	8.0	75.7	O K
360 min Winter	29.483	0.133	0.0	8.0	8.0	64.3	O K
480 min Winter	29.461	0.111	0.0	7.9	7.9	53.8	O K
600 min Winter	29.442	0.092	0.0	7.9	7.9	44.7	O K
720 min Winter	29.426	0.076	0.0	7.8	7.8	37.0	O K
960 min Winter	29.406	0.056	0.0	7.1	7.1	27.0	O K
1440 min Winter	29.382	0.032	0.0	5.7	5.7	15.3	O K
2160 min Winter	29.363	0.013	0.0	4.4	4.4	6.1	O K
2880 min Winter	29.352	0.002	0.0	3.6	3.6	0.9	O K
4320 min Winter	29.350	0.000	0.0	2.6	2.6	0.0	O K
5760 min Winter	29.350	0.000	0.0	2.1	2.1	0.0	O K
7200 min Winter	29.350	0.000	0.0	1.7	1.7	0.0	O K
8640 min Winter	29.350	0.000	0.0	1.5	1.5	0.0	O K
10080 min Winter	29.350	0.000	0.0	1.3	1.3	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.796	0.0	261.0	0			
10080 min Summer	0.701	0.0	266.7	0			
15 min Winter	99.825	0.0	64.2	18			
30 min Winter	65.339	0.0	84.6	32			
60 min Winter	40.718	0.0	106.0	60			
120 min Winter	24.507	0.0	128.4	110			
180 min Winter	17.966	0.0	141.5	138			
240 min Winter	14.329	0.0	150.3	176			
360 min Winter	10.392	0.0	164.0	248			
480 min Winter	8.272	0.0	173.9	316			
600 min Winter	6.925	0.0	182.1	380			
720 min Winter	5.987	0.0	189.0	440			
960 min Winter	4.754	0.0	200.0	558			
1440 min Winter	3.431	0.0	216.1	796			
2160 min Winter	2.471	0.0	233.1	1164			
2880 min Winter	1.956	0.0	245.7	1500			
4320 min Winter	1.405	0.0	263.5	0			
5760 min Winter	1.110	0.0	276.3	0			
7200 min Winter	0.925	0.0	286.1	0			
8640 min Winter	0.796	0.0	294.1	0			
10080 min Winter	0.701	0.0	300.7	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr	
Date 26/11/2018 12:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Rainfall Details for Hydrobrake-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.199

Time (mins)	Area
From:	To: (ha)

0	4 0.199
---	---------

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr	
Date 26/11/2018 12:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-02.SRCX

Storage is Online Cover Level (m) 30.630

Cellular Storage Structure

Invert Level (m) 29.350 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	510.0	510.0	1.300	0.0	559.7
0.100	510.0	519.0	1.400	0.0	559.7
0.200	510.0	528.1	1.500	0.0	559.7
0.300	510.0	537.1	1.600	0.0	559.7
0.400	510.0	546.1	1.700	0.0	559.7
0.500	510.0	555.2	1.800	0.0	559.7
0.600	0.0	559.7	1.900	0.0	559.7
0.700	0.0	559.7	2.000	0.0	559.7
0.800	0.0	559.7	2.100	0.0	559.7
0.900	0.0	559.7	2.200	0.0	559.7
1.000	0.0	559.7	2.300	0.0	559.7
1.100	0.0	559.7	2.400	0.0	559.7
1.200	0.0	559.7	2.500	0.0	559.7

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0136-8000-0680-8000
Design Head (m) 0.680
Design Flow (l/s) 8.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 136
Invert Level (m) 29.270
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.680	8.0
Flush-Flo™	0.231	8.0
Kick-Flo®	0.492	6.9
Mean Flow over Head Range	-	6.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr	
Date 26/11/2018 12:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.9	1.200	10.4	3.000	16.1	7.000	24.1
0.200	7.9	1.400	11.2	3.500	17.4	7.500	25.0
0.300	7.9	1.600	12.0	4.000	18.5	8.000	25.8
0.400	7.6	1.800	12.6	4.500	19.6	8.500	26.6
0.500	6.9	2.000	13.3	5.000	20.6	9.000	27.4
0.600	7.5	2.200	13.9	5.500	21.6	9.500	28.1
0.800	8.6	2.400	14.5	6.000	22.5		
1.000	9.6	2.600	15.1	6.500	23.4		

Infrastructure Design Limited		Page 1																																																																																																																																																
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr																																																																																																																																																	
Date 26/11/2018 14:18 File Cascade.casx	Designed by IDL Checked by PT																																																																																																																																																	
Micro Drainage		Source Control 2017.1.2																																																																																																																																																
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>																																																																																																																																																		
Upstream Structures Outflow To Overflow To Hydrobrake-01.srcx (None) (None) BlueRoof-01.SRCX BlueRoof-02.SRCX Porous-CP-to-HB01.SRCX Hydrobrake-02.SRCX Porous-CP-to-HB02.SRCX Half Drain Time : 175 minutes.																																																																																																																																																		
<table><tr><th>Storm Event</th><th>Max Level (m)</th><th>Max Depth (m)</th><th>Max Infiltration (l/s)</th><th>Max Control (l/s)</th><th>Max E (l/s)</th><th>Max Outflow (l/s)</th><th>Max Volume (m³)</th><th>Status</th></tr><tr><td>15 min Summer</td><td>29.199</td><td>0.249</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>73.8</td><td>O K</td></tr><tr><td>30 min Summer</td><td>29.283</td><td>0.333</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>98.8</td><td>O K</td></tr><tr><td>60 min Summer</td><td>29.358</td><td>0.408</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>120.9</td><td>O K</td></tr><tr><td>120 min Summer</td><td>29.443</td><td>0.493</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>146.1</td><td>O K</td></tr><tr><td>180 min Summer</td><td>29.480</td><td>0.530</td><td></td><td>0.0</td><td>6.6</td><td>6.6</td><td>157.2</td><td>O K</td></tr><tr><td>240 min Summer</td><td>29.496</td><td>0.546</td><td></td><td>0.0</td><td>7.3</td><td>7.3</td><td>161.8</td><td>O K</td></tr><tr><td>360 min Summer</td><td>29.511</td><td>0.561</td><td></td><td>0.0</td><td>8.2</td><td>8.2</td><td>166.3</td><td>O K</td></tr><tr><td>480 min Summer</td><td>29.520</td><td>0.570</td><td></td><td>0.0</td><td>8.9</td><td>8.9</td><td>168.9</td><td>O K</td></tr><tr><td>600 min Summer</td><td>29.517</td><td>0.567</td><td></td><td>0.0</td><td>8.7</td><td>8.7</td><td>168.0</td><td>O K</td></tr><tr><td>720 min Summer</td><td>29.512</td><td>0.562</td><td></td><td>0.0</td><td>8.3</td><td>8.3</td><td>166.7</td><td>O K</td></tr><tr><td>960 min Summer</td><td>29.503</td><td>0.553</td><td></td><td>0.0</td><td>7.7</td><td>7.7</td><td>163.8</td><td>O K</td></tr><tr><td>1440 min Summer</td><td>29.478</td><td>0.528</td><td></td><td>0.0</td><td>6.5</td><td>6.5</td><td>156.5</td><td>O K</td></tr><tr><td>2160 min Summer</td><td>29.431</td><td>0.481</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>142.5</td><td>O K</td></tr><tr><td>2880 min Summer</td><td>29.386</td><td>0.436</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>129.2</td><td>O K</td></tr><tr><td>4320 min Summer</td><td>29.327</td><td>0.377</td><td></td><td>0.0</td><td>6.0</td><td>6.0</td><td>111.7</td><td>O K</td></tr></table>			Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status	15 min Summer	29.199	0.249		0.0	6.0	6.0	73.8	O K	30 min Summer	29.283	0.333		0.0	6.0	6.0	98.8	O K	60 min Summer	29.358	0.408		0.0	6.0	6.0	120.9	O K	120 min Summer	29.443	0.493		0.0	6.0	6.0	146.1	O K	180 min Summer	29.480	0.530		0.0	6.6	6.6	157.2	O K	240 min Summer	29.496	0.546		0.0	7.3	7.3	161.8	O K	360 min Summer	29.511	0.561		0.0	8.2	8.2	166.3	O K	480 min Summer	29.520	0.570		0.0	8.9	8.9	168.9	O K	600 min Summer	29.517	0.567		0.0	8.7	8.7	168.0	O K	720 min Summer	29.512	0.562		0.0	8.3	8.3	166.7	O K	960 min Summer	29.503	0.553		0.0	7.7	7.7	163.8	O K	1440 min Summer	29.478	0.528		0.0	6.5	6.5	156.5	O K	2160 min Summer	29.431	0.481		0.0	6.0	6.0	142.5	O K	2880 min Summer	29.386	0.436		0.0	6.0	6.0	129.2	O K	4320 min Summer	29.327	0.377		0.0	6.0	6.0	111.7	O K
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status																																																																																																																																										
15 min Summer	29.199	0.249		0.0	6.0	6.0	73.8	O K																																																																																																																																										
30 min Summer	29.283	0.333		0.0	6.0	6.0	98.8	O K																																																																																																																																										
60 min Summer	29.358	0.408		0.0	6.0	6.0	120.9	O K																																																																																																																																										
120 min Summer	29.443	0.493		0.0	6.0	6.0	146.1	O K																																																																																																																																										
180 min Summer	29.480	0.530		0.0	6.6	6.6	157.2	O K																																																																																																																																										
240 min Summer	29.496	0.546		0.0	7.3	7.3	161.8	O K																																																																																																																																										
360 min Summer	29.511	0.561		0.0	8.2	8.2	166.3	O K																																																																																																																																										
480 min Summer	29.520	0.570		0.0	8.9	8.9	168.9	O K																																																																																																																																										
600 min Summer	29.517	0.567		0.0	8.7	8.7	168.0	O K																																																																																																																																										
720 min Summer	29.512	0.562		0.0	8.3	8.3	166.7	O K																																																																																																																																										
960 min Summer	29.503	0.553		0.0	7.7	7.7	163.8	O K																																																																																																																																										
1440 min Summer	29.478	0.528		0.0	6.5	6.5	156.5	O K																																																																																																																																										
2160 min Summer	29.431	0.481		0.0	6.0	6.0	142.5	O K																																																																																																																																										
2880 min Summer	29.386	0.436		0.0	6.0	6.0	129.2	O K																																																																																																																																										
4320 min Summer	29.327	0.377		0.0	6.0	6.0	111.7	O K																																																																																																																																										
<table><tr><th>Storm Event</th><th>Rain (mm/hr)</th><th>Flooded Volume (m³)</th><th>Discharge Volume (m³)</th><th>Time-Peak (mins)</th></tr><tr><td>15 min Summer</td><td>99.825</td><td>0.0</td><td>190.8</td><td>154</td></tr><tr><td>30 min Summer</td><td>65.339</td><td>0.0</td><td>258.8</td><td>197</td></tr><tr><td>60 min Summer</td><td>40.718</td><td>0.0</td><td>341.6</td><td>242</td></tr><tr><td>120 min Summer</td><td>24.507</td><td>0.0</td><td>417.0</td><td>298</td></tr><tr><td>180 min Summer</td><td>17.966</td><td>0.0</td><td>460.8</td><td>340</td></tr><tr><td>240 min Summer</td><td>14.329</td><td>0.0</td><td>491.4</td><td>374</td></tr><tr><td>360 min Summer</td><td>10.392</td><td>0.0</td><td>536.0</td><td>418</td></tr><tr><td>480 min Summer</td><td>8.272</td><td>0.0</td><td>569.8</td><td>482</td></tr><tr><td>600 min Summer</td><td>6.925</td><td>0.0</td><td>596.3</td><td>568</td></tr><tr><td>720 min Summer</td><td>5.987</td><td>0.0</td><td>618.7</td><td>634</td></tr><tr><td>960 min Summer</td><td>4.754</td><td>0.0</td><td>654.6</td><td>744</td></tr><tr><td>1440 min Summer</td><td>3.431</td><td>0.0</td><td>705.5</td><td>984</td></tr><tr><td>2160 min Summer</td><td>2.471</td><td>0.0</td><td>772.8</td><td>1428</td></tr><tr><td>2880 min Summer</td><td>1.956</td><td>0.0</td><td>811.3</td><td>1820</td></tr><tr><td>4320 min Summer</td><td>1.405</td><td>0.0</td><td>864.6</td><td>2724</td></tr></table>			Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)	15 min Summer	99.825	0.0	190.8	154	30 min Summer	65.339	0.0	258.8	197	60 min Summer	40.718	0.0	341.6	242	120 min Summer	24.507	0.0	417.0	298	180 min Summer	17.966	0.0	460.8	340	240 min Summer	14.329	0.0	491.4	374	360 min Summer	10.392	0.0	536.0	418	480 min Summer	8.272	0.0	569.8	482	600 min Summer	6.925	0.0	596.3	568	720 min Summer	5.987	0.0	618.7	634	960 min Summer	4.754	0.0	654.6	744	1440 min Summer	3.431	0.0	705.5	984	2160 min Summer	2.471	0.0	772.8	1428	2880 min Summer	1.956	0.0	811.3	1820	4320 min Summer	1.405	0.0	864.6	2724																																																																
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)																																																																																																																																														
15 min Summer	99.825	0.0	190.8	154																																																																																																																																														
30 min Summer	65.339	0.0	258.8	197																																																																																																																																														
60 min Summer	40.718	0.0	341.6	242																																																																																																																																														
120 min Summer	24.507	0.0	417.0	298																																																																																																																																														
180 min Summer	17.966	0.0	460.8	340																																																																																																																																														
240 min Summer	14.329	0.0	491.4	374																																																																																																																																														
360 min Summer	10.392	0.0	536.0	418																																																																																																																																														
480 min Summer	8.272	0.0	569.8	482																																																																																																																																														
600 min Summer	6.925	0.0	596.3	568																																																																																																																																														
720 min Summer	5.987	0.0	618.7	634																																																																																																																																														
960 min Summer	4.754	0.0	654.6	744																																																																																																																																														
1440 min Summer	3.431	0.0	705.5	984																																																																																																																																														
2160 min Summer	2.471	0.0	772.8	1428																																																																																																																																														
2880 min Summer	1.956	0.0	811.3	1820																																																																																																																																														
4320 min Summer	1.405	0.0	864.6	2724																																																																																																																																														
©1982-2017 XP Solutions																																																																																																																																																		

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 03 1:100yr				
Date 26/11/2018 14:18 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
5760 min Summer	29.226	0.276	0.0	6.0	6.0	81.8	O K
7200 min Summer	29.136	0.186	0.0	6.0	6.0	55.1	O K
8640 min Summer	29.050	0.100	0.0	6.0	6.0	29.7	O K
10080 min Summer	28.997	0.047	0.0	5.9	5.9	13.9	O K
15 min Winter	29.233	0.283	0.0	6.0	6.0	83.8	O K
30 min Winter	29.319	0.369	0.0	6.0	6.0	109.4	O K
60 min Winter	29.415	0.465	0.0	6.0	6.0	137.7	O K
120 min Winter	29.497	0.547	0.0	7.4	7.4	162.1	O K
180 min Winter	29.518	0.568	0.0	8.8	8.8	168.5	O K
240 min Winter	29.529	0.579	0.0	9.6	9.6	171.5	O K
360 min Winter	29.542	0.592	0.0	10.4	10.4	175.5	O K
480 min Winter	29.561	0.611	0.0	11.9	11.9	181.1	O K
600 min Winter	29.558	0.608	0.0	11.6	11.6	180.3	O K
720 min Winter	29.551	0.601	0.0	11.0	11.0	178.0	O K
960 min Winter	29.535	0.585	0.0	10.0	10.0	173.5	O K
1440 min Winter	29.519	0.569	0.0	8.9	8.9	168.8	O K
2160 min Winter	29.482	0.532	0.0	6.7	6.7	157.6	O K
2880 min Winter	29.427	0.477	0.0	6.0	6.0	141.4	O K
4320 min Winter	29.346	0.396	0.0	6.0	6.0	117.4	O K
5760 min Winter	29.163	0.213	0.0	6.0	6.0	63.3	O K
7200 min Winter	29.007	0.057	0.0	5.9	5.9	17.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
5760 min Summer	1.110	0.0	913.7	3520			
7200 min Summer	0.925	0.0	943.3	4176			
8640 min Summer	0.796	0.0	966.0	4664			
10080 min Summer	0.701	0.0	982.4	5248			
15 min Winter	99.825	0.0	217.5	171			
30 min Winter	65.339	0.0	293.8	216			
60 min Winter	40.718	0.0	386.4	266			
120 min Winter	24.507	0.0	470.4	322			
180 min Winter	17.966	0.0	519.6	332			
240 min Winter	14.329	0.0	553.9	352			
360 min Winter	10.392	0.0	603.9	402			
480 min Winter	8.272	0.0	642.0	484			
600 min Winter	6.925	0.0	672.0	578			
720 min Winter	5.987	0.0	697.3	670			
960 min Winter	4.754	0.0	737.9	724			
1440 min Winter	3.431	0.0	795.2	1024			
2160 min Winter	2.471	0.0	870.6	1492			
2880 min Winter	1.956	0.0	914.6	1988			
4320 min Winter	1.405	0.0	975.5	2984			
5760 min Winter	1.110	0.0	1031.7	3552			
7200 min Winter	0.925	0.0	1065.7	3960			

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr	
Date 26/11/2018 14:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-03.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
8640 min Winter	28.972	0.022	0.0	5.4	5.4	6.6	O K
10080 min Winter	28.959	0.009	0.0	4.8	4.8	2.7	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
8640 min Winter	0.796	0.0	1092.2	4496
10080 min Winter	0.701	0.0	1112.3	5224

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr	
Date 26/11/2018 14:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-03.SRCX

Storage is Online Cover Level (m) 30.550

Cellular Storage Structure

Invert Level (m) 28.950 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	312.0	312.0	1.300	0.0	372.1
0.100	312.0	319.1	1.400	0.0	372.1
0.200	312.0	326.1	1.500	0.0	372.1
0.300	312.0	333.2	1.600	0.0	372.1
0.400	312.0	340.3	1.700	0.0	372.1
0.500	312.0	347.3	1.800	0.0	372.1
0.600	312.0	354.4	1.900	0.0	372.1
0.700	312.0	361.5	2.000	0.0	372.1
0.800	312.0	368.5	2.100	0.0	372.1
0.900	0.0	372.1	2.200	0.0	372.1
1.000	0.0	372.1	2.300	0.0	372.1
1.100	0.0	372.1	2.400	0.0	372.1
1.200	0.0	372.1	2.500	0.0	372.1

Complex Outflow Control

Hydro-Brake® Optimum

Unit Reference MD-SHE-0121-6000-0600-6000
Design Head (m) 0.600
Design Flow (l/s) 6.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 121
Invert Level (m) 28.850
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.600	6.0
Flush-Flo™	0.202	6.0
Kick-Flo®	0.435	5.2
Mean Flow over Head Range	-	5.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr	
Date 26/11/2018 14:18 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.3	1.200	8.3	3.000	12.8	7.000	19.2
0.200	6.0	1.400	8.9	3.500	13.8	7.500	19.9
0.300	5.9	1.600	9.5	4.000	14.7	8.000	20.5
0.400	5.5	1.800	10.0	4.500	15.5	8.500	21.1
0.500	5.5	2.000	10.6	5.000	16.3	9.000	21.8
0.600	6.0	2.200	11.0	5.500	17.1	9.500	22.4
0.800	6.9	2.400	11.5	6.000	17.8		
1.000	7.6	2.600	12.0	6.500	18.5		

Orifice

Diameter (m) 0.125 Discharge Coefficient 0.600 Invert Level (m) 29.450

Infrastructure Design Limited							Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB01 1:100yr				
Date 26/11/2018 12:19 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB01.SRCX</u>							
Upstream Structures			Outflow To		Overflow To		
(None)			Hydrobrake-01.srcx		(None)		
Half Drain Time : 7 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	30.270	0.290	0.0	20.7	20.7	11.3	O K
30 min Summer	30.285	0.305	0.0	21.5	21.5	12.6	O K
60 min Summer	30.266	0.286	0.0	20.5	20.5	11.0	O K
120 min Summer	30.220	0.240	0.0	17.9	17.9	7.7	O K
180 min Summer	30.191	0.211	0.0	14.9	14.9	6.0	O K
240 min Summer	30.171	0.191	0.0	12.6	12.6	4.9	O K
360 min Summer	30.144	0.164	0.0	9.7	9.7	3.6	O K
480 min Summer	30.128	0.148	0.0	7.9	7.9	3.0	O K
600 min Summer	30.115	0.135	0.0	6.7	6.7	2.5	O K
720 min Summer	30.105	0.125	0.0	5.9	5.9	2.1	O K
960 min Summer	30.090	0.110	0.0	4.7	4.7	1.6	O K
1440 min Summer	30.077	0.097	0.0	3.4	3.4	1.3	O K
2160 min Summer	30.067	0.087	0.0	2.5	2.5	1.0	O K
2880 min Summer	30.058	0.078	0.0	1.9	1.9	0.8	O K
4320 min Summer	30.049	0.069	0.0	1.4	1.4	0.6	O K
5760 min Summer	30.044	0.064	0.0	1.1	1.1	0.5	O K
7200 min Summer	30.039	0.059	0.0	0.9	0.9	0.5	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	99.825	0.0	19.5	13			
30 min Summer	65.339	0.0	26.6	21			
60 min Summer	40.718	0.0	34.0	36			
120 min Summer	24.507	0.0	41.5	66			
180 min Summer	17.966	0.0	46.0	96			
240 min Summer	14.329	0.0	49.0	126			
360 min Summer	10.392	0.0	53.5	186			
480 min Summer	8.272	0.0	56.9	246			
600 min Summer	6.925	0.0	59.5	308			
720 min Summer	5.987	0.0	61.7	368			
960 min Summer	4.754	0.0	65.3	488			
1440 min Summer	3.431	0.0	70.4	734			
2160 min Summer	2.471	0.0	75.5	1084			
2880 min Summer	1.956	0.0	79.0	1436			
4320 min Summer	1.405	0.0	83.6	2184			
5760 min Summer	1.110	0.0	86.6	2880			
7200 min Summer	0.925	0.0	88.5	3600			
©1982-2017 XP Solutions							

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB01 1:100yr				
Date 26/11/2018 12:19 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.036	0.056	0.0	0.8	0.8	0.4	O K
10080 min Summer	30.034	0.054	0.0	0.7	0.7	0.4	O K
15 min Winter	30.288	0.308	0.0	21.7	21.7	12.8	O K
30 min Winter	30.295	0.315	0.0	22.0	22.0	13.4	O K
60 min Winter	30.261	0.281	0.0	20.2	20.2	10.6	O K
120 min Winter	30.200	0.220	0.0	16.0	16.0	6.5	O K
180 min Winter	30.168	0.188	0.0	12.4	12.4	4.8	O K
240 min Winter	30.148	0.168	0.0	10.1	10.1	3.8	O K
360 min Winter	30.123	0.143	0.0	7.4	7.4	2.8	O K
480 min Winter	30.105	0.125	0.0	5.9	5.9	2.1	O K
600 min Winter	30.093	0.113	0.0	5.0	5.0	1.7	O K
720 min Winter	30.086	0.106	0.0	4.3	4.3	1.5	O K
960 min Winter	30.077	0.097	0.0	3.4	3.4	1.3	O K
1440 min Winter	30.067	0.087	0.0	2.5	2.5	1.0	O K
2160 min Winter	30.055	0.075	0.0	1.8	1.8	0.8	O K
2880 min Winter	30.049	0.069	0.0	1.4	1.4	0.6	O K
4320 min Winter	30.041	0.061	0.0	1.0	1.0	0.5	O K
5760 min Winter	30.037	0.057	0.0	0.8	0.8	0.4	O K
7200 min Winter	30.033	0.053	0.0	0.7	0.7	0.4	O K
8640 min Winter	30.031	0.051	0.0	0.6	0.6	0.3	O K
10080 min Winter	30.029	0.049	0.0	0.5	0.5	0.3	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.796	0.0	89.8	4400			
10080 min Summer	0.701	0.0	90.6	4984			
15 min Winter	99.825	0.0	22.3	13			
30 min Winter	65.339	0.0	30.2	22			
60 min Winter	40.718	0.0	38.5	38			
120 min Winter	24.507	0.0	47.0	68			
180 min Winter	17.966	0.0	51.9	98			
240 min Winter	14.329	0.0	55.4	128			
360 min Winter	10.392	0.0	60.4	188			
480 min Winter	8.272	0.0	64.2	248			
600 min Winter	6.925	0.0	67.2	308			
720 min Winter	5.987	0.0	69.7	368			
960 min Winter	4.754	0.0	73.7	482			
1440 min Winter	3.431	0.0	79.5	734			
2160 min Winter	2.471	0.0	85.3	1100			
2880 min Winter	1.956	0.0	89.4	1456			
4320 min Winter	1.405	0.0	94.9	2152			
5760 min Winter	1.110	0.0	98.5	2896			
7200 min Winter	0.925	0.0	100.9	3640			
8640 min Winter	0.796	0.0	102.6	4288			
10080 min Winter	0.701	0.0	103.9	5072			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:100yr																																		
Date 26/11/2018 12:19 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB01.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.123 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.123</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.123
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.123																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:100yr																																									
Date 26/11/2018 12:19 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB01.SRCX</u> Storage is Online Cover Level (m) 30.590 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>6.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>115.0</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>191.7</td> <td>Slope (1:X)</td> <td>150.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>29.980</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>30.000</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	115.0	Max Percolation (l/s)	191.7	Slope (1:X)	150.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	29.980	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	30.000	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	115.0																																							
Max Percolation (l/s)	191.7	Slope (1:X)	150.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	29.980	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	30.000																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited							Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:100yr				
Date 26/11/2018 12:20 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Upstream Structures			Outflow To		Overflow To		
(None)			Hydrobrake-02.SRCX		(None)		
Half Drain Time : 0 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	30.186	0.166	0.0	48.5	48.5	1.3	O K
30 min Summer	30.105	0.085	0.0	47.0	47.0	0.3	O K
60 min Summer	30.020	0.000	0.0	36.3	36.3	0.0	O K
120 min Summer	30.020	0.000	0.0	23.4	23.4	0.0	O K
180 min Summer	30.020	0.000	0.0	17.6	17.6	0.0	O K
240 min Summer	30.020	0.000	0.0	14.1	14.1	0.0	O K
360 min Summer	30.020	0.000	0.0	10.2	10.2	0.0	O K
480 min Summer	30.020	0.000	0.0	8.2	8.2	0.0	O K
600 min Summer	30.020	0.000	0.0	6.8	6.8	0.0	O K
720 min Summer	30.020	0.000	0.0	5.9	5.9	0.0	O K
960 min Summer	30.020	0.000	0.0	4.7	4.7	0.0	O K
1440 min Summer	30.020	0.000	0.0	3.4	3.4	0.0	O K
2160 min Summer	30.020	0.000	0.0	2.4	2.4	0.0	O K
2880 min Summer	30.020	0.000	0.0	1.9	1.9	0.0	O K
4320 min Summer	30.020	0.000	0.0	1.4	1.4	0.0	O K
5760 min Summer	30.020	0.000	0.0	1.1	1.1	0.0	O K
7200 min Summer	30.020	0.000	0.0	0.9	0.9	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	99.825	0.0	19.3	11			
30 min Summer	65.339	0.0	26.6	18			
60 min Summer	40.718	0.0	33.8	0			
120 min Summer	24.507	0.0	41.3	0			
180 min Summer	17.966	0.0	45.6	0			
240 min Summer	14.329	0.0	48.7	0			
360 min Summer	10.392	0.0	53.1	0			
480 min Summer	8.272	0.0	56.4	0			
600 min Summer	6.925	0.0	59.0	0			
720 min Summer	5.987	0.0	61.2	0			
960 min Summer	4.754	0.0	64.8	0			
1440 min Summer	3.431	0.0	69.8	0			
2160 min Summer	2.471	0.0	74.9	0			
2880 min Summer	1.956	0.0	78.5	0			
4320 min Summer	1.405	0.0	83.3	0			
5760 min Summer	1.110	0.0	86.4	0			
7200 min Summer	0.925	0.0	88.5	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:100yr				
Date 26/11/2018 12:20 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.020	0.000	0.0	0.8	0.8	0.0	O K
10080 min Summer	30.020	0.000	0.0	0.7	0.7	0.0	O K
15 min Winter	30.191	0.171	0.0	48.6	48.6	1.4	O K
30 min Winter	30.020	0.000	0.0	43.9	43.9	0.0	O K
60 min Winter	30.020	0.000	0.0	28.5	28.5	0.0	O K
120 min Winter	30.020	0.000	0.0	17.4	17.4	0.0	O K
180 min Winter	30.020	0.000	0.0	12.8	12.8	0.0	O K
240 min Winter	30.020	0.000	0.0	10.2	10.2	0.0	O K
360 min Winter	30.020	0.000	0.0	7.4	7.4	0.0	O K
480 min Winter	30.020	0.000	0.0	5.9	5.9	0.0	O K
600 min Winter	30.020	0.000	0.0	4.9	4.9	0.0	O K
720 min Winter	30.020	0.000	0.0	4.3	4.3	0.0	O K
960 min Winter	30.020	0.000	0.0	3.4	3.4	0.0	O K
1440 min Winter	30.020	0.000	0.0	2.4	2.4	0.0	O K
2160 min Winter	30.020	0.000	0.0	1.7	1.7	0.0	O K
2880 min Winter	30.020	0.000	0.0	1.4	1.4	0.0	O K
4320 min Winter	30.020	0.000	0.0	1.0	1.0	0.0	O K
5760 min Winter	30.020	0.000	0.0	0.8	0.8	0.0	O K
7200 min Winter	30.020	0.000	0.0	0.6	0.6	0.0	O K
8640 min Winter	30.020	0.000	0.0	0.5	0.5	0.0	O K
10080 min Winter	30.020	0.000	0.0	0.5	0.5	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	0.796	0.0	90.0	0			
10080 min Summer	0.701	0.0	91.0	0			
15 min Winter	99.825	0.0	22.8	11			
30 min Winter	65.339	0.0	30.1	0			
60 min Winter	40.718	0.0	38.3	0			
120 min Winter	24.507	0.0	46.6	0			
180 min Winter	17.966	0.0	51.5	0			
240 min Winter	14.329	0.0	54.9	0			
360 min Winter	10.392	0.0	59.9	0			
480 min Winter	8.272	0.0	63.6	0			
600 min Winter	6.925	0.0	66.6	0			
720 min Winter	5.987	0.0	69.1	0			
960 min Winter	4.754	0.0	73.0	0			
1440 min Winter	3.431	0.0	78.8	0			
2160 min Winter	2.471	0.0	84.6	0			
2880 min Winter	1.956	0.0	88.7	0			
4320 min Winter	1.405	0.0	94.4	0			
5760 min Winter	1.110	0.0	98.1	0			
7200 min Winter	0.925	0.0	100.7	0			
8640 min Winter	0.796	0.0	102.6	0			
10080 min Winter	0.701	0.0	104.0	0			

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:100yr																																		
Date 26/11/2018 12:20 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB02.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+0</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.121 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.121</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+0	Time (mins) Area			From:	To:	(ha)	0	4	0.121
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+0																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.121																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:100yr																																									
Date 26/11/2018 12:20 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB02.SRCX</u> Storage is Online Cover Level (m) 30.630 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>8.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>76.3</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>169.6</td> <td>Slope (1:X)</td> <td>40.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>30.020</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>28.850</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0	Membrane Percolation (mm/hr)	1000	Length (m)	76.3	Max Percolation (l/s)	169.6	Slope (1:X)	40.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	30.020	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	28.850	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	76.3																																							
Max Percolation (l/s)	169.6	Slope (1:X)	40.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	30.020	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	28.850																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited							Page 1
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:100yr + 40%				
Date 26/11/2018 12:24 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Upstream Structures			Outflow To		Overflow To		
(None)			Hydrobrake-02.SRCX		(None)		
Half Drain Time : 190 minutes.							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max E Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	34.659	0.059	0.0	2.0	2.0	62.2	O K
30 min Summer	34.677	0.077	0.0	3.4	3.4	81.4	O K
60 min Summer	34.696	0.096	0.0	5.2	5.2	100.6	O K
120 min Summer	34.713	0.113	0.0	6.5	6.5	117.4	O K
180 min Summer	34.718	0.118	0.0	6.9	6.9	121.0	O K
240 min Summer	34.720	0.120	0.0	7.1	7.1	122.4	O K
360 min Summer	34.722	0.122	0.0	7.3	7.3	123.7	O K
480 min Summer	34.722	0.122	0.0	7.3	7.3	123.6	O K
600 min Summer	34.721	0.121	0.0	7.2	7.2	122.7	O K
720 min Summer	34.719	0.119	0.0	7.0	7.0	121.3	O K
960 min Summer	34.714	0.114	0.0	6.6	6.6	117.8	O K
1440 min Summer	34.705	0.105	0.0	5.9	5.9	110.1	O K
2160 min Summer	34.695	0.095	0.0	5.1	5.1	100.1	O K
2880 min Summer	34.688	0.088	0.0	4.5	4.5	92.5	O K
4320 min Summer	34.679	0.079	0.0	3.6	3.6	82.7	O K
5760 min Summer	34.672	0.072	0.0	2.9	2.9	76.1	O K
7200 min Summer	34.667	0.067	0.0	2.5	2.5	70.5	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
15 min Summer	139.755	0.0	53.1	57			
30 min Summer	91.475	0.0	74.9	60			
60 min Summer	57.005	0.0	107.3	74			
120 min Summer	34.310	0.0	131.9	122			
180 min Summer	25.153	0.0	146.3	162			
240 min Summer	20.060	0.0	156.3	192			
360 min Summer	14.548	0.0	170.9	252			
480 min Summer	11.581	0.0	181.8	318			
600 min Summer	9.696	0.0	190.4	386			
720 min Summer	8.382	0.0	197.5	452			
960 min Summer	6.656	0.0	208.7	582			
1440 min Summer	4.803	0.0	223.9	838			
2160 min Summer	3.460	0.0	250.5	1212			
2880 min Summer	2.739	0.0	262.6	1572			
4320 min Summer	1.968	0.0	277.5	2296			
5760 min Summer	1.555	0.0	298.0	3056			
7200 min Summer	1.294	0.0	306.8	3816			
©1982-2017 XP Solutions							

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:100yr + 40%				
Date 26/11/2018 12:24 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.662	0.062	0.0	2.2	2.2	65.6	O K
10080 min Summer	34.659	0.059	0.0	2.0	2.0	61.9	O K
15 min Winter	34.666	0.066	0.0	2.4	2.4	69.8	O K
30 min Winter	34.686	0.086	0.0	4.4	4.4	90.7	O K
60 min Winter	34.707	0.107	0.0	6.1	6.1	112.5	O K
120 min Winter	34.734	0.134	0.0	8.6	8.6	130.3	O K
180 min Winter	34.741	0.141	0.0	9.3	9.3	132.9	O K
240 min Winter	34.743	0.143	0.0	9.6	9.6	133.9	O K
360 min Winter	34.742	0.142	0.0	9.5	9.5	133.5	O K
480 min Winter	34.737	0.137	0.0	8.9	8.9	131.5	O K
600 min Winter	34.732	0.132	0.0	8.4	8.4	129.0	O K
720 min Winter	34.726	0.126	0.0	7.8	7.8	126.3	O K
960 min Winter	34.717	0.117	0.0	6.9	6.9	120.4	O K
1440 min Winter	34.704	0.104	0.0	5.8	5.8	108.9	O K
2160 min Winter	34.691	0.091	0.0	4.8	4.8	95.6	O K
2880 min Winter	34.683	0.083	0.0	4.1	4.1	87.3	O K
4320 min Winter	34.673	0.073	0.0	3.0	3.0	76.9	O K
5760 min Winter	34.666	0.066	0.0	2.4	2.4	69.0	O K
7200 min Winter	34.660	0.060	0.0	2.0	2.0	62.7	O K
8640 min Winter	34.655	0.055	0.0	1.8	1.8	58.1	O K
10080 min Winter	34.652	0.052	0.0	1.6	1.6	54.7	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	1.114	0.0	313.0	4504			
10080 min Summer	0.981	0.0	316.6	5248			
15 min Winter	139.755	0.0	61.5	56			
30 min Winter	91.475	0.0	86.3	58			
60 min Winter	57.005	0.0	122.0	74			
120 min Winter	34.310	0.0	149.6	118			
180 min Winter	25.153	0.0	165.7	158			
240 min Winter	20.060	0.0	177.0	188			
360 min Winter	14.548	0.0	193.3	258			
480 min Winter	11.581	0.0	205.6	330			
600 min Winter	9.696	0.0	215.3	402			
720 min Winter	8.382	0.0	223.4	472			
960 min Winter	6.656	0.0	236.1	612			
1440 min Winter	4.803	0.0	253.4	878			
2160 min Winter	3.460	0.0	282.7	1252			
2880 min Winter	2.739	0.0	296.6	1612			
4320 min Winter	1.968	0.0	314.1	2352			
5760 min Winter	1.555	0.0	336.7	3120			
7200 min Winter	1.294	0.0	347.2	3832			
8640 min Winter	1.114	0.0	354.7	4584			
10080 min Winter	0.981	0.0	359.5	5344			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr + 40%	
Date 26/11/2018 12:24 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage Source Control 2017.1.2		

Cascade Rainfall Details for BlueRoof-01.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Green Roof

Area (m²)	1107	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)
0 4	0.020116	32 36	0.004061	64 68	0.000820	96 100	0.000166
4 8	0.016470	36 40	0.003325	68 72	0.000671	100 104	0.000136
8 12	0.013484	40 44	0.002722	72 76	0.000550	104 108	0.000111
12 16	0.011040	44 48	0.002229	76 80	0.000450	108 112	0.000091
16 20	0.009039	48 52	0.001825	80 84	0.000368	112 116	0.000074
20 24	0.007400	52 56	0.001494	84 88	0.000302	116 120	0.000061
24 28	0.006059	56 60	0.001223	88 92	0.000247		
28 32	0.004961	60 64	0.001002	92 96	0.000202		

Time Area Diagram

Total Area (ha) 0.176

Time (mins) From: To:	Area (ha)
0 4	0.176

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr + 40%	
Date 26/11/2018 12:24 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-01.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	1107.0	1107.0	1.300	0.0	1127.0
0.100	1107.0	1120.3	1.400	0.0	1127.0
0.200	0.0	1127.0	1.500	0.0	1127.0
0.300	0.0	1127.0	1.600	0.0	1127.0
0.400	0.0	1127.0	1.700	0.0	1127.0
0.500	0.0	1127.0	1.800	0.0	1127.0
0.600	0.0	1127.0	1.900	0.0	1127.0
0.700	0.0	1127.0	2.000	0.0	1127.0
0.800	0.0	1127.0	2.100	0.0	1127.0
0.900	0.0	1127.0	2.200	0.0	1127.0
1.000	0.0	1127.0	2.300	0.0	1127.0
1.100	0.0	1127.0	2.400	0.0	1127.0
1.200	0.0	1127.0	2.500	0.0	1127.0

Pipe Outflow Control

Diameter (m) 0.150 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Blue Roof 01 1:100yr + 40%				
Date 26/11/2018 12:25 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for BlueRoof-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	34.647	0.047	0.0	1.0	1.0	28.7	O K
10080 min Summer	34.645	0.045	0.0	0.9	0.9	27.1	O K
15 min Winter	34.651	0.051	0.0	1.2	1.2	30.9	O K
30 min Winter	34.666	0.066	0.0	2.0	2.0	40.3	O K
60 min Winter	34.683	0.083	0.0	2.7	2.7	50.2	O K
120 min Winter	34.697	0.097	0.0	3.6	3.6	58.8	O K
180 min Winter	34.700	0.100	0.0	3.8	3.8	60.8	O K
240 min Winter	34.701	0.101	0.0	3.8	3.8	61.1	O K
360 min Winter	34.700	0.100	0.0	3.8	3.8	61.0	O K
480 min Winter	34.699	0.099	0.0	3.7	3.7	59.9	O K
600 min Winter	34.696	0.096	0.0	3.5	3.5	58.5	O K
720 min Winter	34.694	0.094	0.0	3.4	3.4	57.0	O K
960 min Winter	34.689	0.089	0.0	3.1	3.1	54.1	O K
1440 min Winter	34.680	0.080	0.0	2.6	2.6	48.8	O K
2160 min Winter	34.670	0.070	0.0	2.1	2.1	42.5	O K
2880 min Winter	34.663	0.063	0.0	1.8	1.8	38.0	O K
4320 min Winter	34.654	0.054	0.0	1.4	1.4	32.8	O K
5760 min Winter	34.649	0.049	0.0	1.1	1.1	29.8	O K
7200 min Winter	34.645	0.045	0.0	0.9	0.9	27.5	O K
8640 min Winter	34.642	0.042	0.0	0.8	0.8	25.3	O K
10080 min Winter	34.639	0.039	0.0	0.7	0.7	23.6	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	1.114	0.0	140.1	4504			
10080 min Summer	0.981	0.0	141.4	5248			
15 min Winter	139.755	0.0	28.0	59			
30 min Winter	91.475	0.0	39.3	62			
60 min Winter	57.005	0.0	55.4	78			
120 min Winter	34.310	0.0	68.0	120			
180 min Winter	25.153	0.0	75.3	170			
240 min Winter	20.060	0.0	80.4	198			
360 min Winter	14.548	0.0	87.9	268			
480 min Winter	11.581	0.0	93.5	340			
600 min Winter	9.696	0.0	97.9	410			
720 min Winter	8.382	0.0	101.6	480			
960 min Winter	6.656	0.0	107.3	616			
1440 min Winter	4.803	0.0	115.2	880			
2160 min Winter	3.460	0.0	128.1	1256			
2880 min Winter	2.739	0.0	134.3	1616			
4320 min Winter	1.968	0.0	142.0	2332			
5760 min Winter	1.555	0.0	151.7	3064			
7200 min Winter	1.294	0.0	156.1	3888			
8640 min Winter	1.114	0.0	159.2	4584			
10080 min Winter	0.981	0.0	161.1	5344			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage Source Control 2017.1.2		

Cascade Rainfall Details for BlueRoof-02.SRCX

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.100	Shortest Storm (mins)	15
Ratio R	0.407	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Green Roof

Area (m³)	639	Evaporation (mm/day)	3
Depression Storage (mm)	5	Decay Coefficient	0.050

Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)	Time (mins) From: To:	Area (ha)
0 4	0.011612	32 36	0.002344	64 68	0.000473	96 100	0.000096
4 8	0.009507	36 40	0.001919	68 72	0.000388	100 104	0.000078
8 12	0.007784	40 44	0.001571	72 76	0.000317	104 108	0.000064
12 16	0.006373	44 48	0.001287	76 80	0.000260	108 112	0.000052
16 20	0.005218	48 52	0.001053	80 84	0.000213	112 116	0.000043
20 24	0.004272	52 56	0.000862	84 88	0.000174	116 120	0.000035
24 28	0.003497	56 60	0.000706	88 92	0.000143		
28 32	0.002863	60 64	0.000578	92 96	0.000117		

Time Area Diagram

Total Area (ha) 0.067

Time (mins) From: To:	Area (ha)
0 4	0.067

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Blue Roof 01 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for BlueRoof-02.SRCX

Storage is Online Cover Level (m) 35.000

Cellular Storage Structure

Invert Level (m) 34.600 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	639.0	639.0	1.300	0.0	654.2
0.100	639.0	649.1	1.400	0.0	654.2
0.200	0.0	654.2	1.500	0.0	654.2
0.300	0.0	654.2	1.600	0.0	654.2
0.400	0.0	654.2	1.700	0.0	654.2
0.500	0.0	654.2	1.800	0.0	654.2
0.600	0.0	654.2	1.900	0.0	654.2
0.700	0.0	654.2	2.000	0.0	654.2
0.800	0.0	654.2	2.100	0.0	654.2
0.900	0.0	654.2	2.200	0.0	654.2
1.000	0.0	654.2	2.300	0.0	654.2
1.100	0.0	654.2	2.400	0.0	654.2
1.200	0.0	654.2	2.500	0.0	654.2

Pipe Outflow Control

Diameter (m) 0.100 Entry Loss Coefficient 0.500
Slope (1:X) 1.0 Coefficient of Contraction 0.600
Length (m) 3.000 Upstream Invert Level (m) 34.600
Roughness k (mm) 0.600

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 01 1:100yr + 40%				
Date 26/11/2018 12:25 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-01.srcx</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	29.550	0.000	0.0	2.6	2.6	0.0	O K
10080 min Summer	29.550	0.000	0.0	2.3	2.3	0.0	O K
15 min Winter	29.941	0.391	0.0	4.0	4.0	72.5	O K
30 min Winter	30.069	0.519	0.0	4.0	4.0	96.1	O K
60 min Winter	30.191	0.641	0.0	4.0	4.0	118.8	O K
120 min Winter	30.281	0.731	0.0	4.0	4.0	135.4	O K
180 min Winter	30.301	0.751	0.0	4.0	4.0	139.2	O K
240 min Winter	30.299	0.749	0.0	4.0	4.0	138.7	O K
360 min Winter	30.267	0.717	0.0	4.0	4.0	132.8	O K
480 min Winter	30.229	0.679	0.0	4.0	4.0	125.9	O K
600 min Winter	30.197	0.647	0.0	4.0	4.0	119.8	O K
720 min Winter	30.163	0.613	0.0	4.0	4.0	113.6	O K
960 min Winter	30.094	0.544	0.0	4.0	4.0	100.8	O K
1440 min Winter	29.949	0.399	0.0	4.0	4.0	73.9	O K
2160 min Winter	29.732	0.182	0.0	4.0	4.0	33.7	O K
2880 min Winter	29.600	0.050	0.0	4.0	4.0	9.3	O K
4320 min Winter	29.550	0.000	0.0	3.3	3.3	0.0	O K
5760 min Winter	29.550	0.000	0.0	2.6	2.6	0.0	O K
7200 min Winter	29.550	0.000	0.0	2.2	2.2	0.0	O K
8640 min Winter	29.550	0.000	0.0	1.9	1.9	0.0	O K
10080 min Winter	29.550	0.000	0.0	1.7	1.7	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	1.114	0.0	333.0	0			
10080 min Summer	0.981	0.0	340.5	0			
15 min Winter	139.755	0.0	81.5	37			
30 min Winter	91.475	0.0	107.7	49			
60 min Winter	57.005	0.0	135.1	70			
120 min Winter	34.310	0.0	163.1	120			
180 min Winter	25.153	0.0	179.9	178			
240 min Winter	20.060	0.0	191.5	234			
360 min Winter	14.548	0.0	208.7	338			
480 min Winter	11.581	0.0	221.4	384			
600 min Winter	9.696	0.0	231.6	462			
720 min Winter	8.382	0.0	240.5	540			
960 min Winter	6.656	0.0	254.3	694			
1440 min Winter	4.803	0.0	275.0	996			
2160 min Winter	3.460	0.0	296.6	1336			
2880 min Winter	2.739	0.0	312.5	1624			
4320 min Winter	1.968	0.0	335.4	0			
5760 min Winter	1.555	0.0	351.9	0			
7200 min Winter	1.294	0.0	364.6	0			
8640 min Winter	1.114	0.0	375.0	0			
10080 min Winter	0.981	0.0	383.7	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr + 40%																																		
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Hydrobrake-01.srcx</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.167 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.167</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins) Area			From:	To:	(ha)	0	4	0.167
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+40																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.167																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-01.srcx

Storage is Online Cover Level (m) 30.650

Cellular Storage Structure

Invert Level (m) 29.550 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	195.0	195.0	1.300	0.0	242.5
0.100	195.0	200.6	1.400	0.0	242.5
0.200	195.0	206.2	1.500	0.0	242.5
0.300	195.0	211.8	1.600	0.0	242.5
0.400	195.0	217.3	1.700	0.0	242.5
0.500	195.0	222.9	1.800	0.0	242.5
0.600	195.0	228.5	1.900	0.0	242.5
0.700	195.0	234.1	2.000	0.0	242.5
0.800	195.0	239.7	2.100	0.0	242.5
0.900	0.0	242.5	2.200	0.0	242.5
1.000	0.0	242.5	2.300	0.0	242.5
1.100	0.0	242.5	2.400	0.0	242.5
1.200	0.0	242.5	2.500	0.0	242.5

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0095-4000-1000-4000
Design Head (m) 1.000
Design Flow (l/s) 4.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 95
Invert Level (m) 29.310
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	4.0
Flush-Flo™	0.294	4.0
Kick-Flo®	0.629	3.2
Mean Flow over Head Range	-	3.5

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 01 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.0	1.200	4.3	3.000	6.7	7.000	10.0
0.200	3.9	1.400	4.7	3.500	7.2	7.500	10.3
0.300	4.0	1.600	5.0	4.000	7.6	8.000	10.6
0.400	3.9	1.800	5.3	4.500	8.1	8.500	10.9
0.500	3.8	2.000	5.5	5.000	8.5	9.000	11.2
0.600	3.4	2.200	5.8	5.500	8.9	9.500	11.5
0.800	3.6	2.400	6.0	6.000	9.3		
1.000	4.0	2.600	6.2	6.500	9.6		

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 02 1:100yr + 40%				
Date 26/11/2018 12:25 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
7200 min Summer	29.393	0.043	0.0	6.4	6.4	20.8	O K
8640 min Summer	29.382	0.032	0.0	5.7	5.7	15.3	O K
10080 min Summer	29.373	0.023	0.0	5.1	5.1	11.3	O K
15 min Winter	29.526	0.176	0.0	8.0	8.0	85.4	O K
30 min Winter	29.579	0.229	0.0	8.0	8.0	111.0	O K
60 min Winter	29.639	0.289	0.0	8.0	8.0	140.1	O K
120 min Winter	29.721	0.371	0.0	8.0	8.0	179.8	O K
180 min Winter	29.771	0.421	0.0	8.0	8.0	204.1	O K
240 min Winter	29.796	0.446	0.0	8.0	8.0	216.2	O K
360 min Winter	29.822	0.472	0.0	8.0	8.0	228.9	O K
480 min Winter	29.834	0.484	0.0	8.0	8.0	234.6	O K
600 min Winter	29.837	0.487	0.0	8.0	8.0	236.1	O K
720 min Winter	29.833	0.483	0.0	8.0	8.0	234.0	O K
960 min Winter	29.806	0.456	0.0	8.0	8.0	221.0	O K
1440 min Winter	29.730	0.380	0.0	8.0	8.0	184.1	O K
2160 min Winter	29.621	0.271	0.0	8.0	8.0	131.4	O K
2880 min Winter	29.524	0.174	0.0	8.0	8.0	84.2	O K
4320 min Winter	29.415	0.065	0.0	7.6	7.6	31.5	O K
5760 min Winter	29.389	0.039	0.0	6.2	6.2	19.0	O K
7200 min Winter	29.375	0.025	0.0	5.2	5.2	12.0	O K
8640 min Winter	29.366	0.016	0.0	4.6	4.6	7.5	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
7200 min Summer	1.294	0.0	804.8	3816			
8640 min Summer	1.114	0.0	823.7	4496			
10080 min Summer	0.981	0.0	837.4	5240			
15 min Winter	139.755	0.0	180.6	18			
30 min Winter	91.475	0.0	245.5	33			
60 min Winter	57.005	0.0	327.1	122			
120 min Winter	34.310	0.0	398.6	218			
180 min Winter	25.153	0.0	440.2	286			
240 min Winter	20.060	0.0	469.5	330			
360 min Winter	14.548	0.0	512.0	418			
480 min Winter	11.581	0.0	544.3	504			
600 min Winter	9.696	0.0	569.6	598			
720 min Winter	8.382	0.0	591.2	708			
960 min Winter	6.656	0.0	625.1	900			
1440 min Winter	4.803	0.0	673.2	1132			
2160 min Winter	3.460	0.0	739.5	1496			
2880 min Winter	2.739	0.0	777.4	1844			
4320 min Winter	1.968	0.0	828.1	2420			
5760 min Winter	1.555	0.0	879.0	3120			
7200 min Winter	1.294	0.0	908.4	3888			
8640 min Winter	1.114	0.0	931.0	4568			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-02.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
10080 min Winter	29.358	0.008	0.0	4.0	4.0	4.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
10080 min Winter	0.981	0.0	947.7	5248

Infrastructure Design Limited		Page 4																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr + 40%																																		
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Hydrobrake-02.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.199 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.199</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins) Area			From:	To:	(ha)	0	4	0.199
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+40																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.199																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-02.SRCX

Storage is Online Cover Level (m) 30.630

Cellular Storage Structure

Invert Level (m) 29.350 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	510.0	510.0	1.300	0.0	559.7
0.100	510.0	519.0	1.400	0.0	559.7
0.200	510.0	528.1	1.500	0.0	559.7
0.300	510.0	537.1	1.600	0.0	559.7
0.400	510.0	546.1	1.700	0.0	559.7
0.500	510.0	555.2	1.800	0.0	559.7
0.600	0.0	559.7	1.900	0.0	559.7
0.700	0.0	559.7	2.000	0.0	559.7
0.800	0.0	559.7	2.100	0.0	559.7
0.900	0.0	559.7	2.200	0.0	559.7
1.000	0.0	559.7	2.300	0.0	559.7
1.100	0.0	559.7	2.400	0.0	559.7
1.200	0.0	559.7	2.500	0.0	559.7

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0136-8000-0680-8000
Design Head (m) 0.680
Design Flow (l/s) 8.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 136
Invert Level (m) 29.270
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.680	8.0
Flush-Flo™	0.231	8.0
Kick-Flo®	0.492	6.9
Mean Flow over Head Range	-	6.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 02 1:100yr + 40%	
Date 26/11/2018 12:25 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum Outflow Control

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.9	1.200	10.4	3.000	16.1	7.000	24.1
0.200	7.9	1.400	11.2	3.500	17.4	7.500	25.0
0.300	7.9	1.600	12.0	4.000	18.5	8.000	25.8
0.400	7.6	1.800	12.6	4.500	19.6	8.500	26.6
0.500	6.9	2.000	13.3	5.000	20.6	9.000	27.4
0.600	7.5	2.200	13.9	5.500	21.6	9.500	28.1
0.800	8.6	2.400	14.5	6.000	22.5		
1.000	9.6	2.600	15.1	6.500	23.4		

Infrastructure Design Limited							Page 2
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Hydrobrake 03 1:100yr + 40%				
Date 26/11/2018 14:19 File Cascade.casx			Designed by IDL Checked by PT				
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Hydrobrake-03.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
5760 min Summer	29.551	0.601	0.0	11.0	11.0	178.1	O K
7200 min Summer	29.522	0.572	0.0	9.1	9.1	169.4	O K
8640 min Summer	29.490	0.540	0.0	7.0	7.0	160.1	O K
10080 min Summer	29.400	0.450	0.0	6.0	6.0	133.5	O K
15 min Winter	29.475	0.525	0.0	6.4	6.4	155.5	O K
30 min Winter	29.544	0.594	0.0	10.6	10.6	176.2	O K
60 min Winter	29.559	0.609	0.0	11.7	11.7	180.5	O K
120 min Winter	29.561	0.611	0.0	11.9	11.9	181.0	O K
180 min Winter	29.561	0.611	0.0	11.9	11.9	181.1	O K
240 min Winter	29.561	0.611	0.0	11.9	11.9	181.1	O K
360 min Winter	29.573	0.623	0.0	12.9	12.9	184.6	O K
480 min Winter	29.576	0.626	0.0	13.2	13.2	185.6	O K
600 min Winter	29.583	0.633	0.0	13.8	13.8	187.6	O K
720 min Winter	29.587	0.637	0.0	14.2	14.2	188.8	O K
960 min Winter	29.590	0.640	0.0	14.5	14.5	189.8	O K
1440 min Winter	29.593	0.643	0.0	14.7	14.7	190.6	O K
2160 min Winter	29.594	0.644	0.0	14.8	14.8	190.8	O K
2880 min Winter	29.590	0.640	0.0	14.5	14.5	189.7	O K
4320 min Winter	29.567	0.617	0.0	12.4	12.4	182.8	O K
5760 min Winter	29.532	0.582	0.0	9.8	9.8	172.5	O K
7200 min Winter	29.499	0.549	0.0	7.5	7.5	162.8	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
5760 min Summer	1.555	0.0	1302.0	3200			
7200 min Summer	1.294	0.0	1347.6	4024			
8640 min Summer	1.114	0.0	1382.9	4928			
10080 min Summer	0.981	0.0	1409.6	5840			
15 min Winter	139.755	0.0	317.0	351			
30 min Winter	91.475	0.0	425.3	389			
60 min Winter	57.005	0.0	551.8	522			
120 min Winter	34.310	0.0	669.8	694			
180 min Winter	25.153	0.0	739.1	804			
240 min Winter	20.060	0.0	787.6	864			
360 min Winter	14.548	0.0	858.2	348			
480 min Winter	11.581	0.0	911.6	442			
600 min Winter	9.696	0.0	954.0	444			
720 min Winter	8.382	0.0	990.4	510			
960 min Winter	6.656	0.0	1047.5	644			
1440 min Winter	4.803	0.0	1130.3	890			
2160 min Winter	3.460	0.0	1232.7	1276			
2880 min Winter	2.739	0.0	1297.6	1664			
4320 min Winter	1.968	0.0	1387.1	2424			
5760 min Winter	1.555	0.0	1466.9	3280			
7200 min Winter	1.294	0.0	1518.2	4256			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr + 40%	
Date 26/11/2018 14:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Summary of Results for Hydrobrake-03.SRCX

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m ³)	Status
8640 min Winter	29.373	0.423	0.0	6.0	6.0	125.3	O K
10080 min Winter	29.104	0.154	0.0	6.0	6.0	45.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Discharge Volume (m ³)	Time-Peak (mins)
8640 min Winter	1.114	0.0	1558.8	5360
10080 min Winter	0.981	0.0	1591.4	5816

Infrastructure Design Limited		Page 4																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr + 40%																																		
Date 26/11/2018 14:19 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Hydrobrake-03.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.188 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.188</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins) Area			From:	To:	(ha)	0	4	0.188
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+40																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.188																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 5
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr + 40%	
Date 26/11/2018 14:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Cascade Model Details for Hydrobrake-03.SRCX

Storage is Online Cover Level (m) 30.550

Cellular Storage Structure

Invert Level (m) 28.950 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	312.0	312.0	1.300	0.0	372.1
0.100	312.0	319.1	1.400	0.0	372.1
0.200	312.0	326.1	1.500	0.0	372.1
0.300	312.0	333.2	1.600	0.0	372.1
0.400	312.0	340.3	1.700	0.0	372.1
0.500	312.0	347.3	1.800	0.0	372.1
0.600	312.0	354.4	1.900	0.0	372.1
0.700	312.0	361.5	2.000	0.0	372.1
0.800	312.0	368.5	2.100	0.0	372.1
0.900	0.0	372.1	2.200	0.0	372.1
1.000	0.0	372.1	2.300	0.0	372.1
1.100	0.0	372.1	2.400	0.0	372.1
1.200	0.0	372.1	2.500	0.0	372.1

Complex Outflow Control

Hydro-Brake® Optimum

Unit Reference MD-SHE-0121-6000-0600-6000
Design Head (m) 0.600
Design Flow (l/s) 6.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 121
Invert Level (m) 28.850
Minimum Outlet Pipe Diameter (mm) 150
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.600	6.0
Flush-Flo™	0.202	6.0
Kick-Flo®	0.435	5.2
Mean Flow over Head Range	-	5.0

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

©1982-2017 XP Solutions

Infrastructure Design Limited		Page 6
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Hydrobrake 03 1:100yr + 40%	
Date 26/11/2018 14:19 File Cascade.casx	Designed by IDL Checked by PT	
Micro Drainage		Source Control 2017.1.2

Hydro-Brake® Optimum

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.3	1.200	8.3	3.000	12.8	7.000	19.2
0.200	6.0	1.400	8.9	3.500	13.8	7.500	19.9
0.300	5.9	1.600	9.5	4.000	14.7	8.000	20.5
0.400	5.5	1.800	10.0	4.500	15.5	8.500	21.1
0.500	5.5	2.000	10.6	5.000	16.3	9.000	21.8
0.600	6.0	2.200	11.0	5.500	17.1	9.500	22.4
0.800	6.9	2.400	11.5	6.000	17.8		
1.000	7.6	2.600	12.0	6.500	18.5		

Orifice

Diameter (m) 0.125 Discharge Coefficient 0.600 Invert Level (m) 29.450

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB01 1:100yr + 40%				
Date 26/11/2018 12:26 File Cascade.casx		Designed by IDL Checked by PT					
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB01.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.044	0.064	0.0	1.1	1.1	0.5	O K
10080 min Summer	30.041	0.061	0.0	1.0	1.0	0.5	O K
15 min Winter	30.369	0.389	0.0	24.8	24.8	20.4	O K
30 min Winter	30.381	0.401	0.0	25.2	25.2	21.7	O K
60 min Winter	30.346	0.366	0.0	23.9	23.9	18.1	O K
120 min Winter	30.262	0.282	0.0	20.3	20.3	10.8	O K
180 min Winter	30.210	0.230	0.0	17.0	17.0	7.1	O K
240 min Winter	30.183	0.203	0.0	14.0	14.0	5.6	O K
360 min Winter	30.150	0.170	0.0	10.3	10.3	3.9	O K
480 min Winter	30.131	0.151	0.0	8.3	8.3	3.1	O K
600 min Winter	30.119	0.139	0.0	7.0	7.0	2.6	O K
720 min Winter	30.107	0.127	0.0	6.0	6.0	2.2	O K
960 min Winter	30.091	0.111	0.0	4.8	4.8	1.7	O K
1440 min Winter	30.078	0.098	0.0	3.5	3.5	1.3	O K
2160 min Winter	30.067	0.087	0.0	2.5	2.5	1.0	O K
2880 min Winter	30.059	0.079	0.0	2.0	2.0	0.8	O K
4320 min Winter	30.049	0.069	0.0	1.4	1.4	0.6	O K
5760 min Winter	30.044	0.064	0.0	1.1	1.1	0.5	O K
7200 min Winter	30.040	0.060	0.0	0.9	0.9	0.5	O K
8640 min Winter	30.037	0.057	0.0	0.8	0.8	0.4	O K
10080 min Winter	30.034	0.054	0.0	0.7	0.7	0.4	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	1.114	0.0	132.1	4384			
10080 min Summer	0.981	0.0	134.0	5088			
15 min Winter	139.755	0.0	32.6	14			
30 min Winter	91.475	0.0	43.7	23			
60 min Winter	57.005	0.0	55.3	40			
120 min Winter	34.310	0.0	67.2	70			
180 min Winter	25.153	0.0	74.2	98			
240 min Winter	20.060	0.0	79.1	128			
360 min Winter	14.548	0.0	86.2	188			
480 min Winter	11.581	0.0	91.5	248			
600 min Winter	9.696	0.0	95.8	308			
720 min Winter	8.382	0.0	99.4	368			
960 min Winter	6.656	0.0	105.1	488			
1440 min Winter	4.803	0.0	113.5	722			
2160 min Winter	3.460	0.0	122.1	1084			
2880 min Winter	2.739	0.0	128.2	1424			
4320 min Winter	1.968	0.0	136.7	2200			
5760 min Winter	1.555	0.0	142.5	2808			
7200 min Winter	1.294	0.0	146.7	3560			
8640 min Winter	1.114	0.0	150.0	4368			
10080 min Winter	0.981	0.0	152.5	5120			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:100yr + 40%																																		
Date 26/11/2018 12:26 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB01.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.123 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.123</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins) Area			From:	To:	(ha)	0	4	0.123
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+40																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.123																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB01 1:100yr + 40%																																									
Date 26/11/2018 12:26 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage		Source Control 2017.1.2																																								
<u>Cascade Model Details for Porous-CP-to-HB01.SRCX</u> Storage is Online Cover Level (m) 30.590 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>6.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>115.0</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>191.7</td> <td>Slope (1:X)</td> <td>150.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>29.980</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>30.000</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	115.0	Max Percolation (l/s)	191.7	Slope (1:X)	150.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	29.980	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	30.000	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	115.0																																							
Max Percolation (l/s)	191.7	Slope (1:X)	150.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	29.980	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	30.000																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Infrastructure Design Limited						Page 2	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU			Chailey Ind Est Porous CP to HB02 1:100yr + 40%				
Date 26/11/2018 12:26 File Cascade.casx		Designed by IDL Checked by PT					
Micro Drainage			Source Control 2017.1.2				
<u>Cascade Summary of Results for Porous-CP-to-HB02.SRCX</u>							
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
8640 min Summer	30.020	0.000	0.0	1.1	1.1	0.0	O K
10080 min Summer	30.020	0.000	0.0	0.9	0.9	0.0	O K
15 min Winter	30.380	0.360	0.0	52.0	52.0	6.2	O K
30 min Winter	30.259	0.239	0.0	49.9	49.9	2.7	O K
60 min Winter	30.020	0.000	0.0	39.9	39.9	0.0	O K
120 min Winter	30.020	0.000	0.0	24.3	24.3	0.0	O K
180 min Winter	30.020	0.000	0.0	17.9	17.9	0.0	O K
240 min Winter	30.020	0.000	0.0	14.3	14.3	0.0	O K
360 min Winter	30.020	0.000	0.0	10.4	10.4	0.0	O K
480 min Winter	30.020	0.000	0.0	8.2	8.2	0.0	O K
600 min Winter	30.020	0.000	0.0	6.9	6.9	0.0	O K
720 min Winter	30.020	0.000	0.0	6.0	6.0	0.0	O K
960 min Winter	30.020	0.000	0.0	4.7	4.7	0.0	O K
1440 min Winter	30.020	0.000	0.0	3.4	3.4	0.0	O K
2160 min Winter	30.020	0.000	0.0	2.4	2.4	0.0	O K
2880 min Winter	30.020	0.000	0.0	1.9	1.9	0.0	O K
4320 min Winter	30.020	0.000	0.0	1.4	1.4	0.0	O K
5760 min Winter	30.020	0.000	0.0	1.1	1.1	0.0	O K
7200 min Winter	30.020	0.000	0.0	0.9	0.9	0.0	O K
8640 min Winter	30.020	0.000	0.0	0.8	0.8	0.0	O K
10080 min Winter	30.020	0.000	0.0	0.7	0.7	0.0	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)			
8640 min Summer	1.114	0.0	131.5	0			
10080 min Summer	0.981	0.0	133.7	0			
15 min Winter	139.755	0.0	32.9	12			
30 min Winter	91.475	0.0	43.7	20			
60 min Winter	57.005	0.0	54.8	0			
120 min Winter	34.310	0.0	66.5	0			
180 min Winter	25.153	0.0	73.4	0			
240 min Winter	20.060	0.0	78.2	0			
360 min Winter	14.548	0.0	85.2	0			
480 min Winter	11.581	0.0	90.5	0			
600 min Winter	9.696	0.0	94.7	0			
720 min Winter	8.382	0.0	98.3	0			
960 min Winter	6.656	0.0	104.0	0			
1440 min Winter	4.803	0.0	112.3	0			
2160 min Winter	3.460	0.0	120.8	0			
2880 min Winter	2.739	0.0	126.9	0			
4320 min Winter	1.968	0.0	135.5	0			
5760 min Winter	1.555	0.0	141.4	0			
7200 min Winter	1.294	0.0	145.7	0			
8640 min Winter	1.114	0.0	149.1	0			
10080 min Winter	0.981	0.0	151.8	0			
©1982-2017 XP Solutions							

Infrastructure Design Limited		Page 3																																	
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:100yr + 40%																																		
Date 26/11/2018 12:26 File Cascade.casx	Designed by IDL Checked by PT																																		
Micro Drainage		Source Control 2017.1.2																																	
<u>Cascade Rainfall Details for Porous-CP-to-HB02.SRCX</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Winter Storms</td> <td>Yes</td> </tr> <tr> <td>Return Period (years)</td> <td>100</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.100</td> <td>Shortest Storm (mins)</td> <td>15</td> </tr> <tr> <td>Ratio R</td> <td>0.407</td> <td>Longest Storm (mins)</td> <td>10080</td> </tr> <tr> <td>Summer Storms</td> <td>Yes</td> <td>Climate Change %</td> <td>+40</td> </tr> </table> <u>Time Area Diagram</u> Total Area (ha) 0.121 <table> <tr> <th align="left" colspan="3">Time (mins) Area</th> </tr> <tr> <th align="left">From:</th> <th align="left">To:</th> <th align="left">(ha)</th> </tr> <tr> <td>0</td> <td>4</td> <td>0.121</td> </tr> </table>			Rainfall Model	FSR	Winter Storms	Yes	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.100	Shortest Storm (mins)	15	Ratio R	0.407	Longest Storm (mins)	10080	Summer Storms	Yes	Climate Change %	+40	Time (mins) Area			From:	To:	(ha)	0	4	0.121
Rainfall Model	FSR	Winter Storms	Yes																																
Return Period (years)	100	Cv (Summer)	0.750																																
Region	England and Wales	Cv (Winter)	0.840																																
M5-60 (mm)	20.100	Shortest Storm (mins)	15																																
Ratio R	0.407	Longest Storm (mins)	10080																																
Summer Storms	Yes	Climate Change %	+40																																
Time (mins) Area																																			
From:	To:	(ha)																																	
0	4	0.121																																	
©1982-2017 XP Solutions																																			

Infrastructure Design Limited		Page 4																																								
33 The Point Rockingham Road Market Harborough Leicestershire LE16 7QU	Chailey Ind Est Porous CP to HB02 1:100yr + 40%																																									
Date 26/11/2018 12:26 File Cascade.casx	Designed by IDL Checked by PT																																									
Micro Drainage Source Control 2017.1.2																																										
<u>Cascade Model Details for Porous-CP-to-HB02.SRCX</u> Storage is Online Cover Level (m) 30.630 <u>Porous Car Park Structure</u> <table> <tr> <td>Infiltration Coefficient Base (m/hr)</td> <td>0.00000</td> <td>Width (m)</td> <td>8.0</td> </tr> <tr> <td>Membrane Percolation (mm/hr)</td> <td>1000</td> <td>Length (m)</td> <td>76.3</td> </tr> <tr> <td>Max Percolation (l/s)</td> <td>169.6</td> <td>Slope (1:X)</td> <td>40.0</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Depression Storage (mm)</td> <td>5</td> </tr> <tr> <td>Porosity</td> <td>0.30</td> <td>Evaporation (mm/day)</td> <td>3</td> </tr> <tr> <td>Invert Level (m)</td> <td>30.020</td> <td>Membrane Depth (m)</td> <td>0</td> </tr> </table> <u>Pipe Outflow Control</u> <table> <tr> <td>Diameter (m)</td> <td>0.150</td> <td>Entry Loss Coefficient</td> <td>0.500</td> </tr> <tr> <td>Slope (1:X)</td> <td>80.0</td> <td>Coefficient of Contraction</td> <td>0.600</td> </tr> <tr> <td>Length (m)</td> <td>10.000</td> <td>Upstream Invert Level (m)</td> <td>28.850</td> </tr> <tr> <td>Roughness k (mm)</td> <td>0.600</td> <td></td> <td></td> </tr> </table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0	Membrane Percolation (mm/hr)	1000	Length (m)	76.3	Max Percolation (l/s)	169.6	Slope (1:X)	40.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	30.020	Membrane Depth (m)	0	Diameter (m)	0.150	Entry Loss Coefficient	0.500	Slope (1:X)	80.0	Coefficient of Contraction	0.600	Length (m)	10.000	Upstream Invert Level (m)	28.850	Roughness k (mm)	0.600		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.0																																							
Membrane Percolation (mm/hr)	1000	Length (m)	76.3																																							
Max Percolation (l/s)	169.6	Slope (1:X)	40.0																																							
Safety Factor	2.0	Depression Storage (mm)	5																																							
Porosity	0.30	Evaporation (mm/day)	3																																							
Invert Level (m)	30.020	Membrane Depth (m)	0																																							
Diameter (m)	0.150	Entry Loss Coefficient	0.500																																							
Slope (1:X)	80.0	Coefficient of Contraction	0.600																																							
Length (m)	10.000	Upstream Invert Level (m)	28.850																																							
Roughness k (mm)	0.600																																									
©1982-2017 XP Solutions																																										

Appendix C – Maintenance and Management Requirements

The Management Company

The responsibility for maintenance of all elements of the development remain with Fairview until handed over to the Management Company.

Handover of external works to the Management Company coincides with completion of the final residential unit.

The Management Company employs a specialist Managing Agent to manage the development which includes all aspects of maintenance.

The Management Company BI registered No. 'tbc' was incorporated in 'tbc' and its directors are currently made up of Fairview representatives plus an appointment from the Managing Agent.

The Managing Agents are 'tbc' who have over 'tbc' years' experience in the industry.

At handover the Management Company and Managing Agent receive as built information together with operating and maintenance manuals which detail all maintenance protocols.

Approximately 1 year following completion of the final unit the residents will be invited to elect members to become directors of the Management Company, the Fairview appointed directors at that time resign from the Management Company to be replaced by the elected representatives of the residents.

To ensure continuity and a full understanding of the development and the operation and maintenance of its various components the representative of the Managing Agent remains as a director of the Management Company and the appointment of the Managing Agents is fixed for a minimum period of two years following the date of resignation of the last Fairview director.

After that two year period the Management Company have the right to re-tender the Managing Agent services but it is very rare that a change is made as our original appointments provide an excellent service.

Within the first two years from the final unit completion on the development the residents have two ways in which they can report any defects and problems which would include flooding and that is either to our Aftersales department or to the Managing Agents, the residents are issued with telephone numbers for both which include out of hours emergency response.

After two years our Aftersales contacts are normally replaced by members of the Management Company. The residents therefore have the ability to contact them or the Managing Agents which then remains through the life of the development.

Attenuation (and surface water drainage system generally)

The principle means of surface water disposal from the development is by way of shallow infiltration and cellular attenuation. The latter of these take the form of buried crate-based storage system.

The Management Company will ensure that the following measures are undertaken to ensure the longevity of the surface water drainage system;

Quarterly

- i) Inspect the performance of the attenuation system by lifting the cover of the chamber(s) immediately upstream of each feature and check that the outlet pipe (into the crates) is free of obstruction and visible (ie not submerged). If the outlet pipe is submerged then remedial action may be required. Remedial advice to be sought from a suitably qualified consulting infrastructure engineer.

Every 6 months

- i) Remove silt build up from *all* catchpits and road gullies.

Annually

- i) Select approx. 20% of the development's surface water inspection chambers (situated in accessible non-private areas) and inspect for blockages / silt build up. Remove silt and debris. Rotate on a 5 yearly cycle to cover all such chambers over this period.

Every 2-5 years (depending on outcome of aforementioned inspections)

- i) Commission a CCTV survey and report on condition of the surface water piped drainage system upstream of the soakaways to check for structural integrity and hydraulic fluidity. Carry out promptly any remedial work as advised by CCTV company.

Permeable Paving

The access road and external parking areas are to be constructed in permeable block paving in order to;

- a) Delay the surface water runoff from these areas, and adjacent driveways, into the ground below, and
- b) Enhance the quality of the rainwater percolating through the surface before discharging into the drainage system.

The Freeholders and Management Company will ensure that the following measures are undertaken to ensure the longevity of the pervious pavement;

Quarterly

- i) Inspect the pervious pavement for signs of ponding and ensure there is no migration of soils from adjacent landscaped areas or other deleterious material that may prematurely clog up the jointing stone situated in the gaps between the blocks. Ideally this type of inspection should be undertaken immediately following a heavy rainfall event.
- ii) Commission vacuum sweeping and brushing of the pervious pavement to ensure joints are kept free of silt. Minimum 3 sweeping per year, thus;
 - a) End of Winter (April) – to collect winter debris
 - b) Mid-Summer (July/August) – to collect dust, flower and grass-type deposits.
 - c) After Autumn leaf fall (November)

The company commissioned to carry out this work should ensure that their vacuum equipment is adjusted accordingly to avoid removal of jointing material. Any lost material should be replaced promptly to avoid the blocks from being dislodged.

Last Resort Remedial Action

- i) Should a portion of the pervious pavement become substantially impervious due to excessive siltation, the following procedure should be followed;
 - a) Lift block paving and laying course
 - b) Break out underlying bitmac base layer and replace with similar compacted depth of course aggregate subbase material to BS EN 13242:2002 Type 4/20, wrapped in geotextile as Terram 1000 or similar.
 - c) Renew laying course, replace blocks and renew jointing material

NB. Material removed from the voids or the layers below the surface may contain heavy metals and hydrocarbons and as such may need to be disposed of as 'controlled waste'. Sediment testing should be carried out before disposal to confirm its classification and appropriate disposal methods.

Blue Roofs

Landscaped Podium decks incorporate a Blue Roof system which comprises void formers and outlets in addition to the water-proofing layers and soil/planting zones. They are provided in order to;

- a) Collect and delay the surface water runoff from these areas and adjacent rainwater pipes, into the drainage system below.
- c) Enhance the quality of the rainwater percolating through the surface before discharging into the drainage system below.

The Freeholders and Management Company will ensure that the following measures are undertaken to ensure the longevity of the Blue Roof system;

1. Following any significant storm event, the outlets should be visually inspected to ensure no blockage has occurred.
2. Following any significant traffic or remedial works that take place on or around the roof, each of the outlets should be visually inspected to ensure all drainage holes are clear and free draining.
3. Quarterly each outlet, should be inspected and cleared of any build up or debris. All leaf litter mainly during an autumnal visit, should be removed from the roof surface. Debris must be removed from the roof and not simply flushed down rainwater pipes.

It is also recommend during maintenance visits to visually inspect the waterproofing system at all upstands, to ensure it is firmly adhered to the detail that it is waterproofing.