

SOAKWAYS attenuated crates

- To be designed for 1m3 for every 16m² of roof serving it.
- Not less than 5 m. from buildings. Depth 600 mm below invert level of drains.
- Use modular attenuation cells of lightweight plastic structure with a high void ratio.
- Beneath the unit & on all sides provide 100mm of gravel and on top 500mm cover including 100mm gravel layer.
- Size of the hole to be 1600mm deep and 1200mm sq.

Pipe to 100mm dia. and 1: 40 fall.
Where the pipe enters the soakaway it should be surrounded by gravel.

All to meet building inspectors approval on site.



NEIGHBOURS HOUSE Feldon

There are no side windows on the two storey element for neighbours property "Feldon" Please refer to photo on drawing number 10.

12 PROP GF
Scale: 1:100

tel : 0796 222 3141
email : sandeep@sskarchitects.co.uk



scale 1 : 100 @ A3

2m 4m 6m 8m

0 1m 3m 5m 7m 9m

All dimensions to be checked on site.
All omissions & discrepancies to be reported to the designer.

© SSK architects owns the copyright of this drawing which must not be reproduced in any manner.


ing application
OJ07 Kew Lodge, Dene Road, DATE:
Northwood, HA6 2DA 25/06/2022

VG NO: PROP GF	12	REVISION: A
--------------------------	-----------	-----------------------

scale - 1 : 100 @ A3

12

PROPOSED



REV A - 23/08/22
Tree protection information
added

Purpose - Householder planning application

All dimensions to be checked on site.
All omissions & discrepancies to be reported to the designer.

C SSK architects owns the copyright of this drawing which must not be reproduced in whole or part without the written permission.

PROJECT: Kew Lodge, Dene Road, Northwood, HA6 2DA DATE: 25/06/2022

DWG NO: **PROP GF** 12 REVISION: **A**

12