



KEY	
	Planning Boundary
	Extent of Section 278 Works
	Works To Be Carried out in Phase 2
	Root Protection Area All works within RPA to be referred to Arboricultural Consultant and subject to AMS
	Bitumen Macadam Surface With Coloured Wearing Course
	Permeable Bitumen Macadam Surface With Coloured Wearing Course
	Sandstone Flags
	Sandstone Flags
	Bitumen Macadam Surface With Standard Black-top Wearing Course
	Concrete Kerb
	Aluminium Edge

	Existing Wall To Be Retained
	Brick Wall To Architects Details
	Proposed Brick Wall
	King Post Temporary Retaining Wall System
	Brick Pillar
	Timber Fence
	Timber Bench
	Timber Picnic Bench
	Play Equipment
	Visitor Cycle Stands
	Demountable Bollards

	Pedestrian Gates To Architects & Engineers Details
	Vehicle Gates To Architects & Engineers Details
	Existing Tree To Be Retained Refer to Arboricultural Survey by Tamla Tree Consultants for AMS
	Proposed Specimen Tree
	Large Shrub
	Proposed Hedge
	Mixed Shrub And Herbaceous Planting
	Proposed Tree Grill and Tree Guard
	Gravel Margin

	Fence line and with gates. 1200mm high. Pedestrian gate and sliding vehicular gate. Refer to Arcadis drawing 146280-ARC-DT-A-700410 & 146280-ARC-EL-A-700411
	Sandstone Flags with Hazard Warning Texture to denote path crossing vehicle route.

1. All dimensions in millimetres unless otherwise shown.
2. All levels in metres above Ordinance Datum (mAOD) unless otherwise shown.
3. All dimensions to be checked on site and any discrepancies reported to Employer before pricing / work starts.
4. Any ambiguities or discrepancies within this drawing and any other information given elsewhere must be reported to Camlins and the Employer for clarification before pricing work proceeds.
5. All drawings to be read in conjunction with other Camlins drawings and specification information as appropriate.
6. Refer to relevant Engineer's and Architect's information as appropriate for confirmation of all engineering and architectural details.
7. All works to be carried out in accordance with the latest British Standards and appropriate codes of practice as a minimum.

P01	8/12/25	Addition of fence line, pedestrian and vehicle gates to Pinner Road frontage. New footpath route designation from Pinner Road. 1.5m wide. Bollards to footpath route. Planting extended adjacent pedestrian entrance. Disabled parking bay lines updated as per approved document part M. Phase 2 area of works denoted. Signage added including white lining arrows and no entry signs.	HS	JS
Rev.	Date	Description	Revised by Checked by	

Camlins
New Zealand House, Abbey Foregate,
Shrewsbury, Shropshire, SY2 6FD
01743 298 779
www.camlins.com

Northwood Cottage Hospital
Logan Construction

General Arrangement - Ground Floor Landscape Plan

Status Planning	Drawn by JS	Checked by MSS
Drawing Number SY752-100-0001	Revision P01	Scale 1:200
		Date 25.11.2025