





Appendix 8.3

GROUNDWATER RISK ASSESSMENT







Groundwater Risk Assessment

Broadwater Lake – Hillingdon Water Sports Facility and Activity Centre.

On behalf of

London borough of Hillingdon

Quality Management

Prepared by:	Scott Greaves BSc MSc FGS	
Reviewed by:	Chris Betts BSc MSc FGS CGeol 	
Reviewed & Authorised by:	Mike Willis BSc MSc FGS	
Date:	August 2025	
Revision:	FINAL	
Project Number:	HYG1120	
Document Reference:	HYG1120 R 2300921 SG Groundwater Risk Assessment.docx	
Document File Path:	C:\Users\Scott\mike willis\Mike Willis - Projects\HYG1120 Outdoor Activity Centre, London Borough of Hillingdon\Reports\Groundwater Risk Assessment\Draft\HYG1120 R 2300921 SG Groundwater Risk Assessment.docx	

COPYRIGHT © Hydrogeo

This report has been produced by Hydrogeo within the terms of the contract with the client and taking account of the resources devoted to it by agreement with the client.

We disclaim any responsibility to the client and others in respect of any matters outside the scope of the above.

This report is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the report at their own risk.

Hydrogeo Ltd
Unit 4 Waddington House
Llanover Business Centre
Llanover
Monmouthshire
NP7 5NT
T: 01873 856813
E: mike@hydrogeo.co.uk
W: hydrogeo.co.uk



Contents

Quality Management	i
Contents	ii
1 Introduction	1
1.1 Background.....	1
1.2 Data Sources & Third-Party Information	2
2 Site Setting and Development Description	3
2.1 Introduction.....	3
2.2 Proposed Development Description	6
3 Environmental Setting	8
3.1 Geology	8
Artificial Geology.....	8
Superficial Geology.....	8
Bedrock Geology	8
BGS Borehole Logs	9
Site Investigation Boreholes.....	10
3.2 Hydrogeology	10
Aquifer Classification	10
Superficial Deposits.....	11
Bedrock Geology	11
BGS Hydrogeology Map	11
3.3 Groundwater Levels	11
Groundwater Levels – Site Investigation and Monitoring.....	12
3.4 Licensed Abstractions	13
3.5 Private Water Supplies	14
3.6 Hydrology.....	15
3.7 Environmental Designations.....	17

4 Site Investigation – Land Based	19
4.1 Introduction.....	19
4.2 Site Investigation	19
4.3 Encountered Ground Conditions.....	20
<i>Concrete Hardstanding</i>	<i>20</i>
<i>Made Ground / Reworked Ground</i>	<i>22</i>
<i>Alluvium 22</i>	
<i>Shepperton Gravel Member.....</i>	<i>22</i>
<i>Chalk 23</i>	
4.4 Encountered Contamination and Chemical Testing.....	24
<i>Laboratory Chemical Testing</i>	<i>24</i>
<i>Soil Screening Results.....</i>	<i>24</i>
<i>Leachate and Groundwater Sample Screening Results</i>	<i>25</i>
5 Site Investigation – Broadwater Lake.....	26
5.1 Introduction.....	26
5.2 Johns Associates Broadwater Lake Sediment Sampling – April 2023	26
<i>Lake Sediment Screening</i>	<i>28</i>
5.3 Johns Associates Broadwater Lake Sediment Sampling March 2025	29
<i>Lake Sediment Screening.....</i>	<i>31</i>
<i>Chemical Testing Results</i>	<i>31</i>
<i>Potentially Toxic Elements (PTE).....</i>	<i>31</i>
<i>Chemical Testing Results</i>	<i>33</i>
<i>Potentially Toxic Elements (PTE).....</i>	<i>33</i>
5.4 Miles Water Engineering Broadwater Lake Ground Investigation July 2023	33
5.5 Greengage Broadwater Lake Submarine Survey September & October 2024, and March 2025	34
35	
6 Broadwater Lake Surface Water Samples.....	36

6.1 Introduction.....	36
6.2 Laboratory Analysis and Chemical Screening	37
<i>Surface Water Sample Screening.....</i>	<i>37</i>
<i>Ammoniacal Nitrogen.....</i>	<i>37</i>
<i>Nitrate as N.....</i>	<i>37</i>
<i>Phosphate, Total inorganic as P / Orthophosphate as P</i>	<i>37</i>
7 Conceptual Hydrogeological Model	38
7.1 Conceptual Hydrogeological Model	38
7.2 Sources	41
7.3 Pathways	43
7.4 Receptors	44
8 Risk Assessment	45
<i>Made Ground and Contamination Hotspot.....</i>	<i>45</i>
<i>Piling 47</i>	
<i>Dredging 47</i>	
<i>Horizontal Direction Drilling (HDD).....</i>	<i>47</i>
<i>Proposed Development</i>	<i>48</i>
8.1 Recommendations and Mitigation Measures	49
<i>Made Ground and Contamination Hotspot.....</i>	<i>49</i>
<i>Construction Environmental Management Plan (Appendix 6.1 of the Environmental Statement)</i>	<i>50</i>
<i>Proposed Monitoring – Groundwater</i>	<i>50</i>
<i>Piling 52</i>	
<i>Dredging 52</i>	
<i>Horizontal Directional Drilling (HDD).....</i>	<i>52</i>
<i>Other Construction Considerations</i>	<i>53</i>
<i>Affinity Water Public Water Boreholes</i>	<i>53</i>
9 Conclusions.....	54

9.1 Conclusions	54
<i>Made Ground and Contamination Hotspot.....</i>	<i>54</i>
<i>Dredging</i>	<i>55</i>
<i>Proposed Development</i>	<i>55</i>
9.2 Recommendations.....	57

Tables

Tables

<i>Table 3-1 BGS GeoIndex Borehole Details</i>	<i>9</i>
<i>Table 3-2 Groundwater Monitoring Levels</i>	<i>12</i>
<i>Table 4-1 Summary of Encountered Ground Conditions.....</i>	<i>23</i>
<i>Table 4-2 Summary of Groundwater Screening Exceedances.....</i>	<i>25</i>
<i>Table 7-1 Mobility of Hydrocarbon Fractions in Groundwater</i>	<i>46</i>

Figures

Figures

<i>Figure 2-1 Site Location Plan</i>	<i>4</i>
<i>Figure 2-2 Indicative Planning Application Boundary.....</i>	<i>5</i>
<i>Figure 2-3 Proposed Development Masterplan – Revised Scheme.....</i>	<i>7</i>
<i>Figure 3-1 Licensed Abstractions</i>	<i>13</i>
<i>Figure 3-2 Environmental Sensitivities.....</i>	<i>18</i>
<i>Figure 4-1 Site Investigation Positions.....</i>	<i>20</i>
<i>Figure 4-2 Existing Concrete Hardstanding</i>	<i>21</i>
<i>Figure 5-1 Johns Associates Initial Lake Sediment Sample Locations.....</i>	<i>28</i>
<i>Figure 5-2 Johns Associates March 2025 Lake Sediment Sample Locations</i>	<i>30</i>
<i>Figure 5-3 Greengage Submarine Survey Locations - Anthropogenic Material.....</i>	<i>35</i>
<i>Figure 6-1 Surface Water Sample Locations</i>	<i>36</i>
<i>Figure 7-1 Proposed Development Hydrogeological Conceptual Model</i>	<i>40</i>
<i>Figure 7-2 Location of Geo-Integrity Identified Hotspot.....</i>	<i>42</i>
<i>Figure 8-1 Area of Mapped Historic Inert Landfill.....</i>	<i>45</i>
<i>Figure 8-2 Proposed HDD Cable Route</i>	<i>48</i>

Drawings

- Drawing 1 Superficial Geology Map*
- Drawing 2 Bedrock Geology Map*
- Drawing 3 Artificial Geology Map*
- Drawing 4 Regional Hydrogeological Conceptual Model*
- Drawing 5 Line of Cross-Sections*

Appendices

Appendix A Broadwater Lake Sediment Laboratory Analysis

Appendix B Broadwater Lake Sediment Screening Results

1 Introduction

1.1 Background

Hydrogeo Limited (Hydrogeo) have been commissioned by the London Borough of Hillingdon (the Applicant) to undertake a Groundwater Risk Assessment for the works associated with the Proposed Development of the Hillingdon Water Sports Facility and Activity Centre (HWSFAC).

This report has been progressed as a standalone document which will inform the Environmental Impact Assessment. The report addresses, further potential effects as a result of the proposed development and will be important within design considerations. The Groundwater Risk Assessment will accompany a number of additional standalone documents in support of the proposed planning application with London Borough of Hillingdon for the development of Hillingdon Water Sports Facility and Activity Centre.

This Groundwater Risk Assessment provides a review of the geological, hydrological and hydrogeological conditions of the site and surrounding area, and provides a Hydrogeological Conceptual Model used to assess the potential risks posed to the groundwater dependent environment as a result of works associated with the proposed development.

The Environment Agency's (EA) approach to groundwater protection guidance note F1 – Non-landfill waste activities indicates the EA's position statement in regard to sites within Source Protection Zone 1 – Inner Catchment.

The position statement from the Environment Agency is as follows, *Inside SPZ1 the Environment Agency will only object to proposals for new development of non-landfill waste operations where it believes the operation poses an intrinsic hazard to groundwater. For example, deposit of waste for recovery activities. The Environment Agency will oppose such new developments via the development planning system*".

"For any other non-landfill waste operations that are proposed in SPZ1, when considering any environmental permit application, the Environment Agency will usually require a detailed risk assessment, and mitigation measures to be put in place to manage all risks to groundwater. Accordingly, the Environment Agency will raise concerns when

responding to any planning application consultation, as to whether a permit could be granted. In sensitive groundwater locations, the Environment Agency will therefore strongly encourage parallel tracked environmental permit applications with planning applications”.

1.2 Data Sources & Third-Party Information

In completing this assessment, Hydrogeo has utilised the following information:

- British Geological Survey (BGS) data;
- BGS borehole records;
- BGS 1:50,000 Geology Map - Sheet 255, Soil and Drift – Beaconsfield, England & Wales (2005);
- BGS The physical properties of major aquifer in England and Wales. Technical Report WD/97/34 (1997);
- Aquifer Vulnerability Map 39 – DEFRA Magic Map Online Viewer.
- BGS 1:100,000 Hydrogeological Map – 14, Maidenhead (1984);
- BGS Memoir – Geology of the Beaconsfield District – 2005;
- Geo-Integrity Phase I Geo-environmental Assessment and Site Walkover – November 2022);
- Geo-Integrity Phase II Geo-environmental Site Investigation (April 2023);
- Miles Water Engineering (MWE) Sediment Testing Reports (July 2023);
- Johns Associates Broadwater Lake Sediment Analysis (April 2023 & March 2025);
- Water Sampling Survey – Broadwater Lake (March 2025);
- UK Water Projects 2015-2016 Virtual Ed. Mid River Colne & Lakes investigating the impacts of Affinity Water’s groundwater abstraction on the Mid River Colne and Lakes (Matthew Rickard).
- CL:AIRE Petroleum Hydrocarbons in Groundwater: Guidance on assessing petroleum hydrocarbons using existing hydrogeological risk assessment methodologies (2017);

2 Site Setting and Development Description

2.1 Introduction

The Hillingdon Water Sports Facility and Activity Centre is being built as a replacement for HOAC which is being lost as a result of HS2. The Site is located at Broadwater Lake, Moorhall Road, Harefield, Uxbridge UB9 6PE, as a result of HS2 Rail Works.

Broadwater Lake is a large body of water with a number of small islands bordered by trees and scrub. Broadwater Sailing Club located at the northern end and a private road provides access from Moorhall Road to the south. Two bungalows are situated south of Broadwater Lake and provide accommodation for site wardens. A Site Location Plan is provided as Figure 2-1, with the indicative planning application red line boundary included as Figure 2-2.

Figure 2-1 Site Location Plan





Figure 2-2 Indicative Planning Application Boundary



2.2 Proposed Development Description

The Development will provide a new water sports facility and activities centre that will be a new base for HWSFAC and Broadwater Sailing Club. The facilities will be fenced off from the surrounding uses around the Site. The centre is to be used year-round by the public and private members of the BSC, which is to be relocated from the northern part of the lake, and their existing clubhouse demolished.

The Development will also involve physical works to Broadwater Lake, including localised dredging to facilitate sailing uses, the creation of new habitats such as islands and an area of land reclamation. The Applicant is also committed to the long-term management of Broadwater Lake to preserve and enhance its wildlife interest.

Localised dredging of the lake will be required to increase the lake depth in order to facilitate sailing from the launch locations.

Figure 2-3 Proposed Development Masterplan – Revised Scheme



3 Environmental Setting

3.1 Geology

Geological information has been gathered from the BGS Geological Map of Beaconsfield, Sheet 255 (Solid and Drift) 1:50,000 Scale, and online BGS mapping resources. A superficial geology map of the Site has been included as Drawing 1, with the bedrock geology shown in Drawing 2.

Artificial Geology

The Site is mapped as underlain by undivided worked ground. This is as a result of the Broadwater Lake area being formed through the surface excavation for sands and gravels historically.

There are also areas across the site which are mapped as infilled ground. These areas have been proven by the Geo-Integrity Site Investigation which has identified inert anthropogenic materials present in made ground soils.

The Site investigation has confirmed that the made ground thickness reaches a maximum of 3.45m within BH4.

Superficial Geology

The Site is mapped as being underlain by Alluvium and Shepperton Gravel Member superficial deposits.

The BGS describe the Alluvium as '*Ground associated with the nearby River Colne and consists of interbedded clays, silts, sands and gravels, associated with flooding events and meandering of the river across the valley floor*'.

The BGS describe the Shepperton Gravel Member as '*generally consisting of sand and gravel, locally with lenses of silt, clay or peat*'.

It is likely that the majority of the shallow Shepperton Gravel Member has been excavated from the lake areas, with mainly the deeper gravels and the higher silt / clay content materials (Alluvium) left in-situ at the base of Broadwater Lake and immediately underlying the lake.

Bedrock Geology

The BGS Maps the site as underlain by the Seaford Chalk and Newhaven Chalk Formation (Undifferentiated).

The Seaford Chalk Formation is described by the BGS as '*Firm white chalk with conspicuous semi-continuous nodular and tabular flint seams. Hardgrounds and thin marls are known from the lowest beds. Some flint nodules are large to very large*'.

The BGS describes the Newhaven Chalk Formation as '*Soft to medium hard, smooth white chalks with numerous marl seams and flint bands*'.

BGS Borehole Logs

The BGS GeoIndex indicates several historical borehole records available within the site area and surrounding vicinity. A summary of the closest / most representative borehole logs have been included within Table 3-1.

Table 3-1 BGS GeoIndex Borehole Details

Borehole Details	Ground Conditions
Reference:TQ08NW641 Name: Affinity Water Broadwater Denham BH 5 NGR:504700, 189600 Depth (m):80m	<ul style="list-style-type: none"> • Ground level to 0.3m – Topsoil • 0.3m to 0.5m – silty CLAY • 0.5m to 1m – Blue CLAY • 1m to 1.8m – PEATY Soil • 1.8m to 3.5m – Sand and Gravel; • 3.5m to 80m – CHALK and flints. Groundwater strike at 1.8mbgl, with Rest Water Level at 1.1mbgl.
Reference:TQ08NW640 Name: Affinity Water Broadwater Denham BH 3 NGR:504100, 189300 Depth (m): 57	<ul style="list-style-type: none"> • Ground level to 1.2m – Topsoil • 1.2m to 6m – Sand and Gravel • 6m to 6.3m – GRAVEL and Chalk • 6.3m to 57m – CHALK and flints Groundwater strike at 1.2mbgl, RWL at 1.2mbgl.
Reference: TQ08NW129 Name: Northmoor Near Denham Bucks NGR:503950, 189810 Depth (m):91.44	<ul style="list-style-type: none"> • Ground level to 0.61m – Topsoil; • 0.61m to 8.53m – Sand and Gravel • 8.53m to 30.48m – CHALK and flints • 30.48m to 59.44m – Sticky CHALK and flint • 59.44m to 74.1m – Sticky CHALK • 74.1m to 76.81m – Hard CHALK • 76.81m to 91.44m – Sticky CHALK

	Rest Water Level at 1.06mbgl.
--	-------------------------------

Site Investigation Boreholes

A number of Site Investigation cable percussive boreholes have been progressed across the Development Site, these have been discussed in detail within Section 4 of this Groundwater Risk Assessment.

3.2 Hydrogeology

The Site is located within a Source Protection Zone (SPZ 1 – Inner Catchment). Source Protection Zones (SPZs) are designated areas around a water well or groundwater abstraction borehole. The inner catchment is typically the zone 50 day travel time of pollutants.

Aquifer Classification

The Aquifer classifications in the UK are as follows:

- **Principal Aquifer:** These are layers of rock or drift deposits that have high intergranular and/or fracture permeability - meaning they usually provide a high level of water storage. They may support water supply and/or river base flow on a strategic scale. In most cases, principal aquifers are aquifers previously designated as major aquifer.
- **Secondary Aquifer:** These include a wide range of rock layers or drift deposits with an equally wide range of water permeability and storage. Secondary aquifers are subdivided into two types:
 - **Secondary A:** permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers;
 - **Secondary B:** predominantly lower permeability layers which may store and yield limited amounts of groundwater due to localised features such as fissures, thin permeable horizons and weathering. These are generally the water-bearing parts of the former non-aquifers;
- **Secondary Undifferentiated:** has been assigned in cases where it has not been possible to attribute either category A or B to a rock type. In most cases, this means that the layer in question has previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type;

- It is believed that the underlying aquifers (Superficial and bedrock) are in partial continuity with each other;
- The partial continuity between groundwater and surface water levels were indicated by broadly similar measured groundwater and lake level within the UK Water Projects 2015-2016 Report;
- The groundwater flow in the superficial deposits is likely to be down the river valley and potentially flow through some of the lakes where the gravel has been excavated
- The UK Water Projects Report indicates that the lake water level rises exceeded the rises expected following rainfall events, and therefore influenced by groundwater levels.

Superficial Deposits

The Superficial deposits underlying the Development site area are designated by the Environment Agency as 'Secondary A Aquifers'. This designation covers the Alluvium and Shepperton Gravel deposits.

Bedrock Geology

The Chalk geology underlying the Site is designated by the Environment Agency (EA) as a 'Principal Aquifer'.

BGS Hydrogeology Map

The Site is mapped by the BGS within Map 14, Cambridge – Maidenhead 1:100,000 Hydrogeological Sheet Map.

The Hydrogeology map covering the Development indicates that the site is located between the +30mAOD and +40mAOD contours of the potentiometric surface of the underlying Chalk. The Site is located at an approximate topographic level of between 36mAOD and 43mAOD, indicating that the potentiometric groundwater surface of the Chalk aquifer is within a minimum of 3m below ground level.

The Site is also mapped as located between the 0mAOD and -25mAOD contours representing the base of the Upper Chalk.

The regional groundwater flow direction based upon the contours of the potentiometric surface of the underlying chalk indicate a flow direction to the southeast.

3.3 Groundwater Levels

All desk based data reviewed, including historical borehole logs and the hydrogeology map indicates the presence of shallow groundwater within 2m below ground level.

Historic borehole records indicate the presence of groundwater strikes at 1.2mbgl and 1.8mbgl respectively, with a single, minor groundwater level rise to rest from 1.8mbgl to 1.2mbgl.

The Geo-Integrity Phase I Report indicates that the Site is located in a High Risk Groundwater Flooding area. The Client Team have indicated to Hydrogeo that there are no proposed sub-surface structures within the proposed development plans. The potential impacts to groundwater needs to be carefully considered during any deeper piling activities for building foundation solutions.

Groundwater Levels – Site Investigation and Monitoring

Groundwater levels were encountered during the Geo-integrity Site Investigation works in the majority of exploratory positions, with groundwater strikes recorded during the drilling works between 1mbgl and 4.9mbgl, with rest water levels between 1.2mbgl and 4.6mbgl.

Subsequent groundwater monitoring progressed between 9th March 2023 and 29th March 2023 within the standpipes installed at BH3, BH6 and BH9 recorded groundwater levels between 0.75m and 2.39m.

Spot heights were captured by Geo-integrity using GPS to determine the groundwater level in relation to Ordnance Datum. Due to the excessive tree cover, and the resulting inaccuracies of the GPS system BH9 groundwater levels in mAOD have not been presented. Table 3-2 presents the groundwater monitoring level from BH3 and BH6.

Table 3-2 Groundwater Monitoring Levels


Borehole ID	Groundwater Levels (mAOD)		
	09/03/2023	15/03/2023	29/03/2023
BH3	38.56	38.65	38.65
BH6	38.67	38.82	38.82

From the Geo-integrity groundwater monitoring rounds, the groundwater flow direction has been determined to the south, which corresponds to the direction of the River Colne.

3.4 Licensed Abstractions

There are a number of licensed groundwater abstractions mapped on-site and within the immediate vicinity. The abstractions are shown spatially within Figure 3-1.

Figure 3-1 Licensed Abstractions



The 2no. on-site abstraction licenses pertain to the historical mineral extraction and concrete production operations across the site, with the Client Team providing Hydrogeo with the Environment Agency documentation. The available information confirms that the original license was granted in March 1966, with another license granted in May 2006.

The original 1966 abstraction license covered abstraction from 2no. points (Point A and B) for flow rates of 37.89l/s and 4.92l/s respectively. The abstraction points were located at National Grid References: TQ 0470 8910 and TQ 0470 8920 respectively. The Client Team note that they have been unable to identify any boreholes across the proposed development site area at the time of reporting.

Affinity Water is licensed to abstract 88MI/d from the underlying Chalk aquifer as part of the Blackford Group license which includes 9 abstraction boreholes in this area, however, not all are currently operational. The Blackford and Northmoor boreholes located in the immediate site vicinity abstract up to 37 MI/day.

The BGS Geoindex indicates that Affinity Water Broadwater BH3 Denham is located approximately 500m west of the proposed development site.

The closest licensed surface water abstraction to the Development is 1156m south at Buckinghamshire Golf Club for top up and make up water for irrigation.

3.5 Private Water Supplies

At the time of reporting Hydrogeo has made an enquiry with London Borough of Hillingdon (LBH) for details in regard to private water supplies within the site vicinity. The enquiry was made under the Freedom of Information Act. Hydrogeo are currently awaiting a response from the Local Authority.

The Client Team has indicated that a number of historic and active abstraction boreholes are present on site, including the current sailing club which utilise a borehole for wash water for boats and domestic purposes. The borehole at the sailing club is not used as a potable water supply.

3.6 Hydrology

The planning application is to be supported by a number of standalone reports relating to the hydrology of the area and proposed development, including:

- Water Framework Directive (WFD) Assessment; and Flood risk, Drainage and Sequential Assessment (Weetwood, September 2023)

A Flood Risk, Drainage and Sequential Assessment has been prepared by Weetwood (September 2023) under separate cover to this Groundwater Risk Assessment to act as a stand alone report to inform planning.

The majority of the Site comprises a water body (Broadwater Lake) within the River Colne floodplain that extends over circa 80ha. Formed as a result of gravel extraction, it is one of over 60 such waterbodies throughout the wider Mid-Colne Valley that together form a complex of wetland features and as such, many of these are likely to be in hydrological continuity with one another.

Broadwater Lake is bordered to the west and north by the River Colne (Main River) and the Grand Union Canal is located to the east. Other former gravel pits/sand pits are located immediately to the north and south, with a narrow terrestrial perimeter forming the lake/river shore and canal embankment. A larger area of land is located adjacent to the south east corner of the lake and is currently characterised by wet woodland, broadleaved woodland and standing water ('the peninsula').

Broadwater Lake is a surface water body (Lake) under the Water Framework Directive (WFD) reference GB30641907. It is located adjacent to the River Colne (Confluence with Chess to the River Thames) WFD reference GB106039023090 and the Grand Union Canal, a Canal under the WFD reference GB70610252. Broadwater Lake is associated with the Thames Basin River Basin District. The most recent data from the Environment Agency (EA) from 2019 shows that their overall WFD rating is Moderate, Chemical rating is Fail and Ecology rating is Moderate. The chemical failure rating is as a result of perfluorooctane Sulphonate (PFOS), and polybrominated diphenyl ethers (PBDE).

Broadwater Lake is located over, and likely is in continuity with the Mid-Chilterns Chalk Groundwater Body reference GB40601G601200. Its most recent (2019) Overall Rating is Poor, Chemical rating is Poor and Quantity rating is Poor.

Data provided by Groundsure and from the EA (flood map for planning) identify that Broadwater Lake and land within 50m is at High risk of fluvial flooding (with the exception

of the raised peninsula in the south-east corner of the lake). Most of the lake within Site is in Flood Zone 3. The peninsula is typically in Flood Zone 1 and the access to Moorhall Road is in Flood Zone 2.

Recent water quality sampling (for microbial and certain water quality parameters relating to use for water sport activity) taken from the south east lake margins by GEA Ltd in 2022 show that the results were generally found to meet the EC Bathing Water Directive (76/160/EEC and 2006/7/EC), with the exception of the concentration of Enterococci within the sample collected from Location No 1, which was classified as 'Poor (fail)'. None of the samples were found to contain salmonella, and all six samples were found to meet the requirements of the EC Bathing Water Directive (76/160/EEC and 2006/7/EC), with the exception of the concentration of Enterococci within the sample collected from Location No 1, which was classified as 'Poor (fail)'. All six samples were found to meet the World Health Organisation (WHO) guidance values with respect to blue-green algae (cyanobacteria). The concentration of *Clostridium perfringens* recorded in one sample is considered to be elevated with respect to the adopted threshold for faecal coliforms, of 200 colony-forming units per 100ml.

The Environment Agency and the Department for Environment and Rural Affairs (DEFRA) Online Water Quality Archive indicates a sampling location within Broadwater Lake, at National Grid Reference (NGR): 504591, 189093. 6No. Samples have been collected 30th October 2019 – 26th April 2022, with 8No. Chemical determinants measured (colour, conductivity, alkalinity, phosphorus, chlorophyll, nitrogen, orthophosphate and nitrogen total oxidised).

3.7 Environmental Designations

Figure 3-2 shows the locations of the environmental sensitivities in relation to the Site.

The Site is set within the landscape context of the Colne Valley Regional Park, which is a mosaic of farmland, woodland and water with 200 km of rivers, canals and over 60 lakes.

The entire Site forms a component part of the Mid Colne Valley SSSI, designated for breeding and over-wintering water birds. A number of nationally and regionally important statutory designated wildlife sites are present within 2km, as detailed in Chapter 5. The site is also designated as a Site of Importance for Nature Conservation (SINC) of Metropolitan importance.

Part of the Site is within the Broadwater Lake Nature Reserve managed by Hertsmere and Middlesex Wildlife Trust, and Northmoor Hill Wood Local Nature Reserve is located approximately 300m west of the Site boundary.


Priority habitat is present onsite and in the adjacent surrounds, comprising deciduous woodland. Parts of the woodland adjacent to the west of the Site are designated as Ancient Woodland.

The Site is adjacent to the Widewater Lock Conservation Area (CA) in the south-east and Black Jacks and Copper Mill Lock (CA) in the north-east. The Site is also 250m from the Harefield Village CA in the east. Broadwater Park Registered Park and Garden is located approximately 400m southwest of the Site boundary.

The Site is located adjacent to an Archaeological Priority Area (APA) in the east designated within the LBH Local Plan.

Broadwater Lake is designated by the Environment Agency (EA) as a Groundwater Dependent Terrestrial Ecosystem.

Figure 3-2 Environmental Sensitivities



4 Site Investigation – Land Based

4.1 Introduction

A Site investigation has been carried out by Geo-integrity following the progression of an earlier Phase I Geo-environmental Study and Site Walkover which indicated the requirement for additional site works.


4.2 Site Investigation

The Geo-integrity Site Investigation was progressed over the course of 10-days 15th – 28th February 2023.

The site works consisted of the advancement of:

- 9no. cable percussive boreholes BH1 – BH9 (maximum 15mbgl);
- 3no. machine excavated infiltration pits (SA1 – SA3);
- 14no. machine excavated trial pits (TP1 – TP14).

Selected cable percussive boreholes (BH3, BH6 and BH9) were installed as groundwater / ground gas monitoring positions for subsequent groundwater and ground gas monitoring rounds. The positions of all intrusive investigations are presented within Figure 4-1, which shows the positions of the intrusive investigations overlain onto the Proposed Development Plan.

Figure 4-1 Site Investigation Positions


4.3 Encountered Ground Conditions

The ground conditions encountered across the site have been summarised based upon the findings within the Geo-integrity Site Investigation Report.

Concrete Hardstanding

Concrete hardstanding was encountered across the majority of the eastern portion of Site Peninsula, the extent of which has been indicated in Figure 4-2 produced as part of the works to support the planning application.

Figure 4-2 Existing Concrete Hardstanding



Made Ground / Reworked Ground

Made Ground was encountered across the extensive areas of the Site Peninsula from ground level and underlying the concrete hardstanding to locally maximum depths of 3.45mbgl along the eastern portion of the site. Generally, the made ground thickness was encountered to depths between 1mbgl – 2mbgl.

The Made Ground was generally encountered as loose, orange / brown silty, sandy gravel, with inclusions of cobble and boulder size fragments of concrete, ash, slag, slate, rubber and glass.

Reworked soils were located along the northern boundary thickening westward. The ground conditions consisted of natural gravels to depths ranging between 2.45mbgl and 3.25mbgl which have been interpreted by Geo-integrity as reflecting the historic infilling process from 2001.

Alluvium

A consistent layer of alluvium deposits was present across the entire site area, at depths ranging 1.3mbgl to 4.50mbgl. The alluvium deposits were encountered as very soft, dark brown, grey, black highly organic, silty, slightly gravelly clay with peat and plant debris. Gravels were encountered as fine to coarse of flint.

Shepperton Gravel Member

Encountered within the deeper site investigation positions (BH1 – BH9) and (TP11- TP14) from depths ranging 0.5mbgl – 4.5mbgl to 6.1mbgl and 8mbgl.

Hydrogeo believe that this shallower identified gravel horizon is likely reworked gravels, as all other gravels encountered are recorded at greater depths below ground level.

The material encountered consisted of a medium dense to dense, dark grey, orange, brown, sandy gravel, gravels being fine to coarse, sub-angular to sub-rounded flint and quartz.

Chalk

Encountered only within the cable percussive boreholes (BH1 – BH9) at depths of 4.5mbgl to in excess of 19.55mbgl, encountered as structureless off-white chalk comprising both gravelly silt and silty gravel.

Table 4-1 summarises the ground conditions encountered underlying the Site.

Table 4-1 Summary of Encountered Ground Conditions

Depth (mbgl)	Strata
Ground level (0mbgl)	Concrete Hardstanding
Ground Level to maximum 3.45mbgl	Made Ground – silty, sandy gravel with inclusions of cobbles and boulders of concrete, ash, slag and slate.
1.3mbgl – 4.50mbgl	Alluvium – very soft, dark brown, grey, black, highly organic, silty, slightly gravelly clay with peat and plant debris.
0.5mbgl – 4.5mbgl & 6.1mbgl – 8.1mbgl	Shepperton Gravel Member – medium dense to dense, dark grey, orange / brown sandy gravel. Gravels being fine to coarse, sub-angular to sub-rounded of flint and quartz.
4.5mbgl – 19.55mbgl (Maximum depth advanced)	Chalk – Off-white structureless chalk, comprising both gravelly silt and silty gravel.

4.4 Encountered Contamination and Chemical Testing

Geo-integrity noted some evidence of contamination which were identified locally within the made ground soils during the site investigation. Hydrocarbon staining and odour was noted within 2no. Trial Pits, TP4 and CBR5 positioned adjacent to an historic concrete bund situated at the north of the site.

In addition, some anthropogenic materials were encountered within the Made Ground such as brick, concrete, ash slag and slate.

Laboratory Chemical Testing

Geo-integrity scheduled 13no. soil samples for chemical analysis at an MCERTS and UKAS accredited laboratory facility for a varied suite of chemical testing including:

- Metals and inorganic substances;
- Speciated PAHs;
- Benzene, toluene, ethylbenzene and xylene (BTEX);
- TPHs;
- Made ground tested for WAC Suite and asbestos.
- Volatile and Semi-volatile organic compounds (SVOC's and VOCs).

3no. groundwater samples were also captured and scheduled for testing for a suite in accordance with environmental quality standards (EQS), including:

- Heavy metals;
- TPHs;
- PAHs;
- Dissolved Organic Carbon (DOC);
- pH
- Essential minerals – calcium, potassium, magnesium, sodium.

Soil Screening Results

No asbestos was indicated within any of the 12no. made ground samples.

Geo-Integrity have screened laboratory soil results against 'commercial end-use criteria targets' for aromatic and aliphatic compounds, as well as TPH compounds did not determine any exceedances of the General Assessment Criteria (GAC).

Leachate and Groundwater Sample Screening Results

Leachate tests were progressed on 2no. made ground samples captured from TP1 and TP2 and 0.5mbgl. The screening of the leachate results indicated marginally elevated levels of chromium, copper, nickel, lead and zinc when compared to the EQS values for freshwater, however when compared to UK Drinking Water Standards (UKDWS) none were significantly elevated.

Groundwater samples taken from BH3, BH6 and BH9 were tested and indicated marginally elevated concentrations of heavy metals including copper, manganese and nickel as indicated in Table 4-2.

All other chemical determinants were present at concentrations below either the Laboratory Level of Detection (LoD) or the respective Screening Criteria (Environmental Quality Standard)

Table 4-2 Summary of Groundwater Screening Exceedances

Heavy Metal	Recorded Value Range (µg/l)	Number of Exceedances	EQS Freshwater (µg/l)	UK DWS (µg/l)
Copper	<0.5 – 1.80	1	1(bioavailable)	2000
Manganese	150 - 760	3	123(bioavailable)	50
Nickel	3.2 – 4.8	2	4(bioavailable)	20

5 Site Investigation – Broadwater Lake

5.1 Introduction

A number of previous intrusive site investigations have been progressed across Broadwater Lake, sampling lake bed sediment to determine ground conditions beneath water level, as well as to determine the chemical condition of the materials across the lake bed.

Investigations include the following reports, and have been summarised below:

- Johns Associates Broadwater Lake Sediment Sampling (April 2023);
- Miles Water Engineering Ground Investigation (July 2023);
- Johns Associates Broadwater Lake Sediment Sampling (March 2025);

5.2 Johns Associates Broadwater Lake Sediment Sampling – April 2023

Lake sediment samples have been captured across Broadwater Lake and issued to an accredited laboratory facility for testing against a suite of chemical determinants. Locations of the captured sediment samples are presented in Figures 5-1 and 5-2 of this report.

The samples were captured across Broadwater Lake by Johns Associates, and were captured to support this Groundwater Risk Assessment, as well as to inform other parts of the planning application process including dredging, ground contamination and water quality.

The proposed dredging works include the dredging of lake bed materials to make deeper lake areas within the sailing corridor. The dredged lake bed materials are then proposed to be retained on-site in the formation of new lake islands, shallow lake areas and land reclamation for the Site Peninsula.

From review of the Ordnance Survey Map of the lake area, no obvious inflows or outflows of water occur.

In total Johns Associates captured 20no. samples from across Broadwater Lake, with all samples tested for a range of chemical determinants including:

- Soil pH;
- Available phosphorus;

- Available potassium;
- Available magnesium;
- Potentially Toxic Elements – including copper, zinc, nickel, zinc, cadmium. Lead, chromium, mercury, molybdenum, selenium, arsenic, fluoride
- Conductivity;
- Organic matter loss on ignition;
- Total phosphorus;
- Total potassium;
- Total magnesium;
- Total calcium;
- Total sodium;
- Total carbon;
- Total sulphur.

Positions of the initial 20 no. lake bed sediment samples are presented below in Figure 5-1.

Figure 5-1 Johns Associates Initial Lake Sediment Sample Locations



Lake Sediment Screening

The 20no. lake sediment samples have been screened against General Assessment Criteria (GAC) consisting of the following.

- Category 4 Screening Levels (C4SLs) – Human health screening criteria produced using the CLEA model, used to assess the risk posed to human health by the deposited sediment. ‘Residential – Without produce’ concentrations have been used.

- Environment Agency Ecological Soils Screening Values (SSVs) – Produced by the EA in 2017, the SSVs are used for screening waste and waste derived materials to be used as soil improvers on agricultural land. The values assess the hazard posed by 19 substances to soil fauna, flora and ecosystems. These values assess the suitability of the materials for agricultural spreading, taking into account background concentrations which have been sourced from the NSIV survey.
- Sewage Sludge on Farmland – Potentially Toxic Elements (PTEs) – the sediment has also been screened using the same values which are applied to sewage sludge spreading on agricultural land.
- NSIV Survey Normal Background Concentrations – These values represent the normal background concentration of substances in the local area. Background concentrations are primarily the result of the material's parent geology.

5.3 Johns Associates Broadwater Lake Sediment Sampling March 2025

Following amendments to the proposed development as a result of consultation and liaison with the statutory consultees, Johns Associates re-attended Site in order to collect additional lake sediment samples.

Samples were collected at 20 no. locations across Broadwater Lake, with the samples issued to an accredited laboratory facility for testing against a suite of chemical determinants. Locations of the sediment samples are presented in Figure 5-1 and Figure 5-2 of this report.

Figure 5-2 Johns Associates March 2025 Lake Sediment Sample Locations

The suite of chemical determinants included:

- Asbestos Screen;
- Toxic metals, including Chromium, Copper, Zinc, Lead, Iron, Cadmium, Mercury, Manganese, Nickel, Selenium;
- pH;
- Organic Matter;
- Fluoride;
- Polyaromatic Hydrocarbons (PAHs);
- Total Petroleum Hydrocarbons (TPHs);
- Available phosphorus;
- Available potassium;
- Available magnesium;
- Conductivity;
- Organic matter loss on ignition;
- Total phosphorus;

- Total potassium;
- Total magnesium;
- Total calcium;
- Total sodium;
- Total carbon;
- Total sulphur.

Lake Sediment Screening

The 20 no. lake sediment samples have been screened against Generic Assessment Criteria(GAC) consisting of the following:

- Category 4 Screening Levels (C4SLs) – Human health screening criteria produced using the CLEA model, used to assess the risk posed to human health by the deposited sediment. ‘Residential – Without produce’ concentrations have been used.
- Environment Agency Ecological Soils Screening Values (SSVs) – Produced by the EA in 2017, the SSVs are used for screening waste and waste derived materials to be used as soil improvers on agricultural land. The values assess the hazard posed by 19 substances to soil fauna, flora and ecosystems. These values assess the suitability of the materials for agricultural spreading, taking into account background concentrations which have been sourced from the NSIV survey.
- Sewage Sludge on Farmland – Potentially Toxic Elements (PTEs) – the sediment has also been screened using the same values which are applied to sewage sludge spreading on agricultural land.
- NSIV Survey Normal Background Concentrations – These values represent the normal background concentration of substances in the local area. Background concentrations are primarily the result of the material's parent geology.

Chemical Testing Results

Laboratory certificates are attached as Appendix A, with the soil screening spreadsheet attached as Appendix B.

Potentially Toxic Elements (PTE)

Potentially toxic elements tested for within the lake sediment samples include copper, zinc, nickel, zinc, cadmium, lead, chromium, mercury, molybdenum, selenium, arsenic, fluoride, TPHs and PAHs.

Screening of the laboratory chemical data concentrations against the Generic Assessment Criteria (GAC) has not indicated any exceeding concentrations within the lake bed sediment.

Chemical Testing Results

Laboratory certificates are attached as Appendix A, with the soil screening spreadsheet attached as Appendix B.

Potentially Toxic Elements (PTE)

Potentially toxic elements tested for within the lake sediment samples include copper, zinc, nickel, zinc, cadmium. Lead, chromium, mercury, molybdenum, selenium, arsenic and fluoride.

Screening of the laboratory chemical concentrations against the C4SL screening criteria did not identify any exceeding concentrations of potentially toxic elements across all 20no. lake sediment samples.

Screening of the potentially toxic element concentrations against the Environment Agency (EA) Ecological Soils Screening Values (SSVs) has indicated a number of exceeding concentrations for cadmium, nickel and zinc.

All other chemical determinants screened against the Environment Agency SSVs remain below the SSV concentration criteria.

The soil chemical laboratory results included as Appendix A present the findings of the screening against the maximum permissible concentrations of the PTEs in arable/grassland soil. These screening values are derived from DEFRA's Code of Practice for Agricultural Use of Sewage Sludge.

The development proposal is to retain and reuse the dredged lake sediment within the boundaries of the lake, initially below water levels, and then eventually to build up Small Island features, and reclaim land on the Site Peninsula.

5.4 Miles Water Engineering Broadwater Lake Ground Investigation July 2023

Miles Water Engineering (MWE) undertook ground investigation on the 28th June 2023 at several locations around the lake to gather lake sediment samples. Samples were collected from shallow areas of the lake.

In total 6 no. investigation positions were completed. At each location, one investigation was undertaken with a handheld auger, and another with a core sampler. In total 12 no. lake sediment samples were collected.

Lake samples were allowed to dry naturally to remove excess moisture for at least one week. After this period the samples were reviewed to confirm results.

The lake bed sediment samples collected all remained consistent with each other, and showed there to be a thin layer of stone and boulders at the surface of the lake bed of around 0.1m in thickness. Underlying this is a band of silty clay 0.2m thick. At the base of the investigation positions was very stiff clay.

As part of the dredging tender process, an MWE subcontractor – Smals Dredging also progressed a site investigation of the Broadwater Lake. and The investigation identified similar conditions to those from the MWE investigation, with stones and boulders underlain by silty clay, becoming stiff clay.

5.5 Greengage Broadwater Lake Submarine Survey September & October 2024, and March 2025


Greengage progressed a submarine survey of Broadwater Lake, providing detailed photographic records of the sediment and ecology present across the lake bed.

The submarine survey was progressed across several dates in September & October 2024, and March 2025, with a total of 113 no. positions being surveyed. The survey has provided camera footage of the lake bed sediment, as well as a number of comments and general observations.

Following review, 12 no. individual survey positions (4, 6, 10, 14, 21, 37, 38, 40, 42, 82, 161c75d2 & 949a5999)) have identified the presence of anthropogenic materials at the bed of Broadwater Lake. The anthropogenic materials identified include metal structures, metal shuttering, metal grate, bricks, and small to large concrete blocks.

Figure 9.3 provides the lake bed survey positions where anthropogenic materials have been identified by the Greengage Survey.

Figure 5-3 Greengage Submarine Survey Locations - Anthropogenic Material



6 Broadwater Lake Surface Water Samples

6.1 Introduction

Hillingdon Council has collected water quality data from 7 no. sample locations around Broadwater Lake across the period 12th November 2024 – 10th June 2025, on a monthly basis. The main purpose for the surface water quality testing was to assess the suitability of the surface water within Broadwater Lake for swimming and boating for children. This surface water sampling is proposed to continue on a monthly basis.

Samples have been collected from seven different positions as shown in Figure 6-1 and include areas across the Site referred to as the slipway, Bench, Beach Tree, Anglers Bridge, Otter, Lagoon and Beach.

Figure 6-1 Surface Water Sample Locations



6.2 Laboratory Analysis and Chemical Screening

Samples were collected in laboratory supplied containers and dispatched to a UKAS and MCERTS accredited laboratory facility for testing. As part of the assessment, several chemical and biological determinants have been tested for. The microbiology suite includes:

- Total Coliforms;
- Eschericia Coli;
- Salmonella Spp;
- Intestinal enterococci;
- Clostridium perfringens;

Chemical analysis of the surface water as part of the assessment included;

- Ammoniacal Nitrogen as NH_4 ;
- Nitrate as N;
- Phosphate, Total inorganic as P;
- Phosphate, Orthophosphate as P.

Surface Water Sample Screening

The surface water samples collected have been screened against Freshwater Environmental Quality Standards (EQS) for ammoniacal nitrogen, nitrate, and phosphate.

Ammoniacal Nitrogen

In total 48 no. samples were collected and analysed for Ammoniacal Nitrogen concentrations. Screening of the laboratory concentrations against the Freshwater EQS of 0.5mg/l has not identified any exceedances.

Nitrate as N

A total of 48 no. samples were collected and analysed for nitrate as N concentrations. Screening of the laboratory data has not indicated any exceedances of the nitrate as N Freshwater EQS of 50mg/l.

Phosphate, Total inorganic as P / Orthophosphate as P

The sampling totalled 48 no. samples tested for phosphate (Total and Ortho). Screening of the laboratory data against the updated recommendations of phosphorus standards for rivers (August 2013) has indicated that all sample concentrations are in exceedance of the 0.035mg/l concentration set out for 'Good' water quality status.

7 Conceptual Hydrogeological Model


A regional Conceptual Hydrogeological Model is included as Drawing 3 of this report, with Figure 7-1 presenting a Conceptual Hydrogeological Model of the proposed development site, including the identified sources, pathways and receptors. Figure 7-1 presents a conceptual hydrogeological model of the proposed development.

7.1 Conceptual Hydrogeological Model

- The site is underlain by a thickness of concrete hardstanding, beneath which are made ground and reworked ground conditions. The concrete hardstanding is presently acting as a capping layer above the inert landfill made ground, and therefore limiting infiltration of rainwater and surface water.
- The underlying Chalk is designated as a Principal Aquifer, and is extensively used for groundwater abstraction, including a significant quantity of public supply. The Chalk aquifer is a dual permeability aquifer which is characterised by very low flow rates through the rock matrix and much higher rates of flow through fissures.
- The Chalk is likely to be heterogeneous with the principal mechanism of groundwater flow to occur through a network of interconnected fractures and solution enlarged voids.
- Geophysical data available from different boreholes within the chalk of the Colne Valley indicates the presence of 3no. distinct fissure horizons at 14m-16mbgl, 26mbgl – 32mbgl and 48mbgl – 52mbgl.
- The majority of groundwater movement within the chalk is likely to be within the top 50m of the saturated zone, and layering is likely, with some horizons more permeable than others.
- BGS data indicates that transmissivity values within major valleys (Thames and Colne) in the Chalk in the Chilterns is high, typically in the range of 1500m²/d to 3000m²/day.
- Leakage from the overlying sands and gravels into the chalk aquifer may be part of the reason for high transmissivity values.
- Groundwater levels within the chalk bedrock may be influenced by the proximity to the Affinity Water abstraction boreholes, and the associated pumping rate of these. This may increase the downward leakage of water into the underlying aquifers.
- The groundwater is thought to only be in partial hydraulic continuity with surface water features due to the superficial gravels becoming very silty towards the base, and the upper surface of the Chalk can often be weathered to a clay like 'putty

chalk'. This *putty chalk*' is noted as locally reducing permeability, especially where the base of the sands and gravels is indicated to have increased silt content.

Figure 7-1 Proposed Development Hydrogeological Conceptual Model




7.2 Sources

Following progression of land based Site Investigation and Broadwater Lake Site Investigation, a number of potential sources of contamination that may pose a risk to groundwater have been identified.

- Made ground has been encountered across the majority of the Geo-Integrity Site investigation positions to a maximum depth of 3.45mbgl. The made ground materials appear to consist of inert waste, consisting of brick, ash, coal, concrete debris etc, and is likely associated with the historic landfill on-site identified within the Geo-Integrity Phase I Report. The identified inert landfill reference: TE1/L/LAF001 was operated by Lafarge Aggregates Limited from 1993, with the license surrendered in June 2004.
- It is noted within the Phase II Geo-Integrity Investigation that inert landfill waste materials appear beyond the mapped boundaries of the historic licensed inert landfill.
- An identified 'hotspot' of malodours and visually impacted hydrocarbon stained made ground around the area of TP4 and CBR5, as well as the presence of marginally elevated heavy metal leachability concentrations has been identified within the Geo-Integrity site investigation. The position of the identified contamination hotspot is shown in Figure 7-2 below.
- Groundwater samples during the Geo-Integrity land based site investigation has identified marginally elevated existing concentrations of nickel, copper and manganese when screened against the UK Drinking Water Standards and their associated Environmental Quality Standards (EQS) as in Table 4-2.
- Laboratory analysis of Broadwater Lake sediment samples has identified measurable concentrations of heavy metals, however when these were screened against residential end use targets, no exceeding concentrations were found. Screening of the sediment samples against Environment Agency (EA) Ecological Soil Screening Values (SSVs) has identified several marginal exceedances for zinc, nickel and cadmium.

Figure 7-2 Location of Geo-Integrity Identified Hotspot



7.3 Pathways

Pathways for the migration of potential contamination have been identified based upon proposed site development plans, construction plans and existing site condition reports including the Geo-Integrity Phase I and Phase II reports.

- It is believed that some of the proposed development structures will require piled foundation solutions, which may present a short-circuit pathway for the migration of near-surface contaminants present within the made ground to greater depths into the underlying groundwater, superficial and chalk aquifers.
- The piling process will likely result in the interconnectivity of the overlying superficial aquifer (sands and gravels) with the underlying chalk aquifer. It is believed that the surface water environment and shallow groundwater environment is already in partial continuity with the groundwater within the chalk bedrock.
- Formation of service ducts will generate made ground, potential for the retention and reuse of this material will need to be considered within appropriate areas within the development. The service ducts and channels may encounter shallow groundwater conditions. Site investigation has encountered groundwater at shallow depths (0.75mbgl at BH9). The channels may provide preferential short circuit pathways for potential contaminants into the underlying groundwater environment.
- The proposed dredging scheme may also result in additional interconnection between the Broadwater Lake and the underlying groundwater if any deeper dredging works are proposed in exceedance of the initial 2m.
- The Outline Construction Method Plan proposes the use of sheet piling into the underlying chalk to allow for the reclamation of some of the Broadwater Lake area as land. Broadwater Lake is underlain by naturally occurring materials. During construction of the reclaimed land it is proposed to use only the dredged lake sediments.
- The proposed horizontal Directional Drilling (HDD) to allow for the connection of services (foul and surface water drainage, HV electrical cable, mains water and fire hydrant, and telecoms & data services) at the Site poses a potential preferential pathway for the short circuit migration of contaminants on and off-site.

7.4 Receptors

The identified receptors of potential contamination have been identified from all reports and available data to Hydrogeo.

The identified receptors are as follows:

- Secondary A Superficial Aquifer;
- Broadwater Lake surface water;
- River Colne;
- Principal bedrock Chalk Aquifer;
- Affinity Water Public Borehole Supply (Source Protection Zone 1 – Inner catchment);

8 Risk Assessment

Made Ground and Contamination Hotspot

Made Ground conditions have been identified across the majority of the proposed development site, with the made ground encountered consisting of mostly inert landfill material including brick, concrete, flints, ash and rubber. The Geo-Integrity Phase I Report has indicated an area of inert landfilled ground, as shown by 1 in Figure 7-1.

Details provided in the Geo-Integrity Phase I Report indicated the landfill as an historic inert landfill, operated by Lafarge Aggregates Ltd from 1993 to 2004, under Waste Permit Reference: TE1/L/LAF001.

Figure 8-1 Area of Mapped Historic Inert Landfill



The identified contamination 'hotspot' encountered within the Geo-Integrity Phase II Site Investigation works in the area of TP4 and CBR5 consisted of malodours and visually impacted made ground conditions with hydrocarbon staining to a maximum depth of 2mbgl. The hotspot position is presented in Figure 6.2 which is included within the Geo-Integrity Site investigation Report.

Laboratory analysis of 2no. soil samples from TP4 (0.75mbgl & 2mbgl) indicates elevated concentrations of Aliphatic hydrocarbon compounds within the C12 – C16, C16 – C21 and C21-C35.

The extent of the contamination hotspot area is shown within the Impacted Made Ground Plan of the Geo-Integrity Phase II Site Investigation Report.

It appears that the contamination hotspot is located beneath the proposed access road area, and extends onto the proposed boat yard areas.

The identified hydrocarbons are included in Table 5.1 of the CL:AIRE Petroleum Hydrocarbons in Groundwater (2017) document which shows the determinants partition coefficient, solubility and mobility. Relevant sections of Table 5.1 of the CL:AIRE document has been reproduced as Table 8-1. Hydrocarbons present are described generally as having low mobility in groundwater.

Table 8-1 Mobility of Hydrocarbon Fractions in Groundwater

Carbon band range	Partition coefficient, K_{oc}		Aqueous Solubility		Overall relative mobility in groundwater
	Value (l/kg)	Potential sorption ranking	Value (l/kg)	Potential mobility ranking	
Aliphatic >C12 – C16	5x10 ⁶	Very Low	7.6x10 ⁻⁴	Very Low	Very Low
Aliphatic >C16 – C21	6.3x10 ⁸	Very Low	3x10 ⁻⁶	Very Low	Very Low
Aliphatic >C21 – C36	Not Included				

As indicated in Table 8-1 the identified hydrocarbon chains have very low mobility rankings within groundwater, and are therefore not considered to pose a significant risk to the underlying groundwater.

Groundwater samples captured during the Geo-Integrity Site Investigation did not indicate the presence of measureable concentrations of TPH compounds, with all associated TPH bands beneath the Laboratory Level of Detection (LoD).

Piling

It is believed that some of the proposed building structures will require a piled foundation solution, with piles bearing into the underlying chalk bedrock. This will result in piles being bored through shallow made ground soils, into the underlying superficial deposits and forming within the chalk bedrock.

The piling process may pose a potential risk of creating short-circuit pathways for near-surface made ground contaminants into the underlying aquifers.

The sheet pile is proposed to terminate within the underlying chalk geology.

To reclaim the land for peninsula construction it is proposed that dredged material from Broadwater lake are used, some areas of the lake bed sediment have already been sampled for laboratory analysis. However, it is recognised that additional samples within the proposed dredging area will need to be collected and analysed prior to the progression of the works.

Dredging

Dredging of Broadwater Lake is proposed to allow for the formation of deeper sailing channels and the creation of new island shallows. The dredging works is proposed to be progressed under an Environment Agency (EA) Environmental Permit, and where possible a waste exemption (using one mechanical movement).

In total 40no. samples of Broadwater Lake sediment have been collected by Johns Associates. Screening of the laboratory chemical results has indicated no exceedances of human health criteria – residential land use targets (used as these are more stringent than Public Open Space Criteria).


The majority of Broadwater Lake bed sediments have been proven as naturally occurring, gravels, sands and silts. During the Greengage Submarine Survey of Broadwater Lake, only 12 no. of 113 no. survey positions identified the presence of anthropogenic materials across the lake bed. Anthropogenic materials identified included, concrete blocks, metal and brick.

Horizontal Direction Drilling (HDD)

Horizontal Directional Drilling (HDD) is required for the service connection of the proposed development. The HDD is required to run from the electricity sub-station, approximately 250m east of the Site, beneath undeveloped land, beneath the Grand Union Canal (GUC) and eventually terminate at the Broadwater Lake Peninsula. Figure 8-2 below provides

the initial proposed HDD cable route. The HDD will allow for connection of High Voltage Electricity, telecoms and data, surface water and foul, and mains water.

Figure 8-2 Proposed HDD Cable Route



The proposed HDD methodology poses a number of potential risks and impacts to the proposed development and surrounding area, including general drilling risks, hydro-fracture, loss to ground, and disturbance of potentially contaminated soils. Additional impacts and hazards for HDD include the Source Protection Zone 1 – Inner Protection Zone, the presence of a Principal Chalk Aquifer underlying the proposed drilling route, and associated unconsolidated and / or weak geology.

It is known that additional mitigation measures will be a requirement to facilitate the feasibility of Horizontal Direction Drilling (HDD). These measures are discussed in detail in following report sections.

Proposed Development

The proposed development consists of considerable coverage of low permeability surfaces including tarmac and concrete for road surfacing and car parking / boat storage. This will restrict the volume of surface and rainfall infiltration into the made ground.

The proposed development consists of a maintenance / servicing building for boats which is likely to include the storage of potentially contaminative materials, fuels, oils chemicals and grease which have the potential to migrate into the made ground and underlying geology following leaks / spills.

Construction phase works including plant machinery refuelling and on-site storage of fuels / oils, break out and grubbing up of existing concrete surfacing may also present potential risks to the groundwater environment.

8.1 Recommendations and Mitigation Measures

Made Ground and Contamination Hotspot

The identified made ground soils have been encountered as containing inert materials including concrete, brick, flints etc, to a maximum depth of 3.45mbgl. Leachate testing of 2no. made ground samples has identified marginal exceedances of chromium, copper, nickel, lead and zinc.

The historic licensed inert landfill area as indicated in Figure 8-1 is shown to extend partially onto the proposed development site (Site Peninsula). Site Investigation positions in this area have indicated a thickness of concrete hardstanding which is effectively capping and restricting the infiltration of rainwater and surface water into the underlying inert waste. This therefore restricts leachate generation and potential for vertical and lateral migration.

This concrete hardstanding will be left intact during development.

The identified hydrocarbons within the Geo-Integrity Site Investigation includes C10-C12 and C12 – C16 chains. Guidance within the CL:AIRE petroleum hydrocarbons in groundwater indicates that these hydrocarbon chain lengths have a very low partition coefficient and a very low mobility in groundwater.

Low mobility in groundwater is also evidenced by the groundwater samples captured by Geo-Integrity which indicates concentrations of all TPH compounds at concentrations below the Laboratory Level of Detection (LoD).

Due to the locality of the contamination hotspot, underlying a proposed road area, the infiltration of rainfall and surface water to this position will be restricted, therefore limiting the potential for leachate generation and migration.

The Geo-Integrity Site Investigation positions in the vicinity of the made ground and contamination hotspot all encounter a significant thickness of low permeability silty clay which isolates the overlying made ground from the underlying superficial sands and gravels and chalk geology, restricting the vertical migration of potential contaminants.

Construction Environmental Management Plan (Appendix 6.1 of the Environmental Statement)

An outline CEMP has been produced by the Applicant Team and is reported as Appendix 6.1 of the Environmental Statement.

The CEMP sets out integrated / embedded mitigation measures that are to be implemented during the enabling and construction works phases. The mitigation measures identified to manage and mitigate the risks posed to the groundwater environment include, but are not limited to the following measures:

- Use of bunded refuelling facilities, with secondary containment measures;
- No excavation of any areas associated with former regulated or potential unregulated waste activities. No removal of any concrete cover over these locations. Provision of a suitably designed/specified impermeable barrier over these areas (e.g., clay) and appropriate overlying clean cover to prevent new pathways to terrestrial areas including connected groundwater.
- No reduction in groundwater quantity available for abstraction due to continuity between Broadwater Lake and aquifer, but a localised improvement in surface water quality. Implementation in accordance with all legal and permitting requirements.

Proposed Monitoring – Groundwater

A suitable groundwater monitoring programme covering the enabling, construction and operational phases of the Proposed Development will be developed and implemented as a planning condition. The monitoring will involve, but are not restricted to the following:

- **Pre-construction Re-assessment:** Before the construction begins, a comprehensive re-assessment of the site's hydrogeological conditions should be conducted. This assessment should include a review of available geological and hydrogeological data, site-specific groundwater flow characteristics, and the identification of nearby water sources such as wells or surface water bodies (Addressed within the Groundwater Risk Assessment).

- **Baseline Monitoring:** Baseline monitoring involves collecting data on groundwater levels, water quality, and flow rates in the vicinity of the construction site before any work begins. This provides a reference point for comparison during and after construction.
- **Installation of Monitoring Wells:** Depending on the site conditions, it may be necessary to install monitoring wells strategically around the construction area. These wells should be properly designed, constructed, and equipped with appropriate instruments to measure groundwater levels and quality accurately.
- **Continuous Monitoring:** During construction, continuous monitoring of groundwater conditions is essential. This typically involves installing automatic monitoring equipment that provides real-time data on groundwater levels, flow rates, and water quality. Automated alarms can be set up to alert project personnel if any predetermined thresholds are exceeded.
- **Regular Sampling and Analysis:** Periodic sampling of groundwater should be conducted at designated intervals to assess changes in water quality throughout the construction process. The samples will be analysed in a laboratory to detect any potential contamination or changes in groundwater chemistry.
- **Construction Activity Tracking:** It is important to document construction activities that may have a potential impact on groundwater, such as excavation, dewatering, or underground utility installation. Keeping a detailed record of these activities will help correlate any changes in groundwater conditions with specific construction actions.
- **Response and Mitigation Measures:** If the monitoring program detects any adverse impacts on groundwater, appropriate response and mitigation measures will be implemented promptly. These will include adjusting construction techniques, altering dewatering methods, or implementing additional pollution control measures.
- **Post-construction Monitoring:** Once construction is completed, post-construction monitoring will be conducted to evaluate the effectiveness of any mitigation measures and ensure that groundwater conditions return to pre-construction levels.
- **Documentation and Reporting:** A comprehensive record of the monitoring program, including data collected, analysis reports, and any mitigation measures taken, will be maintained. This documentation is critical for regulatory compliance, future reference, and potential legal requirements.

Piling

The Applicant will commission of a site-specific Piling Risk Assessment. The Environment Agency have published technical guidance regarding the assessment of risks associated with, and preventing pollution from piling and penetrative ground improvement methods. The guidance outlines a process to allow designers to select an appropriate piling method and any mitigation and monitoring measures required.

The project team will engage with a piling contractor at an early stage of the construction phase works so that all potential piling specific risks can be addressed, and where required mitigated without significantly affecting the project timescale.

Dredging

Dredging of lake sediment materials will take place within a turbidity curtain to initially contain the spread of suspended particles (turbidity).

The placement of dredged materials within island edges will be contained within a geotextile with pockets and posts, installed using operator and long reach excavator, and within sheet piles for the land reclamation of the peninsula.

Dredging is only taking place across certain areas of the Broadwater Lake where increased depths are required to allow for sailing corridors. Depths of dredging are indicated at a maximum of 2m depth. From all the information and data provided to Hydrogeo and reviewed in preparation of this report, it appears that the alluvium deposits will remain intact during the dredging process, and that no further interconnectivity between the groundwater and Broadwater Lake will be created.

Where interconnectivity does occur, it is likely to be across limited areas, which are unlikely to significantly affect the present condition of the underlying groundwater.

Horizontal Directional Drilling (HDD)

Additional site investigation works are proposed, and currently being scoped in order to prove up ground conditions across the proposed HDD route, particularly at areas of drilling entry and exit.

HDD is a very common technique for the installation of sub-surface service connections, and the risks associated with it are well understood. Based on industry experience, planned design and skilled execution by a suitably qualified and competent HDD contractor, the risks are minimised.

A Breakout Management Plan should be put in place by the HDD contractor to assess the risks posed by potential breakouts of drilling fluid (bentonite). The Breakout Management Plan should incorporate the following measures:

- Drilling suspension protocols;
- Breakout containment strategies;
- Fluid removal and clean-up procedures, and;
- Incident recording and reporting.

It is recommended that no refuelling of plant machinery associated with the HDD process occurs within vicinity of any watercourses (Grand Union Canal and Eastern Broadwater Lake Channel).

Other Construction Considerations

A Construction Environmental Management Plan (CEMP) should be put in place to consider any potential risks associated with construction works on-site, i.e. temporary on-site storage and refuelling of site plant.

The CEMP should also consider the management of surface waters and surface water runoff during construction periods to ensure no potentially impacted surface waters enter Broadwater Lake, or the River Colne.

Affinity Water Public Water Boreholes

Affinity Water have been identified as a key stakeholder due to proximity of a PWS groundwater borehole and sensitivity of the groundwater environment.

Affinity Water have been consulted at the pre-planning application stage, and provided with a draft version of this groundwater risk assessment, and draft versions of the Phase I Geo-environmental Assessment, and Phase II Site investigation reports for review and comment.

Dialogue is to be continued with Affinity Water throughout the enabling, construction and operational phases of development.

An Affinity Groundwater Abstraction borehole is located approximately 500m west of the proposed development Site. This borehole is advanced to a maximum depth of 57mbgl, and abstracts groundwater from the Principal Chalk Aquifer.

9 Conclusions

9.1 Conclusions

Hydrogeo Limited (Hydrogeo) has been commissioned by Quod (The Client) to undertake a Groundwater Risk Assessment for the Proposed Development of Hillingdon Water Sports Facility and Activity Centre.

Outdoor Activity Centre at Broadwater Lake. The current outdoor activity centre is to be relocated as a result of construction works associated with the High Speed 2 Rail Scheme.

The hydrogeological conceptual model has been characterised based upon previous reports progressed by Geo-Integrity, including a Phase I Geo-environmental Desk Study and Site Walkover, as well as the subsequent Phase II Site Investigation Report. Additional details have been captured from BGS maps and data.

The underlying chalk bedrock is designated by the Environment Agency as a 'Principal Aquifer', and the site is located within a Source Protection Zone I – Inner catchment, relating to a public water supply abstraction borehole.

The Geo-Integrity Phase II Site Investigation progressed 9no. boreholes, 14no. trial pits, and several other CBR and Soakaway test positions, which have been used to inform the geological and hydrogeological conditions underlying the site within this Groundwater Risk Assessment. The Site Investigation has identified a hotspot of hydrocarbon malodours and visually impacted made ground materials.

The groundwater beneath the site is expected to be partly in hydraulic continuity with the surface water features in the area, including Broadwater Lake itself, and the River Colne. The Groundwater flow direction is believed to be toward the base of the valley (toward Broadwater Lake). This direction may be influenced during periods of extensive pumping at the Affinity Public Supply Boreholes.

Made Ground and Contamination Hotspot

Laboratory analysis of 3no. soil samples from the identified hotspot area has indicated exceeding concentrations of Aliphatic >C10-12 and Aliphatic C12 – C16 TPH compounds, to a maximum depth of 2mbgl.

Using CL:AIRE Guidance 'Petroleum Hydrocarbons in Groundwater', these TPH Hydrocarbons have very low partition coefficient, a very low potential mobility ranking and an overall very low relative mobility in groundwater.

The low mobility is further evidenced by 3no. groundwater samples which indicates concentrations of all TPH chain determinants at concentrations below their respective laboratory Level of Detection (LoD).

Leachability testing of 2no. made ground samples did not identify any exceedances of the UK Drinking Water Standards (UKDWS), and is therefore not thought to pose a significant potential risk to the underlying aquifers.

A significant thickness of low permeability silty clay has been encountered which isolates the overlying made ground from the underlying superficial sands and gravels and chalk geology, restricting the vertical migration of potential contaminants.

The area of historic licensed inert landfill that extends partially onto the development site has been encountered as covered by a thickness of concrete hardstanding within the Geo-Integrity Site Investigation positions. This concrete layer is effectively acting as a capping layer and restricting the infiltration of rainwater and surface water into the underlying inert material.

Dredging

Screening of 20 no. Broadwater Lake sediment samples against stringent human health criteria did not indicate any exceeding concentrations, and it is not thought that this material poses a significant risk to the underlying groundwater and aquifers.

Proposed dredging requirements indicate that the maximum depth of dredging is to be between 1.5m – 2m beneath the existing lake base. Based on the conceptual model and geology of the site, dredging to this depth is not likely to significantly increase the continuity of the groundwater and Broadwater Lake as underlying low permeability silts and clays of the Alluvium depots will remain intact.

Proposed Development

A Construction Environmental Management Plan (CEMP) should be put in place to consider any potential risks associated with construction works on-site, i.e temporary on-site storage and refuelling of site plant.

The CEMP should also consider the management of surface waters and surface water runoff during construction periods to ensure no potentially impacted surface waters enter Broadwater Lake.

9.2 Recommendations

It is recommended that a specific Piling Risk Assessment is progressed to inform the construction process. The Piling Risk Assessment should detail the specific piling methodologies, risks associated with the piling operations, and mitigation measures required to inform the Development.

The concrete hardstanding cover WILL be left in-situ across the site to restrict the infiltration of rainwater / surface water into the made ground and therefore reduce the likelihood of leachate generation and lateral / vertical migration. The concrete hardstanding is currently covering the underlying historic licensed inert landfill area.

Discussions should be opened with Affinity Water at an early stage to gauge their potential concerns in regard to the works and to discuss any mitigation measures.

The Construction Environment Management Plan (CEMP) will address any potential risks posed by construction to the groundwater environment including the storage and refuelling of site plant vehicles and the management of surface water runoff during construction.

Construction phase works including construction of service trenches and ducts, as well as piling are likely to generate materials (arisings). Therefore it may be considered prudent to develop a remediation strategy which sets out control measures and explores where possible suitable retention and re-use areas for the generated materials in and across the proposed development site.


A Breakout Management Plan should be put in place by the HDD contractor to assess the risks posed by potential breakouts of drilling fluid (bentonite).

If any additional contamination 'hotspots' are identified a discovery strategy should be put in place and agreed with the local authority.






Drawings

Drawing 1

Superficial Geology Map




DRAWING 1 Superficial Geology

- KEY**
-  Site Boundary
 - GBR BGS 1:50k Superficial deposits**
 -  Alluvium
 -  Shepperton Gravel Member
 -  Gerrards Cross Gravel
 -  Winter Hill Gravel

Contains British Geological Survey materials
© NERC [2023]


Contains Bing Satellite imagery
© Microsoft [2023]







Date	By	Paper	Scale	Rev
05 2023	SG	A3	1:7,500	1

Drawing 2

Bedrock Geology Map



DRAWING 2 Bedrock Geology Map

- KEY**
-  Site Boundary
 - GBR BGS 1:50k Bedrock**
 -  London Clay Formation
 -  Lambeth Group
 -  Seaford Chalk Formation

Contains British Geological Survey materials
© NERC [2023]

Contains Bing Satellite imagery
© Microsoft [2023]



Date	By	Paper	Scale	Rev
05 2023	SG	A3	1:10,000	1


Drawing 3

Artificial Geology Map





DRAWING 3 Artificial Geology

KEY

 Site Boundary


GBR BGS 1:50k Artificial ground

 Worked Ground

 Infilled Ground

Contains British Geological Survey materials
© NERC [2023]


Contains Bing Satellite imagery
© Microsoft [2023]



Date	By	Paper	Scale	Rev
05 2023	SG	A3	1:7,500	1

Drawing 4

Regional Hydrogeological Conceptual Model



DRAWING 2 – Regional Hydrogeological Conceptual Site Model

Contains British Geological Survey materials [C10/018] © NERC [2023]
 Contains Ordnance Survey Data © Crown Copyrights [2023] Licence No. 100047852

Client: London Borough of Hillingdon

Project: Outdoor Activity Centre Ref: HYG1120

Date: 05 2023 Drawn By: SG Checked: MW

HYDROGEO

Telephone: 01873 856813 Email: mike@hydrogeo.co.uk Web: www.hydrogeo.co.uk

Drawing 5

Line of Cross-Sections




DRAWING 5 Cross-Sections

KEY
 Site Boundary

Contains British Geological Survey materials
© NERC [2023]

Contains Bing Satellite imagery
© Microsoft [2023]



Date	By	Paper	Scale	Rev
05 2023	SG	A3	1:7,500	1

Appendices

Appendix A

Broadwater Lake Sediment Laboratory Analysis

Appendix B

Broadwater Lake Sediment Screening Results

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 1

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	28-APR-2023

Report Number	66761
Sample Number	623553

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.0						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	22.4	2							
Available Potassium	170	2-							
Available Magnesium	69.6	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	23.0	Arable 200					
		Grassland 330					
Total Zinc	77.4	Arable 300					
		Grassland 300					
Total Nickel	37.6	Arable 110					
		Grassland 180					
Total Cadmium	0.52	Arable 3					
		Grassland 3					
Total Lead	29.6	Arable 300					
		Grassland 300					
Total Chromium	51.6	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Myles Nicholson*

Date *28/04/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 1

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	28-APR-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66761
Sample Number	623553

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	3.69	Arable 3		<div style="width: 100%; height: 10px; background-color: red;"></div>					
		Grassland 5							
Total Arsenic	15.4	Arable 50		<div style="width: 30%; height: 10px; background-color: blue;"></div>					
		Grassland 50							
Fluoride	68.4	Arable 500		<div style="width: 10%; height: 10px; background-color: blue;"></div>					
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Myles Nicholson

Date 28/04/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 1

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	28-APR-2023

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Report Number	66761
Sample Number	623553

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2248
Organic Matter LOI	% w/w	4.6
Total Nitrogen	% w/w	0.127
Total Phosphorus	mg/kg	999
Total Potassium	mg/kg	1778
Total Magnesium	mg/kg	2434
Total Calcium	mg/kg	39913
Total Sodium	mg/kg	174
Total Carbon	% w/w	2.71
Total Sulphur	mg/kg	2003

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 2

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--


Laboratory References

Date Received	11-APR-2023
Date Reported	28-APR-2023




Report Number	66761
Sample Number	623554

ANALYTICAL RESULTS *on 'dry matter' basis.*







pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.7						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	30.8	3							
Available Potassium	247	3							
Available Magnesium	96.6	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	29.9	Arable 200					
		Grassland 330					
Total Zinc	104	Arable 300					
		Grassland 300					
Total Nickel	38.7	Arable 110					
		Grassland 180					
Total Cadmium	0.65	Arable 3					
		Grassland 3					
Total Lead	39.2	Arable 300					
		Grassland 300					
Total Chromium	56.3	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Myles Nicholson

Date 28/04/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 2

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	28-APR-2023

Report Number	66761
Sample Number	623554

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	2.81	Arable 3		<div></div>					
		Grassland 5							
Total Arsenic	26.0	Arable 50		<div></div>					
		Grassland 50							
Fluoride	3.3	Arable 500		<div></div>					
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Myles Nicholson

Date 28/04/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 2

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received	11-APR-2023
Date Reported	28-APR-2023

Report Number	66761
Sample Number	623554

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2147
Organic Matter LOI	% w/w	6.8
Total Nitrogen	% w/w	0.219
Total Phosphorus	mg/kg	1435
Total Potassium	mg/kg	2371
Total Magnesium	mg/kg	3277
Total Calcium	mg/kg	82839
Total Sodium	mg/kg	230
Total Carbon	% w/w	4.34
Total Sulphur	mg/kg	2044

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 3

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--


Laboratory References

Date Received	11-APR-2023
Date Reported	16-MAY-2023




Report Number	66762
Sample Number	623555

ANALYTICAL RESULTS *on 'dry matter' basis.*







pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.1						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	18.8	2							
Available Potassium	122	2-							
Available Magnesium	46.9	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	18.5	Arable 200					
		Grassland 330					
Total Zinc	64.9	Arable 300					
		Grassland 300					
Total Nickel	29.7	Arable 110					
		Grassland 180					
Total Cadmium	0.37	Arable 3					
		Grassland 3					
Total Lead	21.2	Arable 300					
		Grassland 300					
Total Chromium	37.8	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Myles Nicholson*

Date *16/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 3

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	16-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66762
Sample Number	623555

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.96	Arable 3		<div></div>					
		Grassland 5							
Total Arsenic	17.7	Arable 50		<div></div>					
		Grassland 50							
Fluoride	3.8	Arable 500		<div></div>					
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Myles Nicholson

Date 16/05/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 3

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 16-MAY-2023

Report Number 66762
Sample Number 623555

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2090
Organic Matter LOI	% w/w	3.3
Total Nitrogen	% w/w	0.097
Total Phosphorus	mg/kg	902
Total Potassium	mg/kg	1623
Total Magnesium	mg/kg	2168
Total Calcium	mg/kg	91670
Total Sodium	mg/kg	173
Total Carbon	% w/w	3.60
Total Sulphur	mg/kg	1161

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 4

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	16-MAY-2023

Report Number	66762
Sample Number	623556

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.3						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	21.8	2							
Available Potassium	71.7	1							
Available Magnesium	37.8	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	16.2	Arable 200 Grassland 330					
Total Zinc	57.6	Arable 300 Grassland 300					
Total Nickel	26.1	Arable 110 Grassland 180					
Total Cadmium	0.32	Arable 3 Grassland 3					
Total Lead	16.1	Arable 300 Grassland 300					
Total Chromium	31.3	Arable 400 Grassland 600					
Total Mercury	<0.2	Arable 1 Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Myles Nicholson*

Date *16/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 4

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	16-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66762
Sample Number	623556

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.55	Arable 3							
		Grassland 5							
Total Arsenic	23.9	Arable 50							
		Grassland 50							
Fluoride	5.1	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Myles Nicholson

Date 16/05/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 4

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	16-MAY-2023

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Report Number	66762
Sample Number	623556

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2144
Organic Matter LOI	% w/w	2.5
Total Nitrogen	% w/w	0.071
Total Phosphorus	mg/kg	815
Total Potassium	mg/kg	1435
Total Magnesium	mg/kg	1944
Total Calcium	mg/kg	74280
Total Sodium	mg/kg	147
Total Carbon	% w/w	3.28
Total Sulphur	mg/kg	562

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 5

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66763
Sample Number 623557

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.1						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	20.2	2							
Available Potassium	111	1							
Available Magnesium	49.5	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	20.5	Arable 200					
		Grassland 330					
Total Zinc	64.5	Arable 300					
		Grassland 300					
Total Nickel	32.4	Arable 110					
		Grassland 180					
Total Cadmium	0.47	Arable 3					
		Grassland 3					
Total Lead	26.0	Arable 300					
		Grassland 300					
Total Chromium	40.8	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1 Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 5

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66763
Sample Number	623557

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.95	Arable 3							
		Grassland 5							
Total Arsenic	19.3	Arable 50							
		Grassland 50							
Fluoride	4.2	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 5

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66763
Sample Number	623557

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2169
Organic Matter LOI	% w/w	4.9
Total Nitrogen	% w/w	0.155
Total Phosphorus	mg/kg	891
Total Potassium	mg/kg	1761
Total Magnesium	mg/kg	2311
Total Calcium	mg/kg	62983
Total Sodium	mg/kg	175
Total Carbon	% w/w	3.93
Total Sulphur	mg/kg	1633

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 6

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66763
Sample Number	623558

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.0						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	14.8	1							
Available Potassium	76.6	1							
Available Magnesium	42.2	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	17.7	Arable 200					
		Grassland 330					
Total Zinc	54.2	Arable 300					
		Grassland 300					
Total Nickel	31.1	Arable 110					
		Grassland 180					
Total Cadmium	0.48	Arable 3					
		Grassland 3					
Total Lead	21.1	Arable 300					
		Grassland 300					
Total Chromium	32.9	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 6

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66763
Sample Number	623558

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.62	Arable 3							
		Grassland 5							
Total Arsenic	12.8	Arable 50							
		Grassland 50							
Fluoride	5.7	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 6

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66763
Sample Number 623558

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2186
Organic Matter LOI	% w/w	4.6
Total Nitrogen	% w/w	0.157
Total Phosphorus	mg/kg	761
Total Potassium	mg/kg	1513
Total Magnesium	mg/kg	1996
Total Calcium	mg/kg	71156
Total Sodium	mg/kg	152
Total Carbon	% w/w	4.06
Total Sulphur	mg/kg	1981

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 7

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66764
Sample Number	623559

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.0						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	16.4	2							
Available Potassium	82.2	1							
Available Magnesium	41.2	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	20.4	Arable 200					
		Grassland 330					
Total Zinc	63.2	Arable 300					
		Grassland 300					
Total Nickel	34.0	Arable 110					
		Grassland 180					
Total Cadmium	0.61	Arable 3					
		Grassland 3					
Total Lead	23.8	Arable 300					
		Grassland 300					
Total Chromium	37.5	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 7

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66764
Sample Number	623559

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.64	Arable 3							
		Grassland 5							
Total Arsenic	18.0	Arable 50							
		Grassland 50							
Fluoride	4.0	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 7

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66764
Sample Number 623559

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2177
Organic Matter LOI	% w/w	5.2
Total Nitrogen	% w/w	0.184
Total Phosphorus	mg/kg	851
Total Potassium	mg/kg	1786
Total Magnesium	mg/kg	2219
Total Calcium	mg/kg	71128
Total Sodium	mg/kg	175
Total Carbon	% w/w	4.36
Total Sulphur	mg/kg	2429

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 8

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--


Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023


Report Number	66764
Sample Number	623560

ANALYTICAL RESULTS *on 'dry matter' basis.*


pH ⁽¹⁾



Soil Nutrients ⁽¹⁾



Potentially Toxic Elements ⁽²⁾



(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 8

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66764
Sample Number	623560

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.56	Arable 3							
		Grassland 5							
Total Arsenic	39.7	Arable 50							
		Grassland 50							
Fluoride	3.9	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 8

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66764
Sample Number 623560

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2132
Organic Matter LOI	% w/w	3.8
Total Nitrogen	% w/w	0.116
Total Phosphorus	mg/kg	1289
Total Potassium	mg/kg	1882
Total Magnesium	mg/kg	2367
Total Calcium	mg/kg	62089
Total Sodium	mg/kg	182
Total Carbon	% w/w	3.11
Total Sulphur	mg/kg	1354

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 9

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66765
Sample Number	623561

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	8.0						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	16.4	2							
Available Potassium	85.8	1							
Available Magnesium	45.9	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	20.7	Arable 200					
		Grassland 330					
Total Zinc	60.7	Arable 300					
		Grassland 300					
Total Nickel	26.5	Arable 110					
		Grassland 180					
Total Cadmium	0.47	Arable 3					
		Grassland 3					
Total Lead	20.4	Arable 300					
		Grassland 300					
Total Chromium	35.5	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 9

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66765
Sample Number	623561

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	1.56	Arable 3						
		Grassland 5						
Total Arsenic	18.8	Arable 50						
		Grassland 50						
Fluoride	69.8	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 9

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66765
Sample Number	623561

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2173
Organic Matter LOI	% w/w	5.8
Total Nitrogen	% w/w	0.186
Total Phosphorus	mg/kg	753
Total Potassium	mg/kg	1606
Total Magnesium	mg/kg	2148
Total Calcium	mg/kg	34813
Total Sodium	mg/kg	156
Total Carbon	% w/w	3.53
Total Sulphur	mg/kg	1344

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 10

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66765
Sample Number 623562

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.9						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	41.6	3							
Available Potassium	136	2-							
Available Magnesium	51.5	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	24.8	Arable 200 Grassland 330					
Total Zinc	95.3	Arable 300 Grassland 300					
Total Nickel	37.5	Arable 110 Grassland 180					
Total Cadmium	0.51	Arable 3 Grassland 3					
Total Lead	26.6	Arable 300 Grassland 300					
Total Chromium	56.4	Arable 400 Grassland 600					
Total Mercury	<0.2	Arable 1 Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 10

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66765
Sample Number	623562

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4 Grassland 4							
Total Selenium	1.98	Arable 3 Grassland 5							
Total Arsenic	26.4	Arable 50 Grassland 50							
Fluoride	5.3	Arable 500 Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 11

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66766
Sample Number 623563

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	12.4	1							
Available Potassium	63.7	1							
Available Magnesium	33.2	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	26.5	Arable 200					
		Grassland 330					
Total Zinc	57.5	Arable 300					
		Grassland 300					
Total Nickel	25.6	Arable 110					
		Grassland 180					
Total Cadmium	0.49	Arable 3					
		Grassland 3					
Total Lead	52.9	Arable 300					
		Grassland 300					
Total Chromium	28.4	Arable 400					
		Grassland 600					
Total Mercury	0.37	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 11

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66766
Sample Number	623563

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.84	Arable 3							
		Grassland 5							
Total Arsenic	17.9	Arable 50							
		Grassland 50							
Fluoride	49.3	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 11

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66766
Sample Number	623563

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2183
Organic Matter LOI	% w/w	8.6
Total Nitrogen	% w/w	0.295
Total Phosphorus	mg/kg	730
Total Potassium	mg/kg	1120
Total Magnesium	mg/kg	1636
Total Calcium	mg/kg	35370
Total Sodium	mg/kg	129
Total Carbon	% w/w	4.82
Total Sulphur	mg/kg	2056

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 12

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66766
Sample Number 623564

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.9						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	10.6	1							
Available Potassium	106	1							
Available Magnesium	45.2	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	30.3	Arable 200					
		Grassland 330					
Total Zinc	55.9	Arable 300					
		Grassland 300					
Total Nickel	22.8	Arable 110					
		Grassland 180					
Total Cadmium	0.42	Arable 3					
		Grassland 3					
Total Lead	71.6	Arable 300					
		Grassland 300					
Total Chromium	28.0	Arable 400					
		Grassland 600					
Total Mercury	0.52	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 12

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66766
Sample Number	623564

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	1.59	Arable 3						
		Grassland 5						
Total Arsenic	11.6	Arable 50						
		Grassland 50						
Fluoride	56.5	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 12

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66766
Sample Number	623564

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2167
Organic Matter LOI	% w/w	7.9
Total Nitrogen	% w/w	0.304
Total Phosphorus	mg/kg	573
Total Potassium	mg/kg	1138
Total Magnesium	mg/kg	2016
Total Calcium	mg/kg	29251
Total Sodium	mg/kg	143
Total Carbon	% w/w	4.27
Total Sulphur	mg/kg	1121

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 13

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE


SOIL




Laboratory References








Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66767
Sample Number 623565

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾		Soil pH						
Determinand	Result	4	5	6	7	8	9	
Soil pH	7.8							

Soil Nutrients ⁽¹⁾			Soil Index						
Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	18.2	2							
Available Potassium	147	2-							
Available Magnesium	52.7	2							

Potentially Toxic Elements ⁽²⁾				% of maximum permissible concentration of PTE in arable/grassland soil					
Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%		
Total Copper	30.1	Arable 200							
		Grassland 330							
Total Zinc	80.7	Arable 300							
		Grassland 300							
Total Nickel	38.6	Arable 110							
		Grassland 180							
Total Cadmium	0.72	Arable 3							
		Grassland 3							
Total Lead	45.2	Arable 300							
		Grassland 300							
Total Chromium	52.1	Arable 400							
		Grassland 600							
Total Mercury	0.27	Arable 1							
		Grassland 1.5							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 13

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66767
Sample Number	623565

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	2.47	Arable 3		<div></div>					
		Grassland 5							
Total Arsenic	24.8	Arable 50		<div></div>					
		Grassland 50							
Fluoride	3.0	Arable 500		<div></div>					
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 13

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66767
Sample Number 623565

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2265
Organic Matter LOI	% w/w	8.4
Total Nitrogen	% w/w	0.311
Total Phosphorus	mg/kg	1252
Total Potassium	mg/kg	1913
Total Magnesium	mg/kg	2451
Total Calcium	mg/kg	65755
Total Sodium	mg/kg	218
Total Carbon	% w/w	5.80
Total Sulphur	mg/kg	2546

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 14

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66767
Sample Number 623566

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	22.6	2							
Available Potassium	173	2-							
Available Magnesium	72.3	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	33.1	Arable 200					
		Grassland 330					
Total Zinc	89.9	Arable 300					
		Grassland 300					
Total Nickel	39.2	Arable 110					
		Grassland 180					
Total Cadmium	0.73	Arable 3					
		Grassland 3					
Total Lead	53.6	Arable 300					
		Grassland 300					
Total Chromium	55.2	Arable 400					
		Grassland 600					
Total Mercury	0.36	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 14

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66767
Sample Number	623566

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	2.63	Arable 3						
		Grassland 5						
Total Arsenic	26.6	Arable 50						
		Grassland 50						
Fluoride	3.0	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 14

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66767
Sample Number	623566

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2295
Organic Matter LOI	% w/w	10.3
Total Nitrogen	% w/w	0.359
Total Phosphorus	mg/kg	1355
Total Potassium	mg/kg	2214
Total Magnesium	mg/kg	2679
Total Calcium	mg/kg	66043
Total Sodium	mg/kg	227
Total Carbon	% w/w	6.23
Total Sulphur	mg/kg	3445

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 15

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66768
Sample Number 623567

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.9						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	18.2	2							
Available Potassium	108	1							
Available Magnesium	45.5	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	20.4	Arable 200					
		Grassland 330					
Total Zinc	59.3	Arable 300					
		Grassland 300					
Total Nickel	27.0	Arable 110					
		Grassland 180					
Total Cadmium	0.48	Arable 3					
		Grassland 3					
Total Lead	31.4	Arable 300					
		Grassland 300					
Total Chromium	42.0	Arable 400					
		Grassland 600					
Total Mercury	<0.2	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 15

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66768
Sample Number	623567

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	1.91	Arable 3							
		Grassland 5							
Total Arsenic	19.1	Arable 50							
		Grassland 50							
Fluoride	9.2	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by Daniel Petty

Date 02/05/23

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 16

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66768
Sample Number 623568

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	18.4	2							
Available Potassium	125	2-							
Available Magnesium	47.1	1							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	22.3	Arable 200					
		Grassland 330					
Total Zinc	59.6	Arable 300					
		Grassland 300					
Total Nickel	27.4	Arable 110					
		Grassland 180					
Total Cadmium	0.49	Arable 3					
		Grassland 3					
Total Lead	31.6	Arable 300					
		Grassland 300					
Total Chromium	37.0	Arable 400					
		Grassland 600					
Total Mercury	0.21	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 16

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66768
Sample Number	623568

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	2.15	Arable 3						
		Grassland 5						
Total Arsenic	20.3	Arable 50						
		Grassland 50						
Fluoride	3.2	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 16

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66768
Sample Number	623568

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2275
Organic Matter LOI	% w/w	8.4
Total Nitrogen	% w/w	0.382
Total Phosphorus	mg/kg	869
Total Potassium	mg/kg	1529
Total Magnesium	mg/kg	1974
Total Calcium	mg/kg	72259
Total Sodium	mg/kg	215
Total Carbon	% w/w	6.47
Total Sulphur	mg/kg	3895

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 17

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66769
Sample Number 623569

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	19.0	2							
Available Potassium	140	2-							
Available Magnesium	60.8	2							

Potentially Toxic Elements ⁽²⁾

Potentially Toxic Elements (2)				% of maximum permissible concentration of PTE in arable/grassland soil				
Determinand	Result mg/kg		Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	23.4	Arable	200	<div><div></div></div>				
		Grassland	330					
Total Zinc	69.0	Arable	300	<div><div></div></div>				
		Grassland	300					
Total Nickel	30.6	Arable	110	<div><div></div></div>				
		Grassland	180					
Total Cadmium	0.61	Arable	3	<div><div></div></div>				
		Grassland	3					
Total Lead	30.9	Arable	300	<div><div></div></div>				
		Grassland	300					
Total Chromium	45.2	Arable	400	<div><div></div></div>				
		Grassland	600					
Total Mercury	<0.2	Arable	1	<div><div></div></div>				
		Grassland	1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 17

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66769
Sample Number	623569

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	% of maximum permissible concentration of PTE in arable/grassland soil					100%
				25%	50%	75%			
Total Molybdenum	<1	Arable 4							
		Grassland 4							
Total Selenium	2.22	Arable 3							
		Grassland 5							
Total Arsenic	21.6	Arable 50							
		Grassland 50							
Fluoride	3.0	Arable 500							
		Grassland 500							

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 17

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66769
Sample Number	623569

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2270
Organic Matter LOI	% w/w	8.6
Total Nitrogen	% w/w	0.366
Total Phosphorus	mg/kg	983
Total Potassium	mg/kg	1787
Total Magnesium	mg/kg	2456
Total Calcium	mg/kg	60733
Total Sodium	mg/kg	192
Total Carbon	% w/w	5.93
Total Sulphur	mg/kg	3561

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 18

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66769
Sample Number 623570

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.7						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	15.4	1							
Available Potassium	123	2-							
Available Magnesium	80.3	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	29.7	Arable 200					
		Grassland 330					
Total Zinc	69.1	Arable 300					
		Grassland 300					
Total Nickel	33.7	Arable 110					
		Grassland 180					
Total Cadmium	0.57	Arable 3					
		Grassland 3					
Total Lead	45.0	Arable 300					
		Grassland 300					
Total Chromium	41.4	Arable 400					
		Grassland 600					
Total Mercury	0.31	Arable 1					
		Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 18

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66769
Sample Number	623570

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	3.08	Arable 3						
		Grassland 5						
Total Arsenic	22.1	Arable 50						
		Grassland 50						
Fluoride	2.5	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 18

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66769
Sample Number	623570

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO4	uS/cm	2339
Organic Matter LOI	% w/w	14.4
Total Nitrogen	% w/w	0.602
Total Phosphorus	mg/kg	840
Total Potassium	mg/kg	1791
Total Magnesium	mg/kg	2462
Total Calcium	mg/kg	70175
Total Sodium	mg/kg	238
Total Carbon	% w/w	10.3
Total Sulphur	mg/kg	5405

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 19

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66770
Sample Number 623571

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	21.0	2							
Available Potassium	143	2-							
Available Magnesium	78.2	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	31.5	Arable 200 Grassland 330					
Total Zinc	87.5	Arable 300 Grassland 300					
Total Nickel	40.6	Arable 110 Grassland 180					
Total Cadmium	0.66	Arable 3 Grassland 3					
Total Lead	40.0	Arable 300 Grassland 300					
Total Chromium	49.4	Arable 400 Grassland 600					
Total Mercury	0.21	Arable 1 Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 19

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

Date Received	11-APR-2023
Date Reported	02-MAY-2023

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Report Number	66770
Sample Number	623571

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil				
			0%	25%	50%	75%	100%
Total Molybdenum	<1	Arable 4 Grassland 4					
Total Selenium	3.27	Arable 3 Grassland 5					
Total Arsenic	28.1	Arable 50 Grassland 50					
Fluoride	2.4	Arable 500 Grassland 500					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 19

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66770
Sample Number 623571

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2267
Organic Matter LOI	% w/w	12.0
Total Nitrogen	% w/w	0.488
Total Phosphorus	mg/kg	1074
Total Potassium	mg/kg	2192
Total Magnesium	mg/kg	3071
Total Calcium	mg/kg	70782
Total Sodium	mg/kg	228
Total Carbon	% w/w	7.82
Total Sulphur	mg/kg	3159

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 20

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66770
Sample Number 623572

ANALYTICAL RESULTS *on 'dry matter' basis.*

pH ⁽¹⁾

Determinand	Result	4	5	6	7	8	9
Soil pH	7.8						

Soil Nutrients ⁽¹⁾

Determinand	Result mg/litre	Soil Index	0	1	2	3	4	5	6
Available Phosphorus	21.0	2							
Available Potassium	182	2+							
Available Magnesium	97.3	2							

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	0%	25%	50%	75%	100%
Total Copper	33.9	Arable 200 Grassland 330					
Total Zinc	101	Arable 300 Grassland 300					
Total Nickel	43.3	Arable 110 Grassland 180					
Total Cadmium	0.69	Arable 3 Grassland 3					
Total Lead	43.7	Arable 300 Grassland 300					
Total Chromium	58.5	Arable 400 Grassland 600					
Total Mercury	0.20	Arable 1 Grassland 1.5					

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by **Daniel Petty**

Date **02/05/23**

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 20

HYDROGEO LTD UNIT 4 WADDINGTON HOUSE LLANOVER BUSINESS CENTRE LLANOVER ABERGAVENNY NP7 9HA	W184
---	-------------

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD GREEN TREE HOUSE SOIL
--

Laboratory References

Date Received	11-APR-2023
Date Reported	02-MAY-2023

Report Number	66770
Sample Number	623572

ANALYTICAL RESULTS *on 'dry matter' basis.*

Potentially Toxic Elements ⁽²⁾

Determinand	Result mg/kg	Maximum mg/kg	% of maximum permissible concentration of PTE in arable/grassland soil					
			0%	25%	50%	75%	100%	
Total Molybdenum	<1	Arable 4						
		Grassland 4						
Total Selenium	3.20	Arable 3						
		Grassland 5						
Total Arsenic	30.4	Arable 50						
		Grassland 50						
Fluoride	2.5	Arable 500						
		Grassland 500						

(1) Recommendations for liming and fertiliser should be obtained from Defra's Fertiliser Manual (RB209). The analytical methods used are as described in Defra's RB427.

(2) Concentration of Potentially Toxic Elements (PTE, commonly referred to as 'heavy metals') are in mg/kg dry soil. The maximum and the percentage of this maximum permissible concentration of PTE in soil are derived from the values in Defra's Code of Practice for Agricultural Use of Sewage Sludge (England & Wales) 1996. If applying organic manures to this soil it is important to ensure the soil is managed with a pH no less than 5.0, and that the PTE maximum values are not exceeded following the application. For soil where the pH value is less than 5.2, a FACTS Qualified Adviser should be consulted. Further details are provided in the Sludge Code.

Released by *Daniel Petty*

Date *02/05/23*

SOIL CHEMICAL ANALYSIS REPORT FOR FIELD - BROADWATERLAKE 20

HYDROGEO LTD
UNIT 4 WADDINGTON HOUSE
LLANOVER BUSINESS CENTRE
LLANOVER
ABERGAVENNY
NP7 9HA

W184

Please quote above code for all enquiries

JOHNS ASSOCIATES LTD
GREEN TREE HOUSE

SOIL

Laboratory References

Date Received 11-APR-2023
Date Reported 02-MAY-2023

Report Number 66770
Sample Number 623572

ANALYTICAL RESULTS *on 'dry matter' basis.*

Determinand	Units	Result
Conductivity Sat CaSO ₄	uS/cm	2328
Organic Matter LOI	% w/w	10.0
Total Nitrogen	% w/w	0.377
Total Phosphorus	mg/kg	1222
Total Potassium	mg/kg	2590
Total Magnesium	mg/kg	3520
Total Calcium	mg/kg	60303
Total Sodium	mg/kg	265
Total Carbon	% w/w	5.74
Total Sulphur	mg/kg	1756

ANALYTICAL REPORT

Report Number	77342-25	W492	JOHNS ASSOCIATES LTD	Client	BROADWATER LAKE
Date Received	06-FEB-2025		GREEN TREE HOUSE		UB9 6AH
Date Reported	17-MAR-2025		11 ST MARGARETS STREET		
Project	SEDMIENT		BRADFORD ON AVON		
Reference	BROADWATER LAKE		BA15 1DA		
Order Number	1437				

Laboratory Reference		SLUR162218	SLUR162219	SLUR162220	SLUR162221	SLUR162222	SLUR162223	SLUR162224	SLUR162225	SLUR162226	SLUR162227
Sample Reference		SITE 11	SITE 12	SITE 13	SITE 14	SITE 15	SITE 16	SITE 17	SITE 18	SITE 19	SITE 20
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Oven Dry Solids	%	17.6	34.7	29.5	15.1	30.6	5.28	15.2	22.0	3.64	34.8
Asbestos Screen		None detected	None detected	None detected	None detected	None detected	None detected	None detected	None detected	None detected	None detected
Hexavalent Chromium	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Total PAH	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
TPH [C5-C35]	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C5-C6	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C6-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C5-C7	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C7-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Conductivity 1:6	uS/cm	181	163	161	173	152	166	151	167	159	335
Total Kjeldahl Nitrogen	% w/w	0.11	0.12	0.12	0.14	0.13	0.11	0.11	0.12	0.13	0.13
Nitrate Nitrogen	mg/kg	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Ammonium Nitrogen	mg/kg	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25
Total Phosphorus (P)	mg/kg	145	128	66.3	154	137	112	136	58.4	114	157
Total Potassium (K)	mg/kg	272	254	174	376	404	324	452	167	346	391

ANALYTICAL REPORT

Report Number	77342-25	W492	JOHNS ASSOCIATES LTD	Client	BROADWATER LAKE
Date Received	06-FEB-2025		GREEN TREE HOUSE		UB9 6AH
Date Reported	17-MAR-2025		11 ST MARGARETS STREET		
Project	SEDMIENT		BRADFORD ON AVON		
Reference	BROADWATER LAKE		BA15 1DA		
Order Number	1437				

Laboratory Reference		SLUR162218	SLUR162219	SLUR162220	SLUR162221	SLUR162222	SLUR162223	SLUR162224	SLUR162225	SLUR162226	SLUR162227
Sample Reference		SITE 11	SITE 12	SITE 13	SITE 14	SITE 15	SITE 16	SITE 17	SITE 18	SITE 19	SITE 20
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Total Magnesium (Mg)	mg/kg	383	345	198	514	532	418	542	199	416	504
Total Copper (Cu)	mg/kg	2.99	2.81	2.06	4.76	4.62	3.56	5.60	2.76	6.48	5.30
Total Zinc (Zn)	mg/kg	11.1	10.2	7.51	16.8	19.0	12.9	20.7	9.25	19.6	18.7
Total Sulphur (S)	mg/kg	1196	1166	523	1841	1347	765	1389	676	1116	1895
Total Calcium (Ca)	mg/kg	47681	41641	12062	46186	29706	15362	16376	14524	16779	24393
Total Molybdenum (Mo)	mg/kg	0.10	0.11	<0.05	0.17	0.13	0.07	0.16	0.08	0.20	0.25
Total Lead (Pb)	mg/kg	3.96	4.00	3.26	6.30	6.90	5.61	10.7	6.46	21.9	12.2
Total Cadmium (Cd)	mg/kg	0.07	0.07	0.05	0.12	0.10	0.07	0.12	0.05	0.10	0.10
Total Mercury (Hg)	mg/kg	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.08	<0.05
Total Nickel (Ni)	mg/kg	4.62	3.95	2.92	6.57	6.81	5.31	6.91	2.49	5.12	6.31
Total Chromium (Cr)	mg/kg	5.43	4.81	2.92	7.51	8.35	6.98	8.87	3.08	6.48	8.03
Total Sodium (Na)	mg/kg	70.3	66.7	51.6	71.0	66.6	57.3	64.0	52.4	64.2	68.4
pH 1:6 [Fresh]		7.85	8.00	7.88	7.93	8.13	7.99	8.20	7.96	8.07	7.78
Organic Matter LOI	% w/w	1.58	2.46	2.64	1.84	2.46	0.43	1.82	2.17	0.50	2.61
Fluoride [100:1 H2SO4 Soluble]	mg/kg	15.3	15.0	<10	16.9	23.1	23.3	17.4	<10	12.9	18.7
Total Arsenic (As)	mg/kg	3.23	2.74	1.25	4.31	3.09	1.78	2.96	1.69	2.72	3.78
Total Selenium (Se)	mg/kg	0.52	0.42	0.34	0.69	0.57	0.45	0.53	0.21	0.39	0.46
Naphthalene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluorene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Phenanthrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable

ANALYTICAL REPORT											
Report Number	77342-25	W492	JOHNS ASSOCIATES LTD GREEN TREE HOUSE 11 ST MARGARETS STREET BRADFORD ON AVON BA15 1DA					Client BROADWATER LAKE UB9 6AH			
Date Received	06-FEB-2025										
Date Reported	17-MAR-2025										
Project	SEDMIENT										
Reference	BROADWATER LAKE										
Order Number	1437										
Laboratory Reference		SLUR162218	SLUR162219	SLUR162220	SLUR162221	SLUR162222	SLUR162223	SLUR162224	SLUR162225	SLUR162226	SLUR162227
Sample Reference		SITE 11	SITE 12	SITE 13	SITE 14	SITE 15	SITE 16	SITE 17	SITE 18	SITE 19	SITE 20
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Benzo[a]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Chrysene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[b]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[k]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[a]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Indeno[1,2,3-cd]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Dibenzo[a,h]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[g,h,i]perylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Notes											
Analysis Notes		<p>The sample submitted was of adequate size to complete all analysis requested.</p> <p>The results as reported relate only to the item(s) submitted for testing.</p> <p>The results are presented on an as received basis unless otherwise stipulated.</p>									
Document Control		This test report shall not be reproduced, except in full, without the written approval of the laboratory.									
Reported by		<p><i>Daniel Petty</i></p> <p>Natural Resource Management, a trading division of Cawood Scientific Ltd.</p> <p>Coopers Bridge, Braziers Lane, Bracknell, Berkshire, RG42 6NS</p> <p>Tel: 01344 886338</p> <p>Fax: 01344 890972</p> <p>email: enquiries@nrm.uk.com</p>									

ANALYTICAL REPORT

Report Number	77341-25	W492	JOHNS ASSOCIATES LTD	Client	BROADWATER LAKE
Date Received	06-FEB-2025		GREEN TREE HOUSE		UB9 6AH
Date Reported	17-MAR-2025		11 ST MARGARETS STREET		
Project	SEDMIENT		BRADFORD ON AVON		
Reference	BROADWATER LAKE		BA15 1DA		
Order Number	1437				

Laboratory Reference		SLUR162208	SLUR162209	SLUR162210	SLUR162211	SLUR162212	SLUR162213	SLUR162214	SLUR162215	SLUR162216	SLUR162217
Sample Reference		SITE 1	SITE 2	SITE 3	SITE 4	SITE 5	SITE 6	SITE 7	SITE 8	SITE 9	SITE 10
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Oven Dry Solids	%	15.9	10.6	7.47	22.7	15.8	25.0	4.40	19.4	27.3	40.8
Asbestos Screen		None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected
Hexavalent Chromium	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Total PAH	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
TPH [C5-C35]	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C5-C6	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C6-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C5-C7	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C7-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Conductivity 1:6	uS/cm	140	179	140	162	164	191	161	166	162	169
Total Kjeldahl Nitrogen	% w/w	0.12	0.13	0.12	0.13	0.14	0.13	0.12	0.13	0.11	0.11
Nitrate Nitrogen	mg/kg	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Ammonium Nitrogen	mg/kg	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25
Total Phosphorus (P)	mg/kg	147	132	139	140	130	182	133	91.7	146	175
Total Potassium (K)	mg/kg	491	450	412	431	366	963	339	221	399	415

ANALYTICAL REPORT

Report Number	77341-25	W492	JOHNS ASSOCIATES LTD	Client	BROADWATER LAKE
Date Received	06-FEB-2025		GREEN TREE HOUSE		UB9 6AH
Date Reported	17-MAR-2025		11 ST MARGARETS STREET		
Project	SEDMIENT		BRADFORD ON AVON		
Reference	BROADWATER LAKE		BA15 1DA		
Order Number	1437				

Laboratory Reference		SLUR162208	SLUR162209	SLUR162210	SLUR162211	SLUR162212	SLUR162213	SLUR162214	SLUR162215	SLUR162216	SLUR162217
Sample Reference		SITE 1	SITE 2	SITE 3	SITE 4	SITE 5	SITE 6	SITE 7	SITE 8	SITE 9	SITE 10
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Total Magnesium (Mg)	mg/kg	638	579	527	551	421	1170	419	263	468	508
Total Copper (Cu)	mg/kg	8.33	7.65	5.59	5.53	4.57	1.13	2.86	2.59	4.49	4.67
Total Zinc (Zn)	mg/kg	22.4	20.7	20.6	20.9	16.7	7.73	9.50	9.28	16.9	18.3
Total Sulphur (S)	mg/kg	1714	1559	1738	1897	1303	1420	1199	939	934	1087
Total Calcium (Ca)	mg/kg	22702	20821	30855	33391	22383	42804	32918	21402	19825	27895
Total Molybdenum (Mo)	mg/kg	0.69	0.63	0.19	0.22	0.16	0.12	0.10	0.08	0.12	0.12
Total Lead (Pb)	mg/kg	11.6	10.4	9.96	8.29	6.45	7.14	6.21	3.63	6.84	6.89
Total Cadmium (Cd)	mg/kg	0.12	0.12	0.13	0.14	0.11	0.16	0.09	0.07	0.11	0.11
Total Mercury (Hg)	mg/kg	<0.05	<0.05	<0.05	<0.05	<0.05	0.05	<0.05	<0.05	<0.05	<0.05
Total Nickel (Ni)	mg/kg	7.72	6.93	6.44	6.52	6.02	12.6	5.72	3.32	6.08	6.88
Total Chromium (Cr)	mg/kg	9.85	8.88	8.29	8.18	6.76	18.3	7.16	4.01	8.07	8.80
Total Sodium (Na)	mg/kg	69.0	66.5	68.0	71.7	64.6	86.6	64.1	59.0	64.0	67.4
pH 1:6 [Fresh]		8.16	7.99	8.15	8.11	8.07	7.82	7.96	8.02	8.09	8.03
Organic Matter LOI	% w/w	1.64	1.52	0.92	2.69	2.39	2.65	0.53	2.31	2.87	2.23
Fluoride [100:1 H2SO4 Soluble]	mg/kg	22.9	12.7	22.4	17.5	16.1	18.9	17.0	13.8	23.3	25.9
Total Arsenic (As)	mg/kg	4.18	3.78	4.11	3.98	2.92	4.13	2.96	1.80	2.35	2.73
Total Selenium (Se)	mg/kg	0.56	0.51	0.53	0.57	0.52	0.63	0.74	0.37	0.55	0.60
Naphthalene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluorene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Phenanthrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable

ANALYTICAL REPORT											
Report Number	77341-25	W492	JOHNS ASSOCIATES LTD GREEN TREE HOUSE 11 ST MARGARETS STREET BRADFORD ON AVON BA15 1DA					Client BROADWATER LAKE UB9 6AH			
Date Received	06-FEB-2025										
Date Reported	17-MAR-2025										
Project	SEDMIENT										
Reference	BROADWATER LAKE										
Order Number	1437										
Laboratory Reference		SLUR162208	SLUR162209	SLUR162210	SLUR162211	SLUR162212	SLUR162213	SLUR162214	SLUR162215	SLUR162216	SLUR162217
Sample Reference		SITE 1	SITE 2	SITE 3	SITE 4	SITE 5	SITE 6	SITE 7	SITE 8	SITE 9	SITE 10
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Benzo[a]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Chrysene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[b]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[k]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[a]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Indeno[1,2,3-cd]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Dibenzo[a,h]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[g,h,i]perylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Notes											
Analysis Notes		The sample submitted was of adequate size to complete all analysis requested. The results as reported relate only to the item(s) submitted for testing. The results are presented on an as received basis unless otherwise stipulated.									
Document Control		This test report shall not be reproduced, except in full, without the written approval of the laboratory.									
Reported by		<i>Daniel Petty</i> Natural Resource Management, a trading division of Cawood Scientific Ltd. Coopers Bridge, Braziers Lane, Bracknell, Berkshire, RG42 6NS Tel: 01344 886338 Fax: 01344 890972 email: enquiries@nrm.uk.com									

Determinants	Units	Broadwater Lake 1	Broadwater Lake 2	Broadwater Lake 3	Broadwater Lake 4	Broadwater Lake 5	Broadwater Lake 6	Broadwater Lake 7	Broadwater Lake 8
pH	pH units	8	7	8.1	8.3	8.1	8	8	8
Phosphorus	mg/l	22.4	30.8	18.8	21.8	20.2	14.8	16.4	31.8
Potassium	mg/l	170	247	122	72	111	77	82	111
Magnesium	mg/l	70	97	47	38	77	42	41	55
Copper	mg/kg	23	29.9	18.5	16.2	20.5	17.7	20.4	23.9
Zinc	mg/kg	77.4	104	64.9	57.6	64.5	54.2	63.2	85.7
Nickel	mg/kg	37.6	38.7	29.7	26.1	32.4	31.1	34	34.5
Cadmium	mg/kg	0.52	0.65	0.37	0.32	0.47	0.48	0.61	0.7
Lead	mg/kg	29.6	39.2	21.2	16.1	26	21.1	23.8	25.5
Chromium	mg/kg	21.6	56.3	37.8	31.3	40.8	32.9	37.5	42.9
Mercury	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Molybdenum	mg/kg	<1	<1	<1	<1	<1	<1	<1	<1
Selenium	mg/kg	3.69	2.81	1.96	1.55	1.95	1.62	1.64	1.56
Arsenic	mg/kg	15.4	26	17.7	23.9	19.3	12.8	18	39.7
Fluoride	mg/kg	68.4	3.3	3.8	5.1	4.2	5.7	4	3.9
Conductivity	uS/cm	2248	2147	2090	2144	2169	2186	2177	2132
Organic Matter	% w/w	4.6	6.8	3.3	2.5	4.9	4.6	5.2	3.8
Total Nitrogen	% w/w	0.127	0.219	0.097	0.071	0.155	0.157	0.184	0.116
Total phosphorus	mg/kg	999	1435	902	815	891	761	851	1289
Total Potassium	mg/kg	1778	2371	1623	1435	1761	1513	1786	1882
Total Magnesium	mg/kg	2434	3277	2168	1944	2311	1996	2219	2367
Total Calcium	mg/kg	39913	82839	91670	74280	62983	71156	71128	62089
Stotal Sodium	mg/kg	174	230	173	147	175	152	175	182
Total Carbon	% w/w	2.71	4.34	3.6	3.28	3.93	4.06	4.36	3.11
Total Sulphur	mg/kg	2003	2044	1161	562	1633	1981	2429	1354

All lab results have been screened against the following criteria:

Suitable 4 Use Levels (S4ULs) – Human health screening criteria produced using the CLEA model, used to assess the risk posed to human health by the deposited sediment. These values determine the suitability of materials kept as bank-side
Environment Agency Ecological Soils Screening Values (SSVs) – Produced by the EA in 2017, the SSVs are used for screening waste and waste derived materials to be used as soil improvers on agricultural land. The values assess the hazard posed
Sewage Sludge on Farmland – Potentially Toxic Elements (PTEs) – the sediment has also been screened using the same values which are applied to sewage sludge spreading on agricultural land.

Exceedance of Suitable 4 Use Levels (S4ULs) - Commercial

Exceedance of Environment Agency Ecological Soils Screening Values (SSVs)

Exceedance of potentially Toxic Elements (PTE) - Sewage sludge on farmland

Broadwater Lake 9	Broadwater Lake 10	Broadwater Lake 11	Broadwater Lake 12	Broadwater Lake 13	Broadwater Lake 14	Broadwater Lake 15	Broadwater Lake 16	Broadwater Lake 17	
8	7.9	7.8	7.9	7.8	7.8	7.8	7.9	7.8	7.8
16.4	41.6	12.4	10.6	18.2	22.6	18.2	18.4	19	
86	136	64	106	147	173	108	125	140	
46	52	33	45	53	72	46	47	61	
20.7	24.8	26.5	30.3	30.1	33.1	20.4	22.3	23.4	
60.7	95.3	57.5	55.9	80.7	89.9	59.3	59.6	69	
26.5	37.5	25.6	22.8	38.6	39.2	27	27.4	30.6	
0.47	0.51	0.49	0.42	0.72	0.73	0.48	0.49	0.61	
20.4	26.6	52.9	71.6	45.2	56.6	31.4	31.6	30.9	
35.5	56.4	28.4	28	52.1	55.2	42	37	45.2	
<0.2	<0.2	0.37	0.52	0.27	0.36	<0.2	0.21	<0.2	
<1	<1	<1	<1	<1	<1	<1	<1	<1	
1.56	1.98	1.84	1.59	2.47	2.63	1.91	2.15	2.22	
18.8	26.4	17.9	11.6	24.8	26.6	19.1	20.3	21.6	
69.8	5.3	49.3	56.5	3	3	9.2	3.2	3	
2173	2241	2183	2167	2265	2295	2248	2275	2270	
5.8	4.1	8.6	7.9	8.4	10.3	6.8	8.4	8.6	
0.186	0.144	0.295	0.304	0.311	0.359	0.296	0.382	0.366	
753	1499	730	573	1252	1355	921	869	983	
1606	2521	1120	1138	1913	2214	1407	1529	1787	
2148	3263	1636	2016	2451	2679	1720	1974	2456	
34813	50962	35370	29251	65755	66043	46636	72259	60733	
156	174	129	143	218	227	154	215	192	
3.53	2.75	4.82	4.27	5.8	6.23	4.2	6.47	5.93	
1344	2367	2056	1121	2546	3445	2607	3895	3561	

retention. 'Commercial' values have been selected as they provide the most conservative screening criteria.

sed by 19 substances to soil fauna, flora and ecosystems. These values asses the suitability of the materials for agricultural spreading, taking into account background concentrations which have been sourced from the NSIV survey.

Broadwater Lake 18	Broadwater Lake 19	Broadwater Lake 20
7.7	7.8	7.8
15.4	21	21
123	143	182
680	78	97
29.7	31.5	33.9
69.1	87.5	101
33.7	40.6	43.3
0.57	0.66	0.69
45	40	43.7
41.4	49.4	58.5
0.31	0.21	0.2
<1	<1	<1
3.08	3.27	3.2
22.1	28.1	30.4
2.5	2.4	2.5
2339	2267	2328
14.4	12	10
0.602	0.488	0.377
840	1074	1222
1791	2192	2590
2462	3071	3520
70175	70782	60303
238	228	265
10.3	7.82	5.74
5405	3159	1756

ANALYTICAL REPORT															
Report Number GREEN TREE HOUSE Date Reported Project Reference Order Number		77341-25 UB9 6AH 17-MAR-2025 SEDMIENT BROADWATER LAKE 1437		W492 JOHNS ASSOCIATES LTD 11 ST MARGARETS STREET BRADFORD ON AVON BA15 1DA		Client BROADWATER LAKE Date Received					06-FEB-2025				
Laboratory Reference		SLUR162208	SLUR162209	SLUR162210	SLUR162211	SLUR162212	SLUR162213	SLUR162214	SLUR162215	SLUR162216	SLUR162217	SLUR162218	SLUR162219	SLUR162220	SLUR162221
Sample Reference		SITE 1	SITE 2	SITE 3	SITE 4	SITE 5	SITE 6	SITE 7	SITE 8	SITE 9	SITE 10	SITE 11	SITE 12	SITE 13	SITE 14
Determinand	Unit	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT	SEDMIENT
Oven Dry Solids	%	15.9	10.6	7.47	22.7	15.8	25.0	4.40	19.4	27.3	40.8	17.6	34.7	29.5	15.1
Asbestos Screen		None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None Detected	None detected	None detected	None detected	None detected
Hexavalent Chromium	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Total PAH	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
TPH [C5-C35]	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C5-C6	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C6-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aliphatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C5-C7	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C7-C8	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C8-C10	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C10-C12	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C12-C16	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C16-C21	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Aromatic TPH C21-C35	mg/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Conductivity 1:6	uS/cm	140	179	140	162	164	191	161	166	162	169	181.0	163.0	161.0	173.0
Total Kjeldahl Nitrogen	% w/w	0.12	0.13	0.12	0.13	0.14	0.13	0.12	0.13	0.11	0.11	0.1	0.1	0.1	0.1
Nitrate Nitrogen	mg/kg	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Ammonium Nitrogen	mg/kg	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25
Total Phosphorus (P)	mg/kg	147	132	139	140	130	182	133	91.7	146	175	145.0	128.0	66.3	154.0
Total Potassium (K)	mg/kg	491	450	412	431	366	963	339	221	399	415	272.0	254.0	174.0	376.0
Total Magnesium (Mg)	mg/kg	638	579	527	551	421	1170	419	263	468	508	383	345	198	514
Total Copper (Cu)	mg/kg	8.33	7.65	5.59	5.53	4.57	1.13	2.86	2.59	4.49	4.67	2.99	2.81	2.06	4.76
Total Zinc (Zn)	mg/kg	22.4	20.7	20.6	20.9	16.7	7.73	9.50	9.28	16.9	18.3	11.1	10.2	7.51	16.8
Total Sulphur (S)	mg/kg	1714	1559	1738	1897	1303	1420	1199	939	934	1087	1196	1166	523	1841
Total Calcium (Ca)	mg/kg	22702	20821	30855	33391	22383	42804	32918	21402	19825	27895	47681	41641	12062	46186
Total Molybdenum (Mo)	mg/kg	0.69	0.63	0.19	0.22	0.16	0.12	0.10	0.08	0.12	0.12	0.10	0.11	<0.05	0.17
Total Lead (Pb)	mg/kg	11.6	10.4	9.96	8.29	6.45	7.14	6.21	3.63	6.84	6.89	3.96	4.00	3.26	6.30
Total Cadmium (Cd)	mg/kg	0.12	0.12	0.13	0.14	0.11	0.16	0.09	0.07	0.11	0.11	0.07	0.07	0.05	0.12
Total Mercury (Hg)	mg/kg	<0.05	<0.05	<0.05	<0.05	<0.05	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Total Nickel (Ni)	mg/kg	7.72	6.93	6.44	6.52	6.02	12.6	5.72	3.32	6.08	6.88	4.62	3.95	2.92	6.57
Total Chromium (Cr)	mg/kg	9.85	8.88	8.29	8.18	6.76	18.3	7.16	4.01	8.07	8.80	5.43	4.81	2.92	7.51
Total Sodium (Na)	mg/kg	69.0	66.5	68.0	71.7	64.6	86.6	64.1	59.0	64.0	67.4	70.3	66.7	51.6	71.0
pH 1:6 [Fresh]		8.16	7.99	8.15	8.11	8.07	7.82	7.96	8.02	8.09	8.03	7.85	8.00	7.88	7.93
Organic Matter LOI	% w/w	1.64	1.52	0.92	2.69	2.39	2.65	0.53	2.31	2.87	2.23	1.58	2.46	2.64	1.84
Fluoride [100:1 H2SO4 Soluble]	mg/kg	22.9	12.7	22.4	17.5	16.1	18.9	17.0	13.8	23.3	25.9	15.3	15.0	<10	16.9
Total Arsenic (As)	mg/kg	4.18	3.78	4.11	3.98	2.92	4.13	2.96	1.80	2.35	2.73	3.23	2.74	1.25	4.31
Total Selenium (Se)	mg/kg	0.56	0.51	0.53	0.57	0.52	0.63	0.74	0.37	0.55	0.60	0.52	0.42	0.34	0.69
Naphthalene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Acenaphthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluorene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Phenanthrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[a]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Chrysene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[b]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[k]fluoranthene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[a]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Indeno[1,2,3-cd]pyrene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Dibenzo[a,h]anthracene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable
Benzo[g,h,i]perylene	ug/l	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable	Unsuitable

