

Report generated: 16/07/2020

PTAL (cell size: 100m)

Day of Week	M-F
Time Period	AM Peak
Walk Speed	4.8 kph
Bus Node Max. Walk Access Time (mins)	8
Bus ReliabilityFactor	2.0
LU Station Max. Walk Access Time (mins)	12
LU ReliabilityFactor	0.75
National Rail Station Max. Walk Access Time (mins)	12
National Rail ReliabilityFactor	0.75

Calculation data

Mode	Stop	Route	Distance (metres)	Frequency(vph)	Walk Time (mins)	SWT (mins)	TAT (mins)	EDF	Weight	AI
Bus	HAYES COLDHARBOUR LANE	E6	234.63	6	2.93	7	9.93	3.02	0.5	1.51
Bus	HAYES COLDHARBOUR LANE	90	234.63	6	2.93	7	9.93	3.02	0.5	1.51
Bus	HAYES COLDHARBOUR LANE	140	234.63	8.5	2.93	5.53	8.46	3.55	1	3.55
Bus	HAYES BOTWELL LANE	U5	364.23	5	4.55	8	12.55	2.39	0.5	1.19
Bus	HAYES BOTWELL LANE	H98	364.23	7.5	4.55	6	10.55	2.84	0.5	1.42
Bus	HAYES BOTWELL LANE	195	364.23	5	4.55	8	12.55	2.39	0.5	1.19
Bus	HAYES BOTWELL LANE	U4	364.23	7.5	4.55	6	10.55	2.84	0.5	1.42
Rail	Hayes & Harlington	'PADTON-HTRWAPT 2T18'	829.64	2	10.37	15.75	26.12	1.15	1	1.15
Rail	Hayes & Harlington	'HTRWAPT-PADTON 2Y14'	829.64	2	10.37	15.75	26.12	1.15	0.5	0.57
Rail	Hayes & Harlington	'PADTON-OXFD 2N14'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'PADTON-OXFD 2N16'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'PADTON-OXFD 2N18'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'PADTON-OXFD 2N22'	829.64	0.67	10.37	45.53	55.9	0.54	0.5	0.27
Rail	Hayes & Harlington	'PADTON-OXFD 2N24'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'RDNGSTN-PADTON 2P09'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'OXFD-PADTON 2P11'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'RDNGSTN-PADTON 2P12'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'RDNGSTN-PADTON 2P14'	829.64	1.33	10.37	23.31	33.68	0.89	0.5	0.45
Rail	Hayes & Harlington	'RDNGSTN-PADTON 2P17'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'OXFD-PADTON 2P18'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'BNBR-PADTON 2P20'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'SLOUGH-PADTON 2P25'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'SLOUGH-PADTON 2P32'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'PADTON-RDNGSTN 2R13'	829.64	1.67	10.37	18.71	29.08	1.03	0.5	0.52
Rail	Hayes & Harlington	'PADTON-RDNGSTN 2R19'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15
Rail	Hayes & Harlington	'PADTON-TWYFORD 2R21'	829.64	0.33	10.37	91.66	102.03	0.29	0.5	0.15

Total Grid Cell AI: 16.86