

Daikin Stylish RXA50B R32 Outdoor Unit 5.0KW



Product details

Promising impressive resistance to even the most severe weather conditions, the Daikin Stylish outdoor air conditioning unit features a blue fin anti-corrosion treated heat exchanger for long lasting use. Simple to install on a roof or terrace or against a wall, this hardwearing unit offers hassle-free installation and a smart, unobtrusive finish.

Product features

- Range of design options available to suit interior
- Air conditioning options for each building type
- Blue fin corrosion-resistant heat exchanger
- Neat, sturdy design
- Easily fitted on roof or terrace or placed against an outside wall

Technical specifications

Brand	Daikin
Range	Stylish
Weight	50 kg

Phase	1
Refrigerant Suitability	R32
Hazardous	N
Depth (mm)	373
Pipe Size Diameter - Gas	12.7 mm
Pipe Size Diameter - Liquid	6.4 mm
Supplier Product Code	RXA50B
Type	AC Unit
Height	734 mm
Width	870 mm
Model Number	RXA50B

Daikin Air Conditioning RXM25A R32 Outdoor Unit 2.5kW



Specification

Air Flow Rate (Cooling) @ High 39.1 m³/min

Brand Daikin

Colour Ivory white

Compatible with various Daikin Air Conditioning Indoor Units. Compatible with Perfera FTXM-A air conditioning indoor units. Contact Ocean air for more details.

COP*5

EER*5.2

Energy Rating (Cooling)*A+++

Fitting Requirements Must be installed by an F-GAS Certified Installer. We require evidence of this before shipment. If you have any questions regarding these regulations, please contact us.

Gas Pipe Size 9.5mm

Liquid Pipe Size 6.4mm

Manufacturer Guarantee/ Manufacturer Warranty 3 Year Warranty

Manufacturer's Model No RXM25A

Max. Pipe Run 20m

Nom. Cooling Capacity 2.5kW

Nom. Heating Capacity 2.8kW

No. of Indoor Units 1

Operating Temperature Range (Cooling)-10°CDB to 50°CDB

Operating Temperature Range (Heating)-20°CDB to 24°CDB

Phrase Single Phase

Power Rating (Watts kW)2.5kW

Power Source220-240V, 50Hz

Product Contents Installation manual x 1; Drain joint x 1; Refrigerant charge label x 1; Multilingual fluorinated greenhouse gases labels x 1; General safety precautions x 1; LOT10 Energy Label x 1; Drain cap x 3; Drain plug x 1

Product Depth367mm

Product Height610mm

Product Width923mm

Range Description Daikin Air Conditioning RXM-A

Refrigerant TypeR32

Remote Controller Included No Controller Supplied. Please Order Separately.

SCOP*5.2

SEER*9.47

Sound Pressure Level46 dBA

System Suitability Suitable for Domestic Heating Systems.

Type Single Split Outdoor Unit

* Efficiency Data Notes All efficiency data is calculated based on pairing with the unit listed in the "Compatible with" section.