



PROPOSED SITE PLANS


THE NEW CAR-PARKING SPACES TO BE PERMEABLE BLOCK PAVING HELD IN BRICK BORDERS TO DE-MARK PARKING SPACES FOR EACH DESIGNATED UNIT. PROVIDE 2-DESIGNATED SPACES FOR CURRENT RESIDENTIAL DWELLING (3-BEDROOM HOUSE) REF: 247 West End Road WHILST PROPOSED NEW DWELLING TO BE DEVELOPED AT AMENITY AREAS ADJACENT TO CURRENT DWELLING TO FORM 247-A West End Road



ELEVATION TO THE NEW TIMBER FENCE BOUNDARY CLOSURE ALONG ELEVATIONS FACING RESIDENTIAL DWELLINGS, 1800mm HIGH WITH EACH PANEL 2000mm LONG & SUPPORTED BY INTERMEDIATE TIMBER POSTS (100mmX100mm) FIXED TO NEW 300mm² MASS CONCRETE BASES

Medium Sized Car

Overall Length	4.319m
Overall Width	1.686m
Overall Body Height	1.466m
Min Body Ground Clearance	0.228m
Max Track Width	1.591m
Lock to Lock Time	4.00 sec
Kerb to Lerb Turning Radius	5.042m



#3: PLANTING NEW DECIDUOUS LAVENDE (HIDCOTE)




#2: PLANTING NEW EVERGREEN HEBE (SEQUOIA SEMPERVIRENS)




#1: PLANTING NEW FLOWERING HOWTHORN TREE IN ROOTS BARRIER



#7: PLANTING NEW EVERGREEN HEBE (AUTUMN GLORY)




#6: PLANTING NEW DECIDUOUS CISTUS (SILVER PINK)



#5: PLANTING NEW EVERGREEN HEBE (PINGUIFOLIA PAGEI)



#4: FLOWER PLANTS (ROSES & LAVENDER)



40 WISE LANE
MILL HILL
LONDON
NW7 2RE
email:
info@homesdesignltd.co.uk
www.homesdesignltd.co.uk

title		PROPOSED PARKING & AMENITY PLANS	
project		247 West End Road Ruislip HA4 6QR	
drawing no	ABC391 / 2006	rev:	scale 1:200 @ A3
drawn by	R. L	contract no.	ABC391