GENERAL NOTES

-ALL DIMENSIONS IN MILLIMETRES
-DO NOT SCALE OFF THIS DRAWING
-ALL DIMENSIONS TO BE CHECKED ON SITE

(C)JAMES BLAKE ASSOCIATES LTD 2023

KEY

- FOOTPATH CONCRETE SETTPAVING, 140 x 210 x 60mm (80mm for vehicular areas) Type such as 'Alpha Antique Tumbled Block Paving' from Brett; Colour such as 'Silver Haze', or similar and approved.
- CONCRETE SETT EDGING 140mm wide, laid as double staggered string using blocks, 140mm x140mm, (60mm depth for pedestrian areas, 80mm depth for vehicular areas) type 'Alpha Antique Tumbled Block' from Brett to match adjacent surfaces or other similar and approved. Laid over 100mm cement mortar bed, 1:3 mix, haunched over 250 x 150mm C20P mix insitu concrete strip foundation.
- PORCELAIN SLAB PAVING; Type such as 'Eclipse' by 'Brett' 600 x 600 x 35mm, Colour such as 'Lunar', or similar and approved. To be dry laid in stack bond, over 20mm mortar, over 150mm depth of suitable granular fill, over firmed sub-grade, all to falls and crossfalls, minimum 1:70.
- ROADWAYS AND FOOTPATHS to be Bitumen Macadam with 6mm gauge aggregate wearing course to be laid over 20mm gauge aggregate base course, all laid over base course of hardcore, all depths to Engineer's specification, laid over firmed sub-grade and geotextile - Terram 1000, all to falls and crossfalls, minimum 1:70 and all to Highway's Authority approval.
- Hoggin path with pressure treated timber edge, over compacted mot & subgrade, over terram 1000 geotextile or similar and approved. Sawn pressure treated softwood gravel board 38mm x 150mm attached with galvanised nails to 50mm at 1.5m centres or closer as required at junctions or curves. 50mm x 600mm long softwood stakes for sharp curves, gravel board to be kerfed with cuts sawn vertically along the back side.
- natural compacted ground path with treated timber edge to mark route. for sharp corners timber to be kerfed with vertical slits in back of timber.Sawn pressure treated softwood gravel board 38mm x 150mm attached with galvanised nails to 50mm at 1.5m centres or closer as required at junctions or curves. 50mm x 600mm long softwood stakes for sharp curves, gravel board to be kerfed with cuts sawn vertically along the back side.
- PRECAST CONCRETE BLOCK EDGING, 50 x 150 x 914mm, flat topped and laid flush with paving. Edging to be bedded into C20 P insitu concrete strip foundation 350 x 300mm, haunched.
- DROPPED KERB, 25mm upstand or flush TO BS7263, to engineer's specification.
- Reinforced gravel parking bays and road ways. washed, rounded, buff coloured gravel, 20mm gauge, 40mm depth, finished level 15mm below adjacent surfaces. Gravel to be reinforced using 'Cellweb' with pressure treated timber edge available from Geosyn tel:01455 617 139 or similar and approved all laid over base course of hardcore, all depths to Engineer's specification, laid over firmed sub-grade and geotextile - Terram 1000.
- SECTION OF TIMBER BOARD WALK INCLUDING HAND RAILS

REV.	DATE	INITIALS	DETAILS

CLIENT	DWG. TITLE
Corner Homes	Proposed Hard Landscape
SITE: Harefield Grove	
PURPOSE OF ISSUE: Planning	

DRG BY	CHECKED	AUT/YD	SCALE	DATE	DWG NO.	REV.
DCG	JBA	JBA	1:250@A1	SEPT 2023	JBA 20 027 04	-

JAMES BLAKE ASSOCIATES
Head Office: 34-52 Out Westgate, Bury St Edmunds, Suffolk, IP33 3PA Tel: (01284) 335797
jamesblake@jba-landmarc.com www.jba-landmarc.com
LANDSCAPE ARCHITECTURE o ARBORICULTURE o ECOLOGY

Daniel Gilthon - 15/10/2023 - K:\JBA\Client Projects\Corner Homes\20 027 Harefield Grove\Drawings\JBA\Master\JBA 20-027 - Detailed Hard Landscape Proposal.dwg