


Plain



The authentic cross camber design of the Marley Eternit concrete plain tile gives it a look to match its outstanding versatility.

Colour availability

Key (F) Fine sanded finish (G) Granular finish (S) Smooth finish




Mosborough Red (S)




Natural Red (F)



Old English Dark Red (S)




Dark Red (G)



Smooth Brown (S)




Antique Brown (G)



Smooth Grey (S)



Greystone (G)



Anthracite (S)

Technical data		
Size of tile	267mm x 168mm	
Minimum pitch*	35°	
Maximum pitch	90°	
Minimum headlap	65mm (roof)	37,5mm (vertical)
Maximum gauge	100mm (roof)	115mm (vertical)
Tile thickness	12mm (nominal)	
Cover width	168mm (nominal)	
Covering capacity (net)	60 tiles/m² at 100mm gauge (roof)	53 tiles/m² at 115mm gauge (vertical)
Weight of tiling (approx.)	73,8kg/m² (0,72 kN/m²) at 100mm gauge (roof)	58kg/m² (0,57 kN/m²) at 115mm gauge (vertical)
Battens required (net)	10 lin.m/m² at 100mm gauge (roof)	8,7 lin.m/m² at 115mm gauge (vertical)
Batten size recommended	38 x 25mm for rafters/supports not exceeding 600mm centres (fixed to BS 5534)	
Tile nails	38mm x 2,65mm	
Authority	BS EN 490	

* The minimum recommended pitch and lap may be influenced by special circumstances, please contact the Technical Advisory Service.

Sustainability
✓ A+ rated in the BRE Green Guide (based on generic rating for UK produced concrete plain tiles Element Refs: 812410017, 812410050, 812410064) ✓ BES 6001 (Responsible Sourcing) certified ✓ Independent carbon footprint certification

Product information
Tile camber Single camber Compatible with clay feature tiles For advice on the use of Feature tiles in main roof areas contact the Technical Advisory Service. † Made to order Club† Bullnose†