

3.4 Tilt & Turn Vents (UJ)

Constructed from high impact PVCU with a mainframe depth of 70mm, and a sightline of 129mm Anglian's tilt & turn vents offer a superb alternative to the standard opening options. They are constructed from high impact PVCU with a mainframe depth of 70mm and a visible sightline of 77mm on our UJ design (fixed panes). Similar to casement windows all frame and vent sections are mitred and welded at the joints.

On White Knight, White Woodgrain and all Dual products the excess residue from the welding process is removed to leave a feature groove finish. On Dark Woodgrain and Golden Oak fully foiled products the residue both internally and externally is removed by knifing.

Tilt & Turn windows have a dual function; they can tilt inwards and turn inwards. Tilt and turn windows are available with many of the features of the casement vents, including a choice of frame colour options of White Knight, Golden/Dual Oak, Dark/Dual Woodgrain, White Woodgrain, Dual Anthracite Grey, Dual Sage Green and Dual Cream and have similar design features such as internal glazing and Warm Edge spacer bar.

Full height Tilt & Turn windows CAN NOT be used a primary door function.

Please refer to the Window & Door Sales Technical Guide for all glazing/colour exclusions, Window Energy Ratings and parameters for all Tilt & Turn windows.

Maximising ventilation whilst maintaining peace of mind.

- Offers excellent ventilation potential whilst maintaining a high level of security and safety.
- Smooth operation of components and hardware.
- High-tech design.
- Manufactured to high levels of quality control.
- Made in Anglian's state of the art production facilities.



Turned.



Tilted.