



MELISI SHOP FRONT IS NOT ORIGINAL



MELISI SHOP FRONT IS NOT ORIGINAL



RUISLIP HIGH STREET CIRCA 1940-1955
IMAGE FOR REFERENCE ONLY



IMAGE FOR REFERENCE ONLY



1.3.9_MELISI

20/01/2022

DESIGNED *by* GOOD PEOPLE

hi@designedbygoodpeople.com 0207 193 0098
Contact: Lee Newham

SHOP FRONT: New Melisi brand blue aluminium shop front with central hinged inward opening door to front of shop as shown.

Long Stainless steel bar handle to door. Glass area to line up with stallriser.

New side windows to match front with stallriser and tiles (no access doors).

Setting out point (SOP) to corner.

STALLRISER: Part Tiled stallriser to match the Northwood branch of Melisi. Tiles from Topps Tiles (Batik Patchwork Blue Tile), 2 tiles depth. Area under this to be painted in blue to match sign. A suitable waterproof board for the stallriser should be used (such as waterproof medite). There should be a to same depth as tiles.


Window mullions covered by panels above windows and on stallriser.

Vinyls to windows (max height 270mm) and in panel below sign.

SIGNAGE: Existing signage and lighting to remain.

Paint pilasters to match Melisi brand blue.

COLOURS TO MATCH TO:



WHITE



BRAND GREEN
TBC



BRAND
RED
TBC



BRAND
DK BLUE
TBC

Option for shop frame to be white.

RAL7047

PLEASE NOTE:
CONTRACTORS SHOULD TAKE THEIR OWN MEASUREMENTS AND ADAPT ARTWORK WITHOUT STRETCHING OR ALTERING THE TYPE.

TILES AND OVERALL DESIGN MATCH OTHER BRANCH IN NORTHWOOD.

THE STALLRISER IS DESIGNED TO BE OF SIMILAR HEIGHT TO OTHERS IN THE HIGH STREET AND TO MORE CLOSELY MATCH THE ORIGINAL AS SEEN IN OLD PHOTOS.

SCALE: 1:40

0 1m