

Topping Engineers Ltd

Windsor House
Cornwall Road
Harrogate HG1 2PW

Date 15/01/2020
File STORAGE CHECK 15.1.20.SRCX

Micro Drainage

Willow Tree, Hillingdon
Storage Check

Designed by TM
Checked by

Source Control 2017.1.2

Page 2



Summary of Results for 100 year Return Period (+30%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Outflow (l/s)	Max Volume (m³)	Status
30 min Winter	8.717	0.717	0.0	9.0	9.0	20.4	0 K
60 min Winter	8.691	0.691	0.0	9.0	9.0	19.7	0 K
120 min Winter	8.495	0.495	0.0	9.0	9.0	14.1	0 K
180 min Winter	8.302	0.302	0.0	9.0	9.0	8.6	0 K
240 min Winter	8.185	0.185	0.0	8.8	8.8	5.3	0 K
360 min Winter	8.127	0.127	0.0	7.0	7.0	3.6	0 K
480 min Winter	8.107	0.107	0.0	5.7	5.7	3.1	0 K
600 min Winter	8.095	0.095	0.0	4.7	4.7	2.7	0 K
720 min Winter	8.087	0.087	0.0	4.1	4.1	2.5	0 K
960 min Winter	8.076	0.076	0.0	3.3	3.3	2.2	0 K
1440 min Winter	8.063	0.063	0.0	2.4	2.4	1.8	0 K
2160 min Winter	8.053	0.053	0.0	1.7	1.7	1.5	0 K
2880 min Winter	8.046	0.046	0.0	1.3	1.3	1.3	0 K
4320 min Winter	8.039	0.039	0.0	1.0	1.0	1.1	0 K
5760 min Winter	8.034	0.034	0.0	0.8	0.8	1.0	0 K
7200 min Winter	8.031	0.031	0.0	0.6	0.6	0.9	0 K
8640 min Winter	8.029	0.029	0.0	0.5	0.5	0.8	0 K
10080 min Winter	8.027	0.027	0.0	0.5	0.5	0.8	0 K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
30 min Winter	86.146	0.0	32.5	32
60 min Winter	53.473	0.0	40.4	50
120 min Winter	32.057	0.0	48.5	86
180 min Winter	23.449	0.0	53.2	114
240 min Winter	18.674	0.0	56.5	138
360 min Winter	13.521	0.0	61.3	192
480 min Winter	10.749	0.0	65.0	252
600 min Winter	8.991	0.0	68.0	312
720 min Winter	7.767	0.0	70.4	370
960 min Winter	6.160	0.0	74.5	494
1440 min Winter	4.438	0.0	80.5	742
2160 min Winter	3.192	0.0	86.9	1100
2880 min Winter	2.524	0.0	91.6	1472
4320 min Winter	1.811	0.0	98.5	2204
5760 min Winter	1.429	0.0	103.7	2992
7200 min Winter	1.189	0.0	107.9	3632
8640 min Winter	1.023	0.0	111.3	4408
10080 min Winter	0.900	0.0	114.3	5144

©1982-2017 XP Solutions

Topping Engineers Ltd		Page 4
Windsor House Cornwall Road Harrogate HG1 2PW	Willow Tree, Hillingdon Storage Check	
Date 15/01/2020	Designed by TM	
File STORAGE CHECK 15.1.20.SRCX	Checked by	
Micro Drainage	Source Control 2017.1.2	

Model Details

Storage is Online Cover Level (m) 10.000

Cellular Storage Structure

Invert Level (m) 8.000 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	30.0	30.0	0.900	0.0	47.6
0.800	30.0	47.6			

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0142-9000-0800-9000
Design Head (m) 0.800
Design Flow (l/s) 9.0
Flush-Flo™ Calculated
Objective Minimise upstream storage
Application Surface
Sump Available Yes
Diameter (mm) 142
Invert Level (m) 8.000
Minimum Outlet Pipe Diameter (mm) 225
Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.800	9.0
Flush-Flo™	0.257	9.0
Kick-Flo®	0.562	7.6
Mean Flow over Head Range	-	7.6

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.1	1.200	10.9	3.000	16.8	7.000	25.3
0.200	8.9	1.400	11.7	3.500	18.1	7.500	26.1
0.300	8.9	1.600	12.5	4.000	19.3	8.000	26.9
0.400	8.7	1.800	13.2	4.500	20.4	8.500	27.7
0.500	8.3	2.000	13.9	5.000	21.5	9.000	28.5
0.600	7.9	2.200	14.5	5.500	22.5	9.500	29.3
0.800	9.0	2.400	15.1	6.000	23.5		
1.000	10.0	2.600	15.7	6.500	24.4		