























Our framing timber is of QPA visual grade, this is the best structural grade available.

We include a 15mm sq groove for electrical routing if you are having oak common rafters.

It is recommended that your frame is sandblasted after it has been raised, once the frame is dry and before any fragile materials are fitted.

Chamfers to tie beams, floor beams & purlins are included.

All our 200 x 75mm braces are from partially air dried stock.

Rebate for joinery if applicable.

All our framing oak is European and usually from one mill in Normandy. They source all their trees from within 100 miles of the mill.

All free standing posts are located with heavy duty angle brackets.

We have 'typical details' for the wall, roof & base details, which can be issued once you are onboard with us.

Most mortise & tenons are fixed with 19mm tapered hand made pegs. More structural connections will have one or two 25mm tapered handmade pegs.