

CLOSED CELL INSULATION SHOULD BE USED FOR PIPES WHICH ARE BELOW THE PREDICTED FLOOD LEVEL

ELECTRICAL SOCKETS SHOULD BE INSTALLED ABOVE
FLOOD LEVEL FOR GROUND FLOOR ,
ELECTRIC RING MAINS SHOULD BE INSTALLED AT FIRST
FLOOR LEVEL WITH DROPS TO GROUND FLOOR SOCKETS
AND SWITCHES

WIRING FOR TELEPHONE, TV, INTERNET AND OTHER SERVICES SHOULD BE PROTECTED BY SUITABLE INSULATION IN THE DISTRIBUTION DUCTS

GROUND FLOOR FINISH TO BE TILED ON CONCRETE
SLAB FLOOR LAID ON DAMP PROOF MEMBRANE LAPPED TO
D.P.C LEVEL IN WALLS

THEREFORE, LOWER THE ENTIRE REAR GARDEN
BY 55MM

