

LOCKER & RILEY

		IE Jamshid Frough of Frough Ltd.					
Date:	EN8425_Q01 20/02/ 2026.	Plaster Consultant inspections of the historic fibrous plaster art deco Egyptian door pediment conservation works actors left & right for compliance with Technical Standard For Places of Entertainment-Planned Conservation works required-	Q01		Author	GBuckley	
Item	Location	Description	Ref	Qty	Per	Rate	Total
		Estimate for remediation works detailed in Locker & Riley historic fibrous plaster report dated 19/12/25					
1.00	Decorative fibrous plaster pediments	Provisional Sum-Erection of 1no working mobile tower platforms actors left and actors right with specialist adaptations for change in levels of flooring and staircase.Full compliance with WAHR-2005 for HSE compliance-Super advanced Pasma compliance-cost allowance for 25% mark up for L&R OHP	scaffolding/ mobile tower				£3,205.13
2.00	Decorative fibrous plaster pediments	Actors Right-Careful remove Greek patera to pediments clean up and refix with suitable dowled connection and plaster bedding.,Form silicone mould from original plaster feature and cast on site to replace broken/missing greek patera.	ABTT plaster Conservation works				£1,307.69
3.00	Decorative fibrous plaster pediments	Actors Left-Careful remove Greek patera to pediments clean up and refix with suitable dowled connection and plaster bedding.,Form silicone mould from original plaster feature and cast on site to replace broken/missing greek patera.	ABTT plaster Conservation works				£1,307.69
4.00	Decorative fibrous plaster pediments	Materials for plaster conservation works and protection	materials				£628.20
		Sub Total					£6,448.71
	Preliminary's						
		L&R RAMS production/cosHH/tool box talks	Health & Safety				£250.00
		Site visit for RAMS,site co-ordination,pre start meeting	Health & Safety				£250.00
		Delivery allowance-£200-Collection Allowance £200	LBC consent compliance with Local Authority				£400.00
		To Collection Excluding VAT					£7,348.71