

03 | DESIGN PROPOSAL

LANDSCAPE STRATEGY - PLAYING FIELD

1:500@A3

A number of strategies are in place surrounding the pavilion proposal to maximise its sustainability an to protect and enhance the existing and proposed foliage in the adjacent landscape. All trees on site are to be retained with the shrubs along the boundary fence to be trimmed back to form a hedge. The ground finish around these trees will be permeable to ensure they maintain appropriate water intake and stay healthy.

To the north of the pavilion root protection measures will be taken in the construction of the strip foundations to insure there is no intrusive or damaging works carried out in the root protection zone of T3 Field Maple (See Arboricultural Impact Assessment Method Statement & Tree Protection Plan included in the submission for more info).

The roof of the pavilion will be bio-solar, constructed to GRO code 2014+ to help increase biodiversity and generate electricity for the pavilion.

