

Textainer - 20ft Standard container



| Ratings              | 20' Standard           |
|----------------------|------------------------|
| Maximum Gross Weight | 30,480 kg (67,200 lb.) |
| Tare Weight          | 2,200 kg ( 4,850 lb.)  |
| Payload              | 28,280 kg (62,350 lb.) |
| External Dimensions  |                        |
| Length               | 6,058 mm (19'-10½")    |
| Width                | 2,438 mm (8'-0")       |
| Height               | 2,591 mm (8'-6")       |
| Internal Dimensions  |                        |
| Length               | 5,900 mm (19'-4¼")     |
| Width                | 2,348 mm (7'-8½")      |
| Height               | 2,385 mm (7'-9 7/8")   |
| Door Opening         |                        |
| Width                | 2,340 mm (7'-8 1/8")   |
| Height               | 2,275 mm (7'-5 5/8")   |