

FOR CONTINUATION SEE BELOW

INSERT
(CONTINUATION FROM BELOW)

ALL DIMENSIONS AND LEVELS
TO BE CHECKED AND
CONFIRMED BY THE ARCHITECT
PRIOR TO CONSTRUCTION.

1. FOR ALL NOTES REFER TO
DETAIL NO. H32519-21

In addition to these notes, reference should be made to the specifications of
work and the relevant standards and standards of work and specifications.
The Contractor is responsible for verifying all site dimensions before
commencing work.
All dimensions are to minimum unless noted otherwise.
The drawings are based on the proposed site plan and the proposed
level of the ground. All dimensions are to the center of the pipe and
all dimensions are to be confirmed by the architect prior to construction.
Levels are in meters unless noted otherwise to Ordnance Survey datum.
The Contractor is responsible for the accuracy of the building which are shown
on the drawings.

NOTES

FOR CONTINUATION
SEE INSERT ABOVE

FOR CONTINUATION SEE DRAWING NO. H32519-21

NOTE: BRICKSETT TYPIC MANHOLE COVERS
SHALL BE Laid WITH THE COVERS
AND FROSTED WITH BRICKMAN ALUMINA

FOUL WATER MANHOLE SCHEDULE					
NO	INVERT COVER LEVEL	HEIGHT LEVEL	DEPTH (M)	NO	COVER TYPE
F1					EXISTING
F2					EXISTING
F3					EXISTING
F4					EXISTING
F5	48.00	48.40	2.00		EXISTING
F6	48.10	48.47	2.00		EXISTING
F7	48.10	48.17	1.00		SEP
F8	48.00	48.30	1.00		SEP
F9	48.00	48.17	1.00		SEP

FOUL WATER MANHOLE SCHEDULE					
NO	INVERT COVER LEVEL	HEIGHT LEVEL	DEPTH (M)	NO	COVER TYPE
F10	48.00	48.22	1.00		SEP
F11	48.00	48.30	1.00		SEP
F12	48.00	48.10	EXISTING		
F13	48.00	48.17	1.00		SEP
F14	48.00	48.30	1.00		SEP
F15	48.00	48.10	1.00		SEP
F16	48.00	48.30	1.00		SEP
F17	48.00	48.30	1.00		SEP
F18	48.00	48.30	1.00		SEP
F19	48.00	48.30	1.00		SEP

STORM WATER MANHOLE SCHEDULE					
NO	INVERT COVER LEVEL	HEIGHT LEVEL	DEPTH (M)	NO	COVER TYPE
S1					EXISTING
S2					EXISTING
S3	48.00	48.10	0.80		SEP
S4	48.00	48.10	1.00		SEP
S5	48.00	48.10	1.00		SEP
S6	48.00	48.10	1.00		SEP
S7	48.00	48.10	1.00		SEP
S8	48.00	48.10	1.00		SEP
S9	48.00	48.10	1.00		SEP
S10	48.00	48.10	1.00		SEP

STORM WATER MANHOLE SCHEDULE					
NO	INVERT COVER LEVEL	HEIGHT LEVEL	DEPTH (M)	NO	COVER TYPE
S11	48.00	48.10	1.00		SEP
S12	48.00	48.10	1.00		SEP
S13	48.00	48.10	1.00		SEP
S14	48.00	48.10	1.00		SEP
S15	48.00	48.10	1.00		SEP
S16	48.00	48.10	1.00		SEP
S17	48.00	48.10	1.00		SEP
S18	48.00	48.10	1.00		SEP
S19	48.00	48.10	1.00		SEP
S20	48.00	48.10	1.00		SEP

E	AMENDED TO ARCHITECT'S COMMENTS	1/11/20	MJB
D	DRAINAGE AMENDMENTS	26/10/20	MJB
C	DRAINAGE AMENDMENTS	5/09/20	MJB
B	MINOR AMENDMENTS	24/02/20	SAL
A	MINOR AMENDMENTS	01/02/20	MJB
O	ORIGINAL ISSUE - PRELIMINARY	27/07/20	MJB
REV	DESCRIPTION	DATE	BY

DIXON
HURST
KEMP

CONSULTING CIVIL &
STRUCTURAL ENGINEERS

50 Portland Road,
East Sussex BN1 8DQ
Tel: 01323 711001
Fax: 01323 711184
Email: info@hdk.co.uk
Web: www.hdk.co.uk

CONTRACT: SACRED HEART
RC. PRIMARY SCHOOL
HERLWYN AVENUE, RUISLIP

DRAINAGE LAYOUT
SHEET 1

DRAWING NO: H32519/20
DATE: 20/05/20
SCALE: 1:50

NO: E
CHECKED: TH
DESIGNED: MJB
APPROVED: MJB