

A fresh look at cycle parking...

Based in Plymouth, BikeAway Ltd has been leading the field as a specialist supplier of vertical stands and lockers since 2001. With all of our products made to order, BikeAway has a cycle storage solution for almost every location.

Lockers

Our vertical cycle lockers are designed to hold 1 bicycle in an upright position. Having installed more than 10,000 lockers in the UK and Ireland, we have built up a wealth of experience to provide units that ideally suit each particular site. BikeAway lockers offer a space saving, secure and user friendly solution to encourage cycling as a realistic form of transport.

This robust locker is particularly suited to urban areas and has been installed in housing estates throughout London for a number of years. They have been so successful that the local authorities return to us time and time again to purchase more.

Space saving

12 BikeAways to fit into just 2 standard car parking spaces.

Security

Of paramount importance, the strength of our lockers is backed up independently by the heavy duty version having passed the attack test required by Standard LPS 1175 as laid down by Secure by Design in conjunction with BRE Global and the Association of Chief Police Officers.

Ease of use

Our unique mounting hoop and ramp allow bikes to be stored safely and securely in seconds, with no metal to metal contact.



Flexibility

There is no limit to the number in a cluster. The overall structure derives strength from the way the units are attached together. These lockers are built on site by our team of fitters and can be installed on any hard standing. The adjustable legs (a feature unique to BikeAway) allow our lockers to be installed on most uneven and sloping surfaces, yet still remain vertical and true to produce a smart finish every time.

Technical information

BikeAways are constructed from 1.5mm thick galvanised steel. The doors are made from 1.6mm or 2mm thick galvanised steel depending on specification. End panels and doors are polyester paint finished. All other surfaces have galvanised finish unless otherwise specified.

Dimensions

680mm Wide
1150mm Deep
1900-2000mm high (legs are adjustable)

Locker management service

BikeAway manages over 1500 lockers, many on housing estates throughout London. Not only do we deal with the administration involved, we also maintain the lockers in full working order. This makes any cycle parking initiative fully sustainable.

