

Tree Number	Botanical Name (Common name)	Age	Dia (mm)	Stems	Height (crown height)	Ult ht (m)	N	E	S	W	Cond	Life Exp	BS Cat	RPR (m)	RPA (m <sup>2</sup> )	Comments	Recommendations
T1	<i>Fraxinus excelsior</i> (Ash)	M	700	1	22(5)	25	4.5	4.5	4.5	4	Good	40+	B2	8.4	221.7	Provides a high level of visual amenity. Prominent tree. Offsite tree. Reasonable form and condition. Stem data estimated as offsite. Ivy on tree. Unable to inspect stem due to ivy. Historically crown reduced with good regrowth. Growing very close to boundary fence. Triple stemmed at 2.5m. Ivy has been severed in past and dead ivy stems remain. Small branch pruning wounds with pockets of decay. Average 3m regrowth.	
T3	<i>Ilex aquifolium</i> (Holly)	SM	150	1	6(2)	12	3	3	3	3	Fair	40+	C1	1.8	10.18	Offsite tree. Reasonable form and condition. Plotted by eye as not on topo. Stem data estimated as offsite. Low bud/leaf density.	
T4	Prunus (Prunus species)	SM	300	1	8(4)	12	4	3	3	3	Fair	20+	C2	3.6	40.72	Offsite tree. Reasonable form and condition. Stem data estimated as offsite. Topped at 7m and regrown. Large branch removal in the past which is sprouting.	
G7	<i>Chamaecyparis lawsoniana</i> (Lawson Cypress)	SM	200	1	5(0)	25	2	2	2	2	Fair	20+	C2	2.4	18.1	Offsite tree. Forms a partial filtered screen. Informal hedge observed from site. Some dieback due to shading of the cherry. Denser at southern end.	

Tree Number	Botanical Name (Common name)	Age	Dia (mm)	Stems	Height (crown height)	Ult ht (m)	N	E	S	W	Cond	Life Exp	BS Cat	RPR (m)	RPA (m <sup>2</sup> )	Comments	Recommendations
T8	X Cupressocyparis leylandii (Leyland Cypress)	EM	450	1	14(2.5)	28	5	5	5	5	Good	40+	B2	5.4	91.62	Offsite tree. Stem data estimated as offsite. Forms a dense screen. Good form and condition. Full Dense canopy overhanging the site. Has not been topped.	
H9	X Cupressocyparis leylandii (Leyland Cypress)	SM	150	1	7(2)	28	2.5	2.5	2.5	2.5	Good	20+	C2	1.8	10.18	Offsite tree. Plotted by eye as not on topo. Stem data estimated as offsite. Forms a dense screen. Good form and condition. Part of linear group. Unmanaged line of 5 of site trees forming a hedge. Has not been managed.	
T11	X Cupressocyparis leylandii (Leyland Cypress)	EM	450	1	8(2.5)	20	4	4	5.5	2	Fair	20+	C2	5.4	91.62	Poor shape & form. Offsite tree. Stem data estimated as offsite. Forms a dense screen. End of neighbouring hedge which has been topped. Poor crown form with large Dense branch south.	