



Paving / Planting		
Code	Description	Details
P1	Asphalt Road	To match Phase A
P2	Concrete Block Paving	Footpath to match Phase A
P3	Tactile Concrete Pavers	Hazard warning paving to match Phase A
P4	Granite paving within parking bays	100x200x80mm; Mid-grey mix; Strecher bond
P5	Resin bound gravel	Buff colour; Steel edge
P6	Natural stone paving	Natural stone paving; Sizes vary from 600-900mm
P7	Clay paving to paths	215x52x70mm; Clay Paver; Salvia; Strecher bond
P8	Clay paving to private amenity	215x52x70mm; Clay Paver; Graphite; Strecher bond
P9	Clay paving to garden spaces	215x52x70mm; Clay Paver; Salvia; Herringbone bond with double header course
P10	Granite block paving	200x100x100mm; Granite; Silver grey; Flamed; Strecher bond; To match Phase A
P11	Play surfacing	Tiger mulch graded across level changes
P12	Timber Decking	Non-slip timber decking
PL1	Hedge	Yew hedging matching Phase 1
PL2	Defensible planting	Mix to reflect Phase 1 character
PL3	Boardwalk / Park edge planting	Herbaceous and perennial mix
PL4	Ecological biodiverse planting	Mix to reflect Phase 1
PL5	Courtyard planting mix	Herbaceous perennials, sensory plants with evergreen backbone
PL6	Low shrub and herbaceous planting	Hardy shrub dominant mix along road
PL7	Amenity Grass Area	Lawn
PL9	Biodiverse green roof	

Landscape Features		
Code	Description	Details
F1	Feature bench	Blocq by Mmcite; length varies
F2	Right Angled Feature bench	Blocq by Mmcite; length varies
F3	A Frame Timber Bench	Bench integrated into raised timber decking
F4	Outdoor Workstation	Flexible outdoor work/cooking surface
F5	Cycle Stand	Specification to match phase A or Linear Park subject to location
F6	Ev charging point - post	Details to be agreed
F7	Timber bench integrated to wall	Blocq by Mmcite; length varies
F8	Rectangular picnic bench. Fixed	Blocq by Mmcite; ref LBQ962
F9	Deck chair	
F10	Signage	Public realm signage to match Phase A
FL1	Street Lighting Column	4m high lighting column with LUX Levels as appropriate for street lighting
FL2	Lighting Bollard	Low level architectural light
FP1	Bird box	Bird box play/discovery feature
FP2	Slide	Small stainless steel slide built into raised deck
FP3	Play log; tall	Timber round balance log
FP4	Timber 'log' play	Timber 'log' balance beam
FP5	Storytellers Chair	Timber play feature
FP6	Bee Springer	Nature themed springer
FP7	Loose armchair	To be agreed as part of building fit out
FP8	Loose table	To be agreed as part of building fit out
FP9	Double springer	Seesaw springer
FP10	Climbing frame	Timber climbing frame
FP11	Play Panel interactive play feature	Timber play and sensory feature
FP12	Bug hotel play/discovery feature	Recycled material
FP13	River Worm / Glacial boulder	
E1	Granite Kerb	150mm x 300mm x 915mm; Silver grey; Fine picked
E2	Flush Granite Kerb	150mm x 125mm x 915mm; Silver grey granite; Fine picked
E3	Flush Pin Kerb	60mm x 150mm x 915mm; Concrete conservation kerb; Fine picked
R1	Railing to private areas	1800mm high railing; PPL Steel with controlled access gate
R2	Low railings	1000mm high
E4	Steel edging	
W1	332mm wide 450mm high brick wall	
W2	215mm wide 450mm high brick wall	
W3	332mm wide 450mm high parapet brick wall with 1100mm railing	
W4	215mm wide 900mm high brick wall	

P8	20.11.20	DBI	Issued for Planning
P7	18.11.20	DBI	For Information
P6	16.11.20	DBI	For Information
P5	07.05.20	DBI	Updated following basement amendments
P4	22.11.19	AHE	Planning Issue
P3	25.10.19	AHE	Update following design changes
P2	10.10.19	AHE	Updated following comments
P1	13.08.19	AHE	First issue
revision	date	drawn	description

General Arrangement Plan

A726-HTA-C0- PS-A-DR-91001 P8
revision

Berkeley West Thames
Southall Waterside Phase C

BKH-SWE-PHC 1 : 250 @ A1 DBI
job scale drawn
reference 0m 5m 10m 15m 20m 25m

78 Chamber Street London, E1 6BL 020 7485 8655 www.hta.co.uk 99 McDonald Road Edinburgh, EH7 4NS 0131 344 4742 info@hta.co.uk hta