

Internal Door Schedule																				
door	Type	Room Name	Door ID	Height	Width	Acoustic Rating (9dB Rw)	Acoustic Seal	Fire Rating	Smoke Seal	Fire Sign	Glazing	Ironmongery Set Manufacturer (see note)	Ironmongery Set Code	Kickplate	Electronic Access Control	Intruder Detector (Contact Sets)	Manual Locking	Power Assisted (Wheelchair Access)	Phase Created	Comments
L00 FFL	E	Waiting room	ID-00-AUD-01	2070	1010	30	Yes	NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	B	Kitchen	ID-00-AUD-02	2070	1010			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Fitting Room	ID-00-AUD-03	2070	1010	35	Yes	30	Yes	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Fitting Room	ID-00-AUD-04	2070	1010	35	Yes	30	Yes	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Fitting Room	ID-00-AUD-05	2070	1010	35	Yes	30	Yes	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Fitting Room	ID-00-AUD-06	2070	1010	35	Yes	30	Yes	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Electronics Workshop / Laboratory	ID-00-AUD-07	2070	1010	30	Yes	30	Yes	No	No	See Spec	To Be Confirmed	Yes	Yes	No	No	No	New Construction	Card Access
L00 FFL	E	Consulting Room / Hearing Therapy	ID-00-AUD-08	2070	1010	35	Yes	NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	G	Corr	ID-00-AUD-09	2970	1378			30	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	Yes	No	No	Yes	New Construction	Card Access
L00 FFL	I	Corr	ID-00-CA-01	2615	1730			NFR	No	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	A	Office 6p	ID-00-CA-02	2070	1010			NFR	No	No	No	See Spec	To Be Confirmed	No	No	No	Yes	No	New Construction	
L00 FFL	G	Corr	ID-00-CA-03	2700	1480			30	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	K	Store	ID-00-CA-04	1650	865			30	Yes	No	No	See Spec	To Be Confirmed	No	No	No	Yes	No	New Construction	
L00 FFL	C	Corr	ID-00-CA-05	2455	1225			30	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	Yes	No	No	Yes	New Construction	Card Access
L00 FFL	F	Store	ID-00-CA-06	2070	1200			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	I	Corr	ID-00-CIR-01	2070	1730			30	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	H	Corr	ID-00-CIR-02	2070	1500			60	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	No	Yes	New Construction	Card Access
L00 FFL	B	Under Stairs Store	ID-00-CIR-03	2070	910			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Store	ID-00-CIR-04	2070	910			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	D	Corr	ID-00-CIR-05	2070	1410			60	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	Yes	No	No	Yes	New Construction	Card Access
L00 FFL	F	Proposed Plant Room (TBC)	ID-00-CIR-06	2070	1200			60	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	H	Corr	ID-00-CIR-07	2070	1400			NFR	No	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	H	Corr	ID-00-CIR-08	2070	1500			60	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	Yes	No	No	Yes	New Construction	Card Access
L00 FFL	D	Corr	ID-00-EDT-01	2070	1410			30	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	Yes	No	No	Yes	New Construction	Card Access
L00 FFL	B	Male WC	ID-00-EDT-02	2070	910			NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Female WC	ID-00-EDT-03	2070	910			NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Dis. WC	ID-00-EDT-04	2070	1010			NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	H	Corr	ID-00-EDT-05	2070	1400			60	Yes	Yes	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	E	Sim De-brief Seminar Room	ID-00-EDT-06	2070	1010			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Sim Control Room	ID-00-EDT-07	2070	1010	30	Yes	NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	F	Sim Room	ID-00-EDT-08	2070	1200	35	Yes	30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	F	General Training	ID-00-EDT-09	2070	1200	30	Yes	NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	F	Store	ID-00-EDT-10	2070	1200			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	F	Store	ID-00-EDT-11	2070	1200			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Store	ID-00-HAE-01	2070	910			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	Store	ID-00-HAE-02	2070	910			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Office 1p	ID-00-HAE-03	2070	1010			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Phlebotomy Room	ID-00-HAE-04	2070	1010			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	B	WC Ambulent User	ID-00-HAE-05	2070	910			NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	B	Dis. WC	ID-00-HAE-06	2070	1010			NFR	No	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	B	Dirty Utility Room	ID-00-HAE-07	2070	910			30	Yes	No	No	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Clean Utility Room	ID-00-HAE-08	2070	1010			30	Yes	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Staff Rest Room	ID-00-HAE-09	2070	1010			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	
L00 FFL	E	Interview Room	ID-00-HAE-10	2070	1010			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	Yes	New Construction	
L00 FFL	D	Treatment Room (1A/1B)	ID-00-HAE-11	2070	1200			NFR	No	No	Yes	See Spec	To Be Confirmed	Yes	No	No	Yes	No	New Construction	

Notes

- All dimensions to be checked on site

- Do not scale off this drawing

- All dimensions are shown in mm unless otherwise stated

- Refer to drawing issue sheet for purpose of issue

- If in doubt ask

- © Llewelyn Davies Weeks

Key Plan

GENERAL

DRAWINGS TO BE READ IN CONJUNCTION WITH SPECIFICATION & FINISHES/ SCHEDULE OF WORKS/ MATERIALS & WORKMANSHIP/ MEP & STRUCTURAL ENGINEER'S DRAWINGS.

CONTRACTOR TO PROVIDE SAMPLES OF ALL FINISHES AND SPECIFIED COLOURS FOR REVIEW PRIOR TO THE PLACING OF ANY ORDERS

SEE GA FLOOR PLAN SERIES 000120 FOR LOCATION OF DOORS

DIMENSIONS ROUNDED UP OR DOWN TO THE NEAREST WHOLE NUMBER. ALL DIMENSIONS TO BE CONFIRMED ON SITE

LEVELS ARE BASED ON MURPHY GEOSPATIAL SURVEY

NO WORKS TO COMMENCE ON SITE WITHOUT NOTIFICATION TO LONDON BOROUGH OF HILLINGDON AND RECEIVING A WRITTEN APPROVAL

FOR ALL ELECTRICAL INFORMATION REFER TO CPW DRAWING

DOOR MANUFACTURE TO BE CONFIRMED WITH THE TRUST.

IRONMONGERY TO BE CONFIRMED WITH ENGLISH HERITAGE

ALL DOORS CONDITIONS TO BE CHECKED.

ALL GOOD CONDITION DOORS TO BE REPAINTED AND MADE GOOD.

ALL DOORS FIRE RATING TO COMPLY WITH FIRE ENGINEERS STAGE 4 REPORT.

EDUCATION AND TRAINING FIRE RATING AND ACOUSTIC RATING TO BE CONFIRMED.

Project Status

REV	DESCRIPTION	DATE	BY	CHK
P01	For Tender	03/03/21	FM	LD
P02	For Tender	10/09/21	FM	LD
P03	For Tender	28/09/21	FM	LD
P04	For Tender	11/10/21	FM	LD
P05	For Review and Approval	03/12/21	FM	LD
P06	For Planning Amendments	28/03/22	ZAK	LD

Structural Consultant

Services Consultant

CAMPBELL REITH

CPW

Cost Consultant

RIDGE AND PARTNERS

Project Title

HILLINGDON HOSPITAL - THE FURZE

Client

THE HILLINGDON HOSPITAL NHS FOUNDATION TRUST

Drawing Title

DOOR SCHEDULE

Project Number

LD20 192.00

Drawing Number

THHFP1-LDW-ZZ-SH-A-250000

Revision

- P06

Scale @ A1

1 : 100

Date

28/03/22

Architects

LLEWELYN DAVIES

Architects | Planners | Designers

The Rookery | 3rd Floor | 2 Dyott Street | London | WC1A 1DE

T +44(0)20 7907 7900 | E london@ldavies.com

www.ldavies.com