

Ref.	Address 1	Address 2	Address 3	Address 4	Species	Measurements	Description	Survey Notes	Google Maps	Recommendations
T001a	5	Sylvana	Close	F/G	Birch ( <i>Betula</i> sp.)	Height (m): 12 Crown Radius (m): 4 DBH (cm): 30 Life Stage: Mature	Located in the central area of the front garden 3 from the driveway. High surface roots within the lawn. Crown breaks at approximately 0.5m from ground level with co-dominant stem. Lower Crown in contact with BT cables. Large sail effect of the upper crown.  Owned by the estate. Target # - building	Front garden	51.5443897,-0.4611894	Reduction of height by approximately 3m and lateral width by approximately 1-1.5m. Prune to clear BT cables. Timescale: 19-Mar-2024 (1 Month)
T001c	10	Sylvana	Close	R/O	Oak ( <i>Quercus</i> sp.)	Height (m): 15 Crown Radius (m): 7 DBH (cm): 50 Life Stage: Mature	Located rear of the rear boundary. Unable to fully view due to no access. Deadwood throughout the crown with major deadwood over the garden. Upper crown extends over the rear garden towards the rear elevation of the building.  Owned by the estate.	Rear of rear garden	51.5440648,-0.4607246	Reduce lateral growth towards the rear elevation of the building by up to approximately 2m of the branch length. Remove major deadwood over the garden.  Timescale: 19-Mar-2024 (1 Month)

G3b	23	Sylvana	Close	R/G	Sycamore ( <i>Acer pseudoplatanus</i> )	Height (m): 8 Crown Radius (m): 3 DBH (cm): 15 Stems: 2 Life Stage: Young	Young Sycamore Trees Located in the rear and front garden to the left hand side adjacent to the side elevation of 24. Base of stems in contact with the building of 24. Previously self set and Bern allowed to grow.	Garden	51.5436792,-0.4591238	Fell to ground level and apply eco pellets Timescale: 19-Mar-2024 (1 Month)
T003c	23	Sylvana	Close	R/G	Hawthorn ( <i>Crataegus</i> sp.)	Height (m): 8 Crown Radius (m): 3 DBH (cm): 45 Life Stage: Over Mature	Located rear of the rear boundary to the left hand side within an overgrown area of the park. Unable to fully view due to the location and the understory growth. Excessive lean over the boundary fence and in conflict with the boundary fence. Old broken hungup dead ivy. In contact with a Laurel to the left hand side of the garden.  Owned by the estate	R/O rear garden	51.5435987,-0.4589933	Fell to ground level Timescale: 19-Mar-2024 (1 Month)

T002b	24	Sylvana	Close	F/G	Sorbus ( <i>Sorbus</i> <i>sp.</i> )	<p>Height (m): 6 Crown Radius (m): 3.5 DBH (cm): 35 Life Stage: Mature</p> <p>Located in the front garden 4m from the front elevation of the building. Crown breaks at approximately 2m from ground level. Delamination at the top section of the dominant central stem around and above union. Multiple fungus brackets of secondary branch of the Delamination stem. BT cable runs through the crown. Encroachment to BT cables of 25 and 23.</p> <p>Owned by the estate. Target # - building</p>	Front garden	51.543771,-0.4592362	<p>Reduce central stem to suitable source. Crown reduction of the remaining Crown by up to approximately 1.5-1.8m of the branch length. Prune to clear BT cables.</p> <p>Timescale: 19-Mar-2024 (1 Month)</p>
-------	----	---------	-------	-----	---	---	--------------	----------------------	---