

Wardale® Cycle Shelter

BXMW/WAR



The Wardale® cycle shelter is our best selling and most versatile shelter. With its modular design the Wardale cycle shelter can be linked together to create banks of shelters which allow to you accommodate almost any quantity of cycles.

The Wardale can also be fitted with [Swinging](#) or [Sliding gates](#) with a range of locking mechanisms available to create a fully lockable and secure shelter.

The versatility of the cycle shelter means that the shelter can be retro-fitted with extensions at a later date pushing the parking capacity upwards whilst keeping installation costs low. The shelter can also be transformed into a [secure compound](#).

Polycarbonate End Panels Included in Price

From

£1,010.00 ex-vat.

* Size Selectable

Choose an Option... ▼

Qty: 1

Add to Basket

or

Add to Quote

 Online price enquiry

 Download spec sheet

Description

Capacity:

- 10 Cycles

Standard Unit Dimensions:

- Length: 4100mm
- Width: 2140mm
- Height: 2150mm

Capacities

- 2000mm - 4 Cycles
- 3600mm - 8 Cycles
- 4100mm - 10 Cycles
- 5000mm - 12 Cycles
- 6000mm - 14 Cycles

Features:

- **Polycarbonate End Panels Included**
- Robust modular construction featuring load bearing purlins
- Welded end frames and purlin section made from heavy-duty box section assembled with anti-tamper high strength bolts
- Anti-climb end frames
- Adjustable baseplates
- Bottom purlin provides anti-crawl bar on level surface
- Hot dipped galvanized to BS EN ISO 1461:2009
- 4mm Clear View PETg UV Roof and Side Cladding (5mm also available)

- Breeam Compliant Configurations

Options:

- HPS Colourcoat steel profile cladding
- Opal Cladding to Roof and Sides
- Extended adjustable baseplates for submerged fixing
- [Swinging Security Gates](#)
- [Sliding Security Gates](#)
- [Mechanical or Keyed Locks](#)
- Further anti crawl bars can be fitted dependent on surface level
- [Helmet Lockers](#)
- Powder Coating to a wide range of colours
- [LED or solar lighting](#)
- Full Installation Service
- Varied Range of [Cycle Racks](#)
- Varied Range of [Cycle Stands](#)

Fixings:

- Root Fixed
- Baseplate Fixed

Finishes Available:

- Galvanised to BS EN ISO 1461:2009
- Galvanised to BS EN ISO 1461:2009 & Polyester Power Coated

Case Studies



Colours



Delivery



Request Drawing



Also Consider



BXMW/AV-WAR-SHELTER



BXMW/AV-WAR-COMPOUND



BXMW/WAR/COM