



Saxon

Textured Concrete Paving

- The Yorkstone aggregate and unique, consistent textured surface ensures superb durability and non-slip properties.
- Available in 6 colours to suit both traditional and contemporary projects.
- A popular cost-effective alternative to natural Yorkstone.
- An extensive choice of size and thickness including Marshalls Trafica format and units incorporating Marshalls patented Fibre Reinforcement.
- Suitable for all landscape environments to suit variable trafficking requirements.
- Product compliant to BS EN 1339: 2003.
- Saxon Kerb is also available to enhance the final project.
- Innovative concrete technology allows paving on a grand scale, new 1m² paving units complement Saxon and capitalise on the trend for larger plan sizes.

Colours

Precise colour and surface texture should be judged from actual materials rather than photographic representations.



	Thickness (mm)	Plan Size (mm)	Pack Size (m ² approx)	Edge	BS Size	Unit Weight (kg approx)	Pack Weight (kg approx)	Natural [†] (Ref No.)	Brown (Ref No.)	Buff (Ref No.)	Charcoal (Ref No.)	Marigold (Ref No.)	Red (Ref No.)
	50	400 x 400	6.4	Rounded	F50	18.2	728	FL5060500	FL5061750	FL5061000	FL5062500		
	50	450 x 300	5.4	Rounded		15.3	612	FL5010500	FL5011750		FL5012500		
	50	450 x 450	8.1	Rounded	E50	22	916	FL5030500	FL5031750	FL5031000	FL5032500		
	50	450 x 600	5.4	Rounded	A50	30	612	FL4900500	FL4911750	FL4911000			
	50	600 x 600	7.2	Rounded	B50	43	872	FL4950600	FL4951750	FL4951100	FL4952500		FL4951600
	50	900 x 300	5.4	Rounded		32	640	FL4970500		FL4971000	FL4972500		
	50	900 x 600	10.8	Rounded	D50	64.6	1292	FL4950500		FL4951000			
Trafica	60	300 x 300	3.4	Rounded	G60	12.8	486	FL5100500		FL5100520			
	63	450 x 600	4.3	Rounded	A63	39.6	634	FL5130650		FL5131150			
	63	600 x 600	5.8	Rounded	B63	53.4	854	FL5130600		FL5131100	FL5132600		
	63	900 x 600	8.6	Rounded	D63	77.6	1242	FL5130500		FL5131000			
Trafica	65	400 x 400	4.8	Rounded	F65	24.7	741	FL5160500		FL5161000	FL5162500		FL5161500
Trafica	70	450 x 450	5.7	Rounded	E70	31	888	FL5180500	FL5181750	FL5181000	FL5182500	FL5182000	FL5181500
NEW	70	1000 x 1000	6	Rounded		165	990			FL517520			
NEW	70	1000 x 500	6	Rounded		82.5	990			FL517620			
Trafica	100	450 x 450	4	Rounded	E100	45.9	918	FL5200500					
Step Tread	50	400 x 400**	40 No.	Rounded	F50	18.2		FL9630650		FL9630700			
Step Tread		450 x 450**	40 No.	Rounded	E50	23		FL9630350		FL9630400			

Saxon with reference numbers indicated in bold black are available ex-stock.

Saxon with reference numbers indicated in light black are manufactured to order, contact our sales office to discuss your requirements.

**Units are supplied with a 55mm wide non-slip black strip as standard however other colours of strip are available. Risers are also manufactured to suit. Please contact our sales office for further details.

[†]Natural products are manufactured from aggregates sourced locally to the works and contain no pigmentation, therefore colour variation between products from different works is possible.

◀ Buff Saxon, Leeds Valley Business Park, West Yorkshire