


Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m) 	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Retention Category
T1	Semi-Mature Cherry Laurel Prunus laurocerasus.	6	1	34	4 3 4 4	25  0	Position: Boundary tree. Form: Multi-stemmed at ground level with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Recorded stem diameter is equivalent for 5 stems (15cm each).	No action required.		Moderate Good Good	Moderate 40+ C
								n/a	3		
T2	Semi-Mature Holly Ilex aquifolium.	5	2.5	24	3 3 3 3	25  0	Position: Boundary tree. Form: Multi-stemmed at ground level with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Recorded stem diameter is equivalent for 6 stems (10cm each).	No action required.		Moderate Good Good	Moderate 40+ C
								n/a	3		
T3	Early-Mature Lime Tilia sp.	7	2	62	1.5 1.5 1.5 1.5	25  0	Position: Street tree. Form: Multi-stemmed at 4.5m with a balanced crown. History: Heavily reduced. Defects: No significant defects observed.	No action required.		Moderate Good Good	High 20-40 B
								n/a	3		
T4	Mature Silver Birch Betula pendula.	12	2	35	4.5 5 5.5 5	25  0	Form: Single stemmed and vertical with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 20-40 C
								n/a	3		
T5	Semi-Mature Holly Ilex aquifolium.	7	1	14	2.5 2.5 2.5 2.5	25  0	Form: Single stemmed with a slight lean and a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		High Good Good	Low 40+ C
								n/a	3		
T6	Early-Mature Japanese Maple Acer japonicum.	4	1	17 @ Base	3 3 1.5 3	25  0	Form: Twin-stemmed at 1m with a slightly unbalanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 20-40 C
								n/a	3		
T7	Semi-Mature Cherry Prunus sp.	10	3	18	2 1.5 1.5 3	25  0	Form: Single stemmed with a slight lean and a slightly unbalanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 20-40 C
								n/a	3		

Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
								Priority	Inspect Freq (yrs)	Physiological Condition	Life Expectancy (yrs)
										Structural Condition	Retention Category
T8	Mature Apple Malus sp.	5.5	3	46	4 4 4 6		Form: Twin-stemmed at 3m with a slightly unbalanced crown. History: Multiple pruning wounds due to crown reduction. Defects: No significant defects observed.	No action required.	Moderate Good Fair	Low 10-20 C	
							n/a	3			
T9	Young Bay Laurel Laurus nobilis.	4	0.5	14	2 2 2 3 3.5		Form: Multi-stemmed at ground level with a slightly unbalanced crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Recorded stem diameter is equivalent for 3 stems (8cm each).	No action required.	High Good Good	Low 40+ C	
							n/a	3			
T10	Early-Mature Fig Ficus carica.	3.5	0	18	3 3 3.5 3 4		Form: Twin-stemmed at ground level with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Recorded stem diameter is equivalent for 2 stems (12cm, 14cm).	No action required.	Moderate Good Good	Low 20-40 C	
							n/a	3			
T11	Mature Copper Beech Fagus sylvatica 'purpurea'.	12	3	70	5.5 5.5 5.5 5.5		Position: Situated on third party land. Form: Multi-stemmed at 3m with a balanced crown. History: Multiple pruning wounds due to crown reduction. Defects: No significant defects observed. Other: Limited inspection, dimensions estimated.	No action required.	Moderate Good Good	High 40+ A	
							n/a	3			